



# NORTHWEST WISCONSIN FLOOD IMPACT STUDY



# Northwest Wisconsin Flood Impact Study

HAZUS-MH Level 2 Analysis



November, 2018

This report was prepared by Northwest Regional Planning Commission using Federal funds under award number 06-69-06049 from the Economic Development Administration, Department of Commerce. The statements, findings, conclusions, and recommendations are those of the author and do not necessarily reflect the views of the Economic Development Administration or the U.S. Department of Commerce.

Additional funds to support this project came from the Wisconsin Economic Development Corporation (WEDC) and Northwest Regional Planning Commission (NWRPC).





# Table of Contents

<b>2016 NORTHWEST WISCONSIN FLOOD</b>	<b>1</b>
<b>REGIONAL FLOOD STUDY OVERVIEW</b>	<b>8</b>
HAZUS-MH	9
STUDY REGION	10
<b>HAZUS-MH FLOOD MODEL</b>	<b>11</b>
USER-DEFINED FACILITIES (UDF)	13
Digitization Process Model	15
USER-DEFINED FACILITY ATTRIBUTES	16
Required HAZUS-MH Attributes	16
Replacement Cost	16
Content Cost	16
Number of Stories	16
Foundation Type	16
First Floor Height	17
Area	17
User Defined Facility ID	17
Occupancy Class	17
OCCUPANCY CLASS	18
VULNERABLE AND CRITICAL FACILITIES	19
CRITICAL INFRASTRUCTURE	21
<b>TERRAIN SURFACE MODEL</b>	<b>23</b>
HYDRO-FLATTENING	24
MOOSAICING	24
TERRAIN HYDROPROCESSING (PRE-PROCESSING)	25
PLACING CUTLINES	29
<b>TERRAIN PROCCESING (HAZUS-MH)</b>	<b>32</b>
<b>HYDROLOGIC ANALYSIS</b>	<b>35</b>
HYDRAULIC ANALYSIS	35
FLOOD DEPTH GRIDS	40
DEPTH GRID ANOMALIES	41
DEPTH GRID MOSAIC PROCESS	42
<b>LOSS ESTIMATION</b>	<b>43</b>
DAMAGE-DEPTH FUNCTIONS	44
<b>RESULTS SUMMARY</b>	<b>45</b>
STRUCTURES IMPACTED	47
ESTIMATED BUILDING LOSSES	47
ESTIMATED CONTENT LOSSES	48
ESTIMATED INVENTORY LOSSES	48
DEBRIS GENERATION	49
<b>BUILDING AND LOSS ESTIMATES</b>	<b>65</b>
ASHLAND COUNTY	66
BAYFIELD COUNTY	85

BURNETT COUNTY .....	112
DOUGLAS COUNTY .....	133
IRON COUNTY.....	161
SAWYER COUNTY .....	177
WASHBURN COUNTY .....	203
<b>MITIGATION MECHANISMS .....</b>	<b>221</b>
ECONOMIC IMPACT ON RURAL COMMUNITIES.....	221
RURAL ECONOMIES .....	221
RESPONDING TO RISKS.....	222
ADAPTATION .....	224
LOCAL RESPONSES TO FLOODING IN NORTHERN WI.....	225
<b>MITIGATION MEASURES FOR CRITICAL FACILITIES AND INFRASTRUCTURE .....</b>	<b>227</b>
WASTEWATER TREATMENT FACILITIES (WWTF's) .....	227
MUNICIPAL WELLHEADS (HIGH CAPACITY WELLS).....	227
ELECTRICAL SUBSTATIONS.....	227
PIPELINES, PIPELINE PUMP STATIONS, & PIPELINE MAINTENANCE STATIONS .....	227
LOCAL GOVERNMENT.....	228
EDUCATIONAL INSTITUTIONS .....	228
FIRE AND EMS, HOSPITALS & LAW ENFORCEMENT .....	228
HAZARDOUS MATERIALS SITES .....	228
DAMS/LEVEES.....	228
CRITICAL FACILITIES AND INFRASTRUCTURE FLOOD ASSESSMENT .....	229
MODELED IMPACTS TO LOCAL ROADWAYS.....	233
<b>STRATEGIES FOR PREPARING FOR RESILIENCY .....</b>	<b>235</b>
FEDERAL PROGRAMS THAT CAN PROVIDE ASSISTANCE PRIOR TO A FLOOD .....	235
FEMA MITIGATION GRANT PROGRAMS .....	236
INTERIOR MODIFICATION/ RETROFIT MEASURES.....	239
Basement Infill.....	239
Abandon Lowest Floor .....	239
Elevate Lowest Interior Floor.....	239
WET FLOODPROOFING MEASURES.....	240
Flood Openings .....	240
Elevate building Utilities.....	241
Floodproof Building Utilities.....	242
Flood Damage-Resistant Materials.....	242
DRY FLOODPROOFING MEASURES.....	243
Passive Dry Floodproofing System.....	243
BARRIER MEASURES.....	243
Floodwall with Gates and Floodwall without Gates .....	243
Levee with Gates and Levee without Gates .....	244
CASE STUDY OF FLOOD MITIGATION TECHNIQUES – DARLINGTON, WI .....	245
FLOOD RECOVERY PROGRAMS .....	248
Federal Emergency Management Agency (FEMA) Public Assistance (PA).....	248
Mitigation Funding Provided through Section 406 of the Stafford Act .....	249
Federal Emergency Management Agency (FEMA) Individual Assistance.....	249
Wisconsin Disaster Fund (WDF) .....	251
EXTERNAL COUNTY & TRIBAL EMERGENCY MANAGEMENT DIRECTOR LIST .....	253
PRESIDENTIAL DISASTER DECLARATIONS.....	254
Emergency Declarations .....	254

MAJOR DISASTER DECLARATIONS .....	254
NATIONAL FLOOD INSURANCE PROGRAM (NFIP) .....	255
REGULATORY TECHNIQUES .....	256
LAND USE PLANNING .....	256
HAZARD MITIGATION PLANNING .....	256
<b>PLANNING FOR FLOOD RESILIENCE .....</b>	<b>257</b>
Why Plan? .....	257
COUNTYWIDE HAZARD MITIGATION PLANS .....	257
COMPREHENSIVE PLANNING .....	258
FLOODPLAIN PROTECTION .....	259
EMERGENCY ACTION PLAN .....	260
RECOVERY PLANNING – BUILD BACK SAFER AND STRONGER .....	260
Resources for flood recovery and recovery planning .....	262
OTHER LOCAL PLANS AND PROGRAMS .....	262
COMMUNITY RATING SYSTEM .....	262
ZONING .....	263
WATERBODIES AND BUFFERS .....	263
Runoff Management .....	264
PUBLIC ROADS .....	265
<b>CULVERT ASSET MANAGEMENT .....</b>	<b>267</b>
ROAD AND CULVERT PROBLEMS ASSOCIATED WITH FLOOD WATERS .....	268
Plunge pools, stream bank scour, & sediment deposits .....	268
DEBRIS ACCUMULATION .....	269
Perched outlet .....	269
ROAD OVERTOPPING .....	270
CULVERT FAILURE CASE STUDIES .....	271
CREATING A CULVERT INVENTORY .....	273
EXAMPLE INVENTORY FORM .....	274
PHOTOGRAPH LOG PAGE .....	275
CURRENTLY EXISTING CULVERT DATA FOR NORTHWEST WISCONSIN .....	275
LIMITATIONS OF FINDING “DAMAGED LOCATIONS” .....	276
CULVERT SIZING PROCEDURES FOR 1% (100 YEAR FLOOD) PEAK FLOW .....	277
<b>MITIGATION TECHNIQUES FOR CULVERTS AND ROADS .....</b>	<b>280</b>
RETAINING WALLS .....	280
SLOPE ROUNDING AND REVEGETATION .....	281
REVEGETATION .....	281
SOIL BIOENGINEERING .....	282
INVASIVE SPECIES .....	284
BIOTECHNICAL STABILIZATION .....	285
ROADWAY DIPS .....	285
LOW WATER CROSSINGS, OVERTOPPING, AND FORDS .....	286
PERMEABLE FILL WITH CULVERT ARRAY .....	287
RAISED CULVERT INLETS .....	288
ENERGY DISSIPATERS AND DEBRIS RACKS .....	289
STREAM CHANNEL MODIFICATION STRUCTURES .....	289
RECONNECTING CUTOFF WATER BODIES .....	290
ENGINEERED LOG JAM COMPLEXES .....	291
BEAVER POND STRUCTURES .....	292
WETLAND MAINTENANCE .....	292



## **FLOOD PREVENTION TECHNIQUES FOR WATER AND WASTEWATER UTILITIES .....294**

MITIGATION OPTIONS FOR WASTEWATER TREATMENT PLANTS.....	298
MITIGATION MEASURES FOR DRINKING WATER ASSETS .....	299
MITIGATION OPTIONS FOR GROUNDWATER UTILITIES .....	300
MITIGATION OPTIONS FOR BOOSTER STATIONS AND OTHER PUMPS .....	300
MITIGATION OPTIONS FOR DRINKING WATER TREATMENT PLANTS.....	301
MITIGATION OPTIONS FOR CHEMICAL AND OTHER STORAGE.....	302
MITIGATION OPTIONS FOR INSTRUMENTATION AND ELECTRICAL CONTROLS .....	302
MITIGATION OPTIONS FOR POWER SUPPLY .....	303
MITIGATION OPTIONS FOR COLLECTION SYSTEM LIFT STATIONS .....	304
MITIGATION OPTIONS FOR HEADWORKS .....	305

## **TABLES**

Table 1: 2016 Northwest Wisconsin Flood, Damage to homes/businesses.....	3
Table 2: 2016 Northwest Wisconsin Flood, Damage to Public Infrastructure.....	3
Table 3: 2016 CDBG, Emergency Assistance Program Grants .....	3
Table 4: Occupancy Class .....	18
Table 5: ESTIMATED LOSSES BY COUNTY, 100-YR FLOOD EVENT .....	45
Table 6: ESTIMATED LOSSES BY COUNTY, 500-YR FLOOD EVENT.....	45
Table 7: ESTIMATED LOSSES BY OCCUPANCY CLASS, 100-YR FLOOD EVENT .....	46
Table 8: ESTIMATED LOSSES BY OCCUPANCY CLASS, 500-YR FLOOD EVENT .....	47
Table 9: ESTIMATED CONTENT LOSSES .....	48
Table 10: ESTIMATED INVENTORY LOSSES .....	49
Table 11: HAZUS FLOOD LOSS ESTIMATES – ASHLAND COUNTY .....	66
Table 12: HAZUS FLOOD LOSS ESTIMATES – BAYFIELD COUNTY .....	85
Table 13: HAZUS FLOOD LOSS ESTIMATES – BURNETT COUNTY .....	112
Table 14: HAZUS FLOOD LOSS ESTIMATES – DOUGLAS COUNTY .....	133
Table 15: HAZUS FLOOD LOSS ESTIMATES – IRON COUNTY .....	161
Table 16: HAZUS FLOOD LOSS ESTIMATES – SAWYER COUNTY.....	177
Table 17: HAZUS FLOOD LOSS ESTIMATES – WASHBURN COUNTY .....	203
Table 18: COUNTY SALES TAX DISTRIBUTION (THOUSANDS \$)– REGION .....	226
Table 19: CRITICAL FACILITIES/INFRASTRUCTURE/HAZARDOUS MATERIALS STORAGE SITE IMPACTS: 100-YEAR FLOOD LOSSES - REGION .....	232
Table 20: CRITICAL FACILITIES/INFRASTRUCTURE/HAZARDOUS MATERIALS STORAGE SITE IMPACTS: 500-YEAR FLOOD LOSSES - REGION .....	233
Table 21: Regionwide Potential Roadway Impacts, 100-year Flood Scenario (miles).....	233
Table 22: Regionwide Potential Roadway Impacts, 500-year Flood Scenario (miles).....	233
Table 23: NFIP PARTICIPATION, REGION.....	255
Table 24: POTENTIAL CULVERT DATA SOURCES, REGION .....	276

## **FIGURES**

Figure 1: 2016 FLOOD HYDROGRAPH .....	2
Figure 2: 2016 FLOOD DAMAGE (PUBLIC ASSISTANCE PROGRAM SUBAWARDS) .....	4
Figure 3: 2016 FLOOD IMPACTS, TRANSPORTATION SYSTEM.....	5
Figure 4: HAZUS MODEL FLOW DIAGRAM.....	12
Figure 5: USER-DEFINED STRUCTURES (DIGITIZED BUILDING FOOTPRINTS) .....	14
Figure 6: VULNERABLE FACILITIES.....	20
Figure 7: CRITICAL INFRASTRUCTURE.....	22
Figure 8: FAILED REACHES (HAZUS RIVERINE HYDRAULICS) .....	37

Figure 9: USGS STREAMGAGES .....	38
Figure 10: HAZUS DERIVED FLOOD BOUNDARY .....	39
Figure 11: DAMAGE DEPTH CURVES, RESIDENTIAL I OCCUPANCY CLASS .....	44
Figure 12: ESTIMATED STRUCTURE IMPACTED (100 YEAR EVENT) .....	50
Figure 13: ESTIMATED STRUCTURES IMPACTED (500 YEAR EVENT) .....	51
Figure 14: ESTIMATED BUILDING LOSSES (100 YEAR EVENT) .....	52
Figure 15: ESTIMATED BUILDING LOSSES (500 YEAR EVENT) .....	53
Figure 16: ESTIMATED CONTENT LOSSES (100 YEAR EVENT) .....	54
Figure 17: ESTIMATED CONTENT LOSSES (500 YEAR EVENT) .....	55
Figure 18: ESTIMATED DEBRIS GENERATION (100 YEAR EVENT) .....	56
Figure 19: ESTIMATED DEBRIS GENERATION (500 YEAR EVENT) .....	57
Figure 20: FLOOD DEPTH GRID, DOUGLAS COUNTY .....	58
Figure 21: FLOOD DEPTH GRID, BAYFIELD COUNTY .....	59
Figure 22: FLOOD DEPTH GRID, ASHLAND COUNTY .....	60
Figure 23: FLOOD DEPTH GRD, IRON COUNTY .....	61
Figure 24: FLOOD DEPTH GRID, BURNETT COUNTY .....	62
Figure 25: FLOOD DEPTH GRID, WASHBURN COUNTY .....	63
Figure 26: FLOOD DEPTH GRID, SAWYER COUNTY .....	64

## MAPS

T47 & 48N, R4W (C. ASHLAND, T. GINGLES, T. SANBORN) .....	67
T47 & 48N, R3W (T. GINGLES, T. SANBORN) .....	68
T47 & 48N, R2W (T. SANBORN) .....	69
T45 & 46N, R4W (T. WHITE RIVER, T. MARENGO) .....	70
T45 & 46N, R3W (T. SANBORN, T. WHITE RIVER, T. ASHLAND) .....	71
T45 & 46N, R2W (C. MELLEN, T. SANBORN, T. MORSE) .....	72
T43 & 44N, R4W (T. MARENGO, T. GORDON) .....	73
T43 & 44N, R3W (T. MORSE, T. GORDON) .....	74
T43 & 44N, R2W (C. MELLEN, T. MORSE, T. GORDON) .....	75
T43N, R1W (T. JACOBS) .....	76
T41 & 42N, R4W (T. SHANAGOLDEN, T. CHIPPEWA) .....	77
T41 & 42N, R3W (T. SHANAGOLDEN, T. CHIPPEWA) .....	78
T41 & 42N, R2W (T. SHANAGOLDEN, T. JACOBS, T. PEEKSVILLE, T. CHIPPEWA) .....	79
T41 & 42N, R1W (V. BUTTERNUT, T. JACOBS, T. PEEKSVILLE, T. CHIPPEWA, T. AGENDA) .....	80
T41 & 42N, R1E (T. AGENDA) .....	81
CITY OF ASHLAND .....	82
VILLAGE OF BUTTERNUT .....	83
CITY OF MELLEN .....	84
T51 & 52N, R3, 4, & 5W (T. BAYFIELD, T. RUSSELL) .....	87
T49 & 50N, R9W (T. ORIENTA) .....	88
T49 & 50N, R8W (T. PORT WING, T. ORIENTA) .....	89
T49 & 50N, R7W (T. PORT WING, T. CLOVER) .....	90
T49, 50 & 51N, R6W (T. BELL, T. WASHBURN) .....	91
T49 50 & 51N, R5W (T. BAYFIELD, T. BAYVIEW, T. WASHBURN) .....	92
T48, 49 & 50N, R4W (C. BAYFIELD, C. WASHBURN, T. BAYVIEW, T. BAYFIELD, T. BARKSDALE) .....	93
T47 & 48N, R9W (T. OULU, T. HUGHES) .....	94
T47 & 48N, R8W (T. TRIPP, T. IRON RIVER, T. KEYSTONE) .....	95
T47 & 48N, R7W (T. WASHBURN, T. BARKSDALE, T. PILSEN, T. KEYSTONE) .....	96
T47 & 48N, R6W (T. WASHBURN, T. BARKSDALE, T. PILSEN, T. KEYSTONE) .....	97
T47 & 48N, R5W (T. WASHBURN, T. BARKSDALE, T. EILEEN) .....	98
T45 & 46N, R9W (T. HUGHES, T. BARNES) .....	99

T45 & 46N, R8W (T. DELTA, T. DRUMMOND) .....	100
T45 & 46N, R7W (T. DELTA, T. DRUMMOND) .....	101
T45 & 46N, R6W (V. MASON, T. MASON, T. GRANDVIEW) .....	102
T45 & 46N, R5W (T. KELLY, T. LINCOLN) .....	103
T43 & 44N, R9W (T. BARNES) .....	104
T43 & 44N, R8W (T. DRUMMOND, T. CABLE) .....	105
T43 & 44N, R7W (T. DRUMMOND, T. CABLE) .....	106
T43 & 44N, R6W (T. GRANDVIEW, T. NAMAKAGON) .....	107
T43 & 44N, R5W (T. GRANDVIEW, T. NAMAKAGON, T. MARENGO) .....	108
CITY OF BAYFIELD .....	109
VILLAGE OF MASON .....	110
CITY OF WASHBURN .....	111
T41 & 42N, R16 & 17W (T. SWISS, T. BLAINE) .....	114
T41 & 42N, R15W (T. BLAINE, T. SWISS) .....	115
T41 & 42N, R14W (T. BLAINE, T. WEBB LAKE) .....	116
T39 & 40N, R19W (T. WEST MARSHLAND) .....	117
T39 & 40N, R18W (T. WEST MARSHLAND, T. UNION) .....	118
T39 & 40N, R17W (T. LINCOLN, T. UNION) .....	119
T39 & 40N, R16W (V. WEBSTER, T. OAKLAND, T. MEENON) .....	120
T39 & 40N, R15W (T. JACKSON, T. SAND LAKE) .....	121
T39 & 40N, R14W (T. SCOTT, T. RUSK) .....	122
T37 & 38N, R20W (T. GRANTSBURG, T. ANDERSON) .....	123
T37 & 38N, R19W (V. GRANTSBURG, T. GRANTSBURG, T. ANDERSON) .....	124
T37 & 38N, R18W (T. WOOD RIVER, T. TRADE LAKE) .....	125
T38N, R17W (T. DANIELS) .....	126
T38N, R16W (V. SIREN, T. SIREN) .....	127
T38N, R15W (T. LA FOLLETTE) .....	128
T37 & 38N, R14W (T. DEWEY, T. ROOSEVELT) .....	129
VILLAGE OF GRANTSBURG .....	130
VILLAGE OF SIREN .....	131
VILLAGE OF WEBSTER .....	132
T49N, R13, 14, & 15W (C. SUPERIOR) .....	135
T49N, R10 & 11W (T. LAKESIDE, T. CLOVERLAND) .....	136
T47 & 48N, R15W (T. SUPERIOR, V. OLIVER) .....	137
T47 & 48N, R14W (C. SUPERIOR, T. SUPERIOR, V. OLIVER, V. SUPERIOR) .....	138
T47 & 48N, R13W (C. SUPERIOR, T. PARKLAND, T. OAKLAND) .....	139
T47 & 48N, R12W (T. LAKESIDE, T. AMNICON, T. HAWTHORNE, V. POPLAR) .....	140
T47 & 48N, R11W (T. LAKESIDE, T. CLOVERLAND, T. MAPLE, T. HAWTHORNE, T. AMNICON, V. LAKE NEBAGAMON, V. POPLAR) .....	141
T47 & 48N, R10W (T. CLOVERLAND, T. MAPLE, T. BRULE, V. LAKE NEBAGAMON) .....	142
T45 & 46N, R15W (T. SUMMIT) .....	143
T45 & 46N, R14W (T. SUMMIT) .....	144
T45 & 46N, R13W (T. OAKLAND, T. GORDON, T. BENNETT, T. SOLON SPRINGS) .....	145
T45 & 46N, R12W (T. HAWTHORNE, T. BENNETT, T. SOLON SPRINGS, V. SOLON SPRINGS) .....	146
T45 & 46N, R11W (T. HAWTHORNE, T. BENNETT, T. HIGHLAND, T. SOLON SPRINGS, V. LAKE NEBAGAMON) .....	147
T45 & 46N, R10W (T. HIGHLAND) .....	148
T43 & 44N, R15W (T. DAIRYLAND) .....	149
T43 & 44N, R14W (T. DAIRYLAND) .....	150
T43 & 44N, R13W (T. GORDON, T. WASCOTT) .....	151
T43 & 44N, R12W (T. SOLON SPRINGS, T. GORDON, T. WASCOTT) .....	152
T43 & 44N, R11W (T. GORDON, T. WASCOTT) .....	153
T43 & 44N, R10W (T. GORDON, T. WASCOTT) .....	154
VILLAGE OF LAKE NEBAGAMON .....	155




VILLAGE OF OLIVER.....	156
VILLAGE OF POPLAR .....	157
VILLAGE OF SOLON SPRINGS .....	158
CITY OF SUPERIOR .....	159
VILLAGE OF SUPERIOR.....	160
T47 & 48N, R1E & 1W (T. GURNEY, T. SAXON, T. KIMBALL).....	162
T45 & 46N, R1W (T. GURNEY, T. SAXON, T. ANDERSON).....	163
T45 & 46N, R1E (T. SAXON, T. KIMBALL, T. ANDERSON, T. KNIGHT).....	164
T45, 46 & 47N, R2E (C. HURLEY, C. MONTREAL, T. KIMBALL, T. PENCE, T. CAREY).....	165
T45 & 46N, R3E (T. OMA) .....	166
T44N, R1W (T. ANDERSON) .....	167
T43 & 44N, R1E (T. KNIGHT).....	168
T43 & 44N, R2E (T. PENCE, T. CAREY, T. MERCER) .....	169
T43 & 44N, R3E (T. OMA, T. MERCER).....	170
T43 & 44N, R4E (T. OMA, T. MERCER).....	171
T41 & 42N, R2E (T. MERCER, T. SHERMAN).....	172
T41 & 42N, R3E (T. MERCER, T. SHERMAN).....	173
T41 & 42N, R4E (T. MERCER, T. SHERMAN).....	174
CITY OF HURLEY.....	175
CITY OF MONTREAL.....	176
T41 & 42N, R9W (C. HAYWARD, T. LENROOT, T. HAYWARD).....	179
T41 & 42N, R8W (T. LENROOT, T. ROUND LAKE, T. HAYWARD).....	180
T41 & 42N, R7W (T. SPIDER LAKE, T. ROUND LAKE).....	181
T41 & 42N, R6W (T. SPIDER LAKE, T. ROUND LAKE) .....	182
T41 & 42N, R5W (T. SPIDER LAKE, T. ROUND LAKE) .....	183
T39 & 40N, R9W (T. BASS LAKE, T. SAND LAKE).....	184
T39 & 40N, R8W (T. BASS LAKE, T. HAYWARD, T. SAND LAKE, T. COUDERAY).....	185
T39 & 40N, R7W (T. HUNTER, T. COUDERAY, T. RADISSON) .....	186
T39 & 40N, R6W (T. HUNTER, T. OJIBWA).....	187
T39 & 40N, R5W (T. WINTER, V. WINTER).....	188
T39 & 40N, R4W (T. DRAPER).....	189
T39 & 40N, R3W (T. DRAPER) .....	190
T37 & 38N, R9W (T. SAND LAKE, T. EDGEWATER).....	191
T37 & 38N, R8W (T. COUDERAY, T. METEOR, V. COUDERAY) .....	192
T37 & 38N, R7W (T. COUDERAY, T. RADISSON, T. WEIRGOR, V. COUDERAY, V. EXELAND, V. RADISSON).....	193
T37 & 38N, R6W (T. OJIBWA, T. RADISSON, T. MEADOWBROOK).....	194
T37 & 38N, R5W (T. WINTER) .....	195
T37 & 38N, R4W (T. WINTER) .....	196
T37 & 38N, R3W (T. WINTER) .....	197
VILLAGE OF COUDERAY.....	198
VILLAGE OF EXELAND.....	199
CITY OF HAYWARD.....	200
VILLAGE OF RADISSON.....	201
VILLAGE OF WINTER.....	202
T41 & 42N, R13W (T. MINONG, T. CHICOG).....	205
T41 & 42N, R12W (T. MINONG, T. CHICOG, T. BROOKLYN, V. MINONG).....	206
T41 & 42N, R11W (T. FROG CREEK, T. GULL LAKE) .....	207
T41 & 42N, R10W (T. FROG CREEK, T. STINNETT).....	208
T39 & 40N, R13W (C. SPOONER, T. CASEY, T. EVERGREEN).....	209
T39 & 40N, R12W (C. SPOONER, T. BROOKLYN, T. TREGO, T. SPOONER).....	210
T39 & 40N, R11W (T. SPRINGBROOK, T. CRYSTAL) .....	211
T39 & 40N, R10W (T. BASS LAKE, T. STONE LAKE).....	212

T37 & 38N, R13W (C. SHELL LAKE, T. BASHAW, T. BARRONETT).....	213
T37 & 38N, R12W (C. SHELL LAKE, C. SPOONER, T. BEAVER BROOK, T. SARONA).....	214
T37 & 38N, R11W (T. MADGE, T. LONG LAKE).....	215
T37 & 38N, R10W (T. BIRCHWOOD, V. BIRCHWOOD).....	216
VILLAGE OF BIRCHWOOD.....	217
VILLAGE OF MINONG.....	218
CITY OF SHELL LAKE.....	219
CITY OF SPOONER.....	220

## 2016 NORTHWEST WISCONSIN FLOOD

Multiple rounds of severe thunderstorms impacted northwest Wisconsin on Monday, July 11<sup>th</sup> and Tuesday, July 12<sup>th</sup>, 2016. During a 24-hour period the parts of region received historically heavy rainfall, with 8 to 12 inches of precipitation falling in some areas. Some of the most intense rainfall occurred in a swath extending from northern Burnett County, northeasterly through northern Iron County. Heavy rains quickly caused rivers to rise, to in some cases – historic levels. A US Geological Survey (USGS) stream gage on the Bad River near Odanah (Ashland County) rose from 300 cubic feet per second to a record peak streamflow of 40,000 cubic feet per second in only 15 hours. In addition to the heavy rainfall, a bow echo windstorm moved across northern Iron County and caused tremendous damage at Saxon Harbor. The marina and campground were devastated by the floodwaters of Oronto Creek, a steep-gradient Lake Superior tributary which had been rerouted during harbor construction in 1965.



The heavy rainfall caused flash flooding across the region caused widespread and severe damage to roads and infrastructure, homes, businesses, and public facilities. In Ashland County, floodwaters overtopped U.S. Highway 2, resulting in the temporary closure of a major thoroughfare across northern Wisconsin. Travel across much of northwestern Wisconsin was not advised due to inundated roadways and washouts. The timing of these storms also coincided with the peak of tourist season in the region.


Tragically, there were four lives lost as a result of the storm. Among those lost were 58-year-old Mitch Koski, former mayor of the City of Montreal, WI and Iron County Board Supervisor. Koski was checking on the well-being of campers at Saxon Harbor when the bridge over Oronto Creek washed out, sweeping his vehicle downstream.

County, state and local government mobilized quickly in the wake of the disaster. Many of the area's roadways were inundated with water and debris and were impassible. With many of the major transportation corridors closed, long detours were necessary to navigate through the impacted region affecting residents and commerce. While highway crews were busy addressing road and bridge impacts, local emergency managers were busy assessing losses at harbors and marinas on Lake Superior. The full force of the storm hit northern Iron County and completely destroyed the marina and campground at Saxon Harbor. At the time of the storm, the marina was housing 70 boats, of which, at least 12 were destroyed, 19 beached, and 6 sunk and were later recovered. The Iron County Forestry boat, which became unmoored during the storm was last reported in the vicinity of Michigan's Keweenaw Peninsula, nearly 100 nautical miles northeast.



The Bad River Nation was also severely impacted by the storm. More than 46 homes within reservation boundaries were affected by flooding, ten of which were completely destroyed. In the wake of the storm, the reservation was completely cut off from regular access to food, water, and medical supplies. The fish hatchery and wild rice operations of the Bad River Tribe also sustained major damage.

**Figure 1: 2016 FLOOD HYDROGRAPH**



Region wide, the flood event impacted over 350 homes and left behind tens of millions of dollars in public sector damage.

In response to the disaster, the Wisconsin Emergency Operations Center was elevated to a Level 1 (full activation), with agency personnel from the Department of Administration, Department of Transportation, Department of Natural Resources and other state, federal and volunteer agencies coordinating resources. On July 12, 2016, a state of emergency was declared for the affected counties and state agency resources were directed to support response and recovery efforts. Emergency response efforts were supported by volunteer organizations including the American Red Cross, local volunteer fire departments, AmeriCorps, Team Rubicon, statewide tribal organizations and the Civil Air Patrol. Private sector business partners also provided resources and supplies to aid flood victims.

On August 9, 2016, a Presidential Disaster Declaration for public assistance was granted for the counties of Ashland, Bayfield, Burnett, Douglas, Florence, Iron, Sawyer, and Washburn, and the Bad River Band of the Lake Superior Chippewa. The severe flooding also impacted the agricultural industry in northwest Wisconsin, resulting in crop losses and reduced yields. Consequently, an agricultural disaster declaration was designated on September 29<sup>th</sup>, 2016 for the counties of Ashland, Bayfield, and Iron, as well as the five neighboring counties of Douglas, Price, Sawyer, Vilas, and Washburn.

**Table 1: 2016 Northwest Wisconsin Flood, Damage to homes/businesses**


County	Affected/Minor Damage	Major Damage	Destroyed	Total
Ashland	140	2	0	\$500,000
Bad River Band	30	6	10	\$1,104,000
Bayfield	20	10	0	\$150,000
Douglas	2	0	0	\$500
Iron	13/1	12/2	0	\$235,000/\$40,000
Sawyer	112	0	0	\$100,000
Washburn	6	9	1	\$500,000
<b>TOTAL</b>	<b>323/1</b>	<b>39/2</b>	<b>11</b>	<b>\$2,629,500</b>

**Table 2: 2016 Northwest Wisconsin Flood, Damage to Public Infrastructure**


County	Total Losses
Ashland	\$7,295,923
Bad River Band	\$3,403,054
Bayfield	\$5,422,000
Burnett	\$405,000
Douglas	\$797,585
Florence	\$47,000
Iron	\$15,778,000
Oneida	\$3,500
Price	\$34,000
Sawyer	\$2,197,000
Washburn	\$3,000,000
Wisconsin DNR (trails)	\$100,000
<b>TOTAL</b>	<b>\$38,540,199</b>


**Table 3: 2016 CDBG, Emergency Assistance Program Grants**

County	Total Grants
Ashland	\$66,017.57
Bayfield	\$75,865.48
Sawyer	\$64,473.10
Iron	\$2,160.00
<b>Total</b>	<b>\$208,516.15</b>













### **Structural Impacts**

Rapidly rising floodwaters quickly overtook a number of structures in low-lying areas. Over 350 structures were affected in the region, with 11 completely destroyed. The community of Odanah on the Bad River Reservation experienced some of the worst devastation, with a total of 10 structures lost. The federal disaster declaration did not cover businesses or homeowners as the level of damage in these areas did not meet the loss thresholds for federal relief. Limited CDBG-EAP funds were available to assist qualified private property owners.



### **Public Infrastructure Impacts**

The 2016 flood exposed a number of vulnerabilities in the region's infrastructure. The intense flood waters washed out numerous roads and bridges across the region. Many of the road and transportation system impacts were attributed to undersized culverts, which were incapable of handling the excessive floodwaters. Flooding also impacted local wastewater utilities, resulting in a 70,000 overflow at the City of Washburn wastewater treatment plant. The storm also resulted in the complete devastation of the marina and campground at Saxon Harbor.



### **Transportation System Impacts**

Flooded and washout roadways resulted in numerous road closures across the region lasting from several days to several weeks. Major state and federal highways were impassible, including US Highway 2 and 63 and State Highway 13. Long detours made travel in the region difficult and hindered emergency response access to many areas. Many of the roadways impacted in the 2016 flood were also impacted in a 2018 flood. Canadian National Railway also closed a section of track from Ashland to Glidden due to issues from the flooding.



### **Health Impacts**

The storms of July 11-12<sup>th</sup> resulted in the loss of four lives. The event also resulted in numerous injuries and medical emergency calls to local first responders. Transportation system disruptions resulted in some communities and residents being temporarily cut off from access medical care. Many homes across the region were without electricity for several days, and residents were required to boil water for home use and consumption.

## REGIONAL FLOOD STUDY OVERVIEW

During the period of July 11-12, 2016, seven counties in Northwest Wisconsin including Ashland, Bayfield, Burnett, Douglas, Iron, Sawyer, and Washburn and the Bad River Band of the Lake Superior Chippewa Tribe, were struck by historic severe storms and flooding that caused severe flood events throughout the region. Transportation infrastructure was heavily damaged when flood waters rose above the surface of roads and bridges. Many primary and secondary arterial roadways and culverts were washed out in the wake of the elevated water level experienced over a short time period. Damage to homes and businesses across the region was substantial, with over \$2.6 million in losses reported. Damage to public infrastructure was even more significant, with \$38 million reported. One of the region's most critical economic assets, Saxon Harbor, was completely destroyed and the major roadways bisecting northern Wisconsin were completely shut down. Business disruption and impacts to commerce were also significant as many communities were left completely isolated due to road closures. These counties had not anticipated, nor were they prepared to respond to an event of this historic magnitude. In the wake of the storm, county and local emergency response plans were implemented and the Wisconsin Emergency Operations Center was activated. In consultations with the Governor's Cabinet secretaries, county and local government officials expressed grave concerns about the state of local infrastructure, the need for better resiliency planning and the economic impacts of flooding on the tourism-dependent economy of northern Wisconsin.

While many of repairs to the flood damage in northern Wisconsin have been completed, the reconstruction of Saxon Harbor is still in progress. Across this region of Wisconsin there has been very limited efforts to identify, evaluate, and address critical infrastructure in the event of future natural disasters- particularly the economic impact susceptibility related to business commerce, emergency services, transportation, communication, and utilities. Furthermore, there is virtually nothing in place to address community resiliency and business recovery after major storm events occur.

In 2013, a pilot flood resiliency study project was completed by the Northwest Regional Planning Commission (NWRPC) for Taylor County, Wisconsin, which demonstrated the potential impacts of historic flood events, pre-identified likely impact areas and assessed the economic impacts to communities, businesses and residents. The study was incorporated into the county's hazard mitigation plan and now serves as a point of reference to guide flood mitigation activities across the county, which in turn, improves resiliency. This proposal would replicate the process model developed under the 2013 Taylor County pilot project for the seven counties (including the Bad River Band of Lake Superior Chippewa) of northwestern Wisconsin impacted by the historic severe storm event of July, 2016 (Presidential Disaster Declaration DR-4275).


This process model uses FEMA's HAZUS software to estimate potential flood losses and to identify structures, businesses, economic assets and community infrastructure impacted by a historic flood event. The HAZUS model will allow for the identification of vulnerable areas that may require planning consideration. Understanding flood risk will allow communities to assess the level of readiness and preparedness to deal with a flood disaster before it occurs. Model results will provide decision makers with the information and tools needed to decide on how to allocate resources for most effective and efficient response and recovery.

Effective local leadership is crucial to economic development, disaster resilience, and economic

recovery activities in northwest Wisconsin communities. This project includes an outreach component to engage with local governing bodies and communities to help them understand why identifying and managing risks, proactively reducing vulnerabilities and improving response and recovery capabilities are key to promoting economic development resilience across the region. This program will not only advance flood resilience, it also would improve and protect water quality and riparian and shoreline habitat.


## HAZUS-MH

HAZUS is a nationally applicable standardized methodology that contains models for estimating potential losses from earthquakes, floods, and hurricanes. HAZUS uses Geographic Information Systems (GIS) technology to estimate physical, economic, and social impacts of disasters. It graphically illustrates the limits of identified high-risk locations due to earthquake, hurricane, flood, and tsunami. Users can then visualize the spatial relationships between populations and other more permanently fixed geographic assets or resources for the specific hazard being modeled, a crucial function in the pre-disaster planning process. The HAZUS module provides varying levels of analysis based on the level of expertise of the user and the availability of locally-derived data inputs. Under a *basic* analysis, HAZUS generates a simplified analysis using the default national databases and parameters contained in the HAZUS software package. This is commonly referred to as the “out of the box” analysis, as no external data sources or parameter manipulation are required. An *advanced* analysis requires more detailed information on local hazard conditions than is provided by the default national databases included in HAZUS. National default inventories may be replaced by user-defined inputs of buildings, essential facilities or other infrastructure. More detailed topographic data, such as LiDAR (light detection and ranging) can be used to produce accurate maps and bare-earth terrain models. The HAZUS flood model uses ground elevation to determine flood depth of a particular area. Advanced analysis using HAZUS generally requires more user expertise.



## STUDY REGION

The study region includes the 7 counties of northwest Wisconsin under the 2016 federal disaster declaration DR-4276. This include the counties of Ashland, Bayfield, Burnett, Douglas, Iron, Sawyer and Washburn. Within this geographic region, there are 148 units of local government and 5 tribal nations.





## HAZUS-MH FLOOD MODEL


The HAZUS-MH Flood Model allows end users to perform a wide range of flood hazard analyses using default databases, user-defined databases or a combination of the two. The analyses performed in HAZUS-MH can be used to support planning and flood mitigation activities. The HAZUS-MH Flood Model can be used to assess both riverine and coastal flooding and estimates potential damage to buildings, essential facilities, transportation lifelines, utility lifelines, vehicles and agricultural crops. Analysis option within the HAZUS-MH module include:

- Studies of specific return intervals of floods (e.g., 100-year or 500-year return intervals).
- Studies of discharge frequencies, including analysis of discharges from specific streams and the exposure to buildings and population from the resultant flooding.
- Studies of annualized losses from flooding.
- Quick Look assessments, which allows the user to quickly evaluate potential flooding from specific flood depths at specific locations.
- What if scenarios, which allow users to evaluate the consequences of specific actions, such as the introduction of flow regulation devices, acquisition of flood-prone properties and other mitigation measures.


Table 6: Building-Related Economic Loss Estimates  
(Millions of dollars)

Category	Area	Residential	Commercial	Industrial	Others	Total
Building Loss	Building	0.41	0.14	0.05	0.01	0.61
	Content	0.23	0.43	0.05	0.01	0.64
	Inventory	0.05	0.02	0.02	0.00	0.09
	<b>Subtotal</b>	<b>0.69</b>	<b>0.59</b>	<b>0.12</b>	<b>0.02</b>	<b>1.42</b>
Business Interruptions	Employment	0.00	0.00	0.00	0.00	0.00
	Production	0.00	0.00	0.00	0.00	0.00
	Material Income	0.00	0.00	0.00	0.00	0.00
	Wages	0.00	0.00	0.00	0.00	0.00
ALL	<b>Subtotal</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
	<b>Total</b>	<b>0.69</b>	<b>0.59</b>	<b>0.12</b>	<b>0.02</b>	<b>1.42</b>


ESTIMATE LOSSES




DETERMINE DAMAGES



DEFINE AND OVERLAY INVENTORY  
(BUILDINGS, ROADS, INFRASTRUCTURE)



MODEL INUNDATION AREA & DEPTH




MODEL LAND SURFACE  
(LIDAR)

The riverine flood hazard analysis module uses characteristics, such as frequency, discharge and ground elevation to estimate flood depth, flood elevation and flow velocity. Economic losses resulting from floods are estimated by HAZUS-MH using depth-damage functions (DDFs) which correlate inundation depth to building and content losses.



**Figure 4: HAZUS MODEL FLOW DIAGRAM**




## USER-DEFINED FACILITIES (UDF)

The key General Building Stock (GBS) databases in HAZUS-MH include square footage by occupancy and building type, building count by occupancy and building type, valuation by occupancy and building type, and general occupancy mapping. Under a level 1 analysis residential structures are derived from Census 2010 and non-residential structures are derived from Dun & Bradstreet (D&B). In order to greatly improve the accuracy of the outputs derived from HAZUS-MH, the default GBS was replaced with user-defined facilities (UDFs) which reflect the actual building footprints as identified through LiDAR, aerial imagery and field reconnaissance.

For modelling purposes, UDFs within the project area was pre-identified within a preliminary inundation zone created by executing a level 1 analysis using USGS National Elevation Dataset (NED) topographic data. It was assumed that all structures identified within flood hazard boundary created using NED data would also be affected in a scenario using LiDAR topographic data. To provide context, all adjacent structures were also digitized. The flood hazard boundary was buffered by ¼ mile and UDF footprints within boundary file were digitized. A total of 36,062 user-defined facilities were identified within the seven-county project area.

Several attributes were assigned to the UDFs in ArcGIS®. Attribute data is used by HAZUS-MH to determine flood impacts and model estimated losses. HAZUS requires seven model attributes, including occupancy, building type, replacement cost, year built, number of stories, foundation type and first floor height.






## DIGITIZATION PROCESS MODEL


**Step 1:** Run level 1, 500-year flood model to create inundation grid.




**Step 2:** Intersect inundation grid with tax parcels



**Step 3:** Use aerial imagery to determine which parcels have structures.



**Step 4:** Create building footprints, differentiate primary and secondary structures and assign UDF attributes.



## USER-DEFINED FACILITY ATTRIBUTES

UDF ATTRIBUTE	DATA	SOURCE
ADDRESS	Parcel Address	Tax Assessment Data
LATITUDE	Building Footprint Centroids	NWRPC
LONGITUDE	Building Footprint Centroids	NWRPC
OWNER NAME	Parcel Owner Name	Tax Assessment Data
PARCEL ID	Parcel identification Number	Tax Assessment Data
OCCUPANCY TYPE*	Visual Interpretation of Aerial Imagery	NWRPC
REPLACEMENT COST*	Estimated Fair Market Value	Tax Assessment Data
CONTENT COST*	HAZUS Multiplier Based on Occupant	NWRPC
NUMBER OF STORIES*	Visual Interpretation of Aerial Imagery	NWRPC
AREA (SQUARE FEET)*	Calculated Based on Footprints	NWRPC
FOUNDATION TYPE*	Visual Interpretation of Aerial Imagery	NWRPC
FIRST FLOOR HEIGHT*	Visual Interpretation of Aerial Imagery	NWRPC

\*Required HAZUS-MH Attribute

## REQUIRED HAZUS-MH ATTRIBUTES

### REPLACEMENT COST

This attribute was populated using the estimated fair market value data (EFMV) included in the Wisconsin Statewide Parcel GIS data. For parcels without EFMV, median values for other buildings with the same given occupancy classification were substituted.

### CONTENT COST

This attribute is an estimated dollar value of the contents of a flood impacted structure. Since the actual value is unknown, HAZUS-MH default contents values were used. These values are derived by taking a percentage of the Replacement cost and multiplying by a given value based on Occupancy class

### NUMBER OF STORIES

This attribute is simply the number of stories a given structure contains. It was derived from various sources including aerial imagery, Bing "Birds-Eye" imagery, & Google Maps/Street View imagery.

### FOUNDATION TYPE

This attribute refers to the base below a flood a flood impacted structure. In the case of this analysis all buildings were either assigned as having a basement (single family/multi-family residential) or being built on a slab (lakefront property & mobile homes). Assigning a foundation type affects how the damage depth curve is applied to a structure. For example, a structure with a basement is likely to have more substantial damage than a mobile home, at a given flood depth.

**FIRST FLOOR HEIGHT**

This attribute describes the height above ground of a building's first floor. This attribute can be populated in a few ways. For instance, it can be supplied from tax assessor information (if available), field measurement, or by measuring from the door threshold to ground surface in oblique imagery. In the case of this analysis, we used HAZUS-supplied values based on foundation type.

**AREA**

This attribute is the total area of a structure, in square feet. It is used to derive inventory costs for some commercial and industrial occupancy classes. This value does not include accessory buildings, attached garages or patios and decking. This value was calculated based on building footprints, in ArcGIS®.

**USER DEFINED FACILITY ID**

A numerical unique identifier given to each structure in the analysis.

**OCCUPANCY CLASS**

HAZUS-MH groups buildings with similar valuation, damage and loss characteristics into a set of pre-defined categories for analysis.

## OCCUPANCY CLASS

Occupancy class is important in determining economic loss, since building value is primarily a function of building use. Occupancy classifications assigned to buildings in the study region were assigned through aerial photo interpretation, tax roll information and research.


CODE	Table 4: Occupancy Class	Contents Value
<b>RESIDENTIAL</b>		
RES 1	Single Family Dwelling	50
RES2	Mobile Home	50
RKS3	Multi Family Dwelling	50
RES4	Temporary Lodging	50
RES5	Institutional Dormitory	50
RES6	Nursing Home	50
<b>COMMERCIAL</b>		
COM 1	Retail Trade	100
COM2	Wholesale Trade	100
COM3	Personal and Repair Services	100
COM4	Professional/Technical/ Business Services	100
COM3	Banks	100
COM6	Hospital	150
COM7	Medical Office/Clinic	150
COM8	Entertainment & Recreation	100
COM9	Theaters	100
COM 10	Parking	50
<b>INDUSTRIAL</b>		
IND1	Heavy	150
IND2	Light	150
IND3	Food/Drugs/Chemicals	150
IND4	Metals/Minerals Processing	150
IND5	High Technology	150
IND6	Construction	100
<b>AGRICULTURE</b>		
AGRI	Agriculture	100
<b>RELIGION/NON-PROFIT</b>		
RELI	Church/Membership Organization	100
<b>GOVERNMENT</b>		
GOV1	General Services	100
GOV 2	Emergency Response	150
<b>EDUCATION</b>		
EDU1	Schools/Libraries	100
EDU2	Colleges/Universities	150



## VULNERABLE AND CRITICAL FACILITIES

Critical community facilities include those that provide essential emergency services to the community and should be functional after a flood. These facilities include hospitals, police stations, fire stations, emergency medical services and educational institutions. HAZUS-MH includes national datasets which identify a range of essential facilities across the country. The default data provided by HAZUS-MH was determined to be incomplete for the study region, thus supplemental data was created to create a comprehensive profile of these assets across the region. Because these assets are tax exempt functions of government, they have no assessed or fair market valuation.








## CRITICAL INFRASTRUCTURE

Critical infrastructure is defined as the transportation and utility infrastructure that provides communities with communications, water, power, mobility and other necessities for both continuity of governance and economic health. HAZUS-MH provides limited default data, but due to the sensitive nature of these facilities, national datasets are typically unavailable. Therefore, it is usually necessary for local communities to provide the data for analysis.









## TERRAIN SURFACE MODEL

HAZUS-MH uses a digital elevation model (DEM) to generate stream channel and floodplain morphology. DEM accuracy is also important in modeling flood depths, which HAZUS-MH uses to estimate flood losses. The most precise elevation data available for the study area is *Light Detection and Ranging* data (LIDAR). LIDAR is a surveying method that uses pulses of light which reflect off objects (building, trees, ground, etc.) and then are recaptured by a sensor. These sensors are usually attached to an aircraft, which follows a pre-determined flight path, ensuring complete coverage for a project area. In most cases a county. By measuring the differences in return time and wavelength of the reflected light pulses, detailed 3D representations of scanned objects can be developed. The sensor's collection of these light pulses, or "returns" (once post processed) creates a 3-dimensional point cloud. Each one of point in the cloud is classified with an x, y, & z coordinates and can also contain additional information. Each county included in our study area has its own collection of point clouds which are stored as LAS datasets. These datasets are massive in size. Multiple terabytes of storage were required to house them and the processing of this amount of data was incredibly time consuming.



LIDAR data was available for each of the seven counties in the project area. As drainage areas do not necessarily correspond to jurisdictional boundaries, it was necessary to process terrain data outside of the project area boundary in order to develop accurate hydraulic models. This external area includes portion of St. Louis, Carlton, Pine, Kanabec, Chisago and Washington Counties in Minnesota and Gogebic and Ontonagon Counties in Michigan. In Wisconsin, the external area includes portions of St. Croix, Polk, Barron, Rusk Price Vilas and Oneida Counties. While supplemental LIDAR data was available for the external area in Minnesota and some counties in Wisconsin, this information was not available for Michigan. In cases where LIDAR was unavailable, US Geological Survey (USGS) National Elevation Data (NED) at a resolution of 1/3<sup>rd</sup> arc second (10 meters) was used. NED data tiles were downloaded from the U.S. Geological Survey and processed in HAZUS with LIDAR data sets to produce a seamless elevation layer. County LIDAR data sets were received as either LAS point cloud data files or digital elevation models derived from LAS points. For some counties, DEMs were hydro-flattened, while others were not. Hydro-flattening is the process of creating a LiDAR-derived DEM in which water surfaces appear / behave as they would in traditional topographic DEMs created from photogrammetric digital terrain models (DTMs). For counties with LIDAR-based DEMs which were not flattened and for which hydro break lines were available, manual hydro-flattening was conducted.

LIDAR data sets for the project area were produced by different vendors with widely varying standards and definitions with regards to how classes were derived. LIDAR-based DEMs data were digitally combined to produce a project area mosaic. For all areas where LIDAR coverage was unavailable, supplemental NED 10m DEMs were used. Due to resolution differences between LIDAR-based DEMs and 10m NED data, the entire project area was resampled to a 5m cell size.



## HYDRO-FLATTENING

Additional processing was done to several individual county LAS datasets through a process called hydro-flattening. Hydro flattening is a process in which break lines around bodies of water are generated as part of the LiDAR collection post-processing. These break lines identify areas where data collection identifies elevation variability over water bodies. These areas are then given a value at the shoreline (or a downstream trending value, in the case of a flowing river) and "flattened" to the given value. This eliminates any erroneous values that would otherwise disrupt the directional flow of a water body.

## MOSAICING


Each county's LiDAR data also had varying degrees of accuracy and data specifications. These disparate datasets needed to be merged into a single uniform contiguous dataset in order to develop a depth grid. Due to the lack of LiDAR data availability in The Western Upper Peninsula of Michigan, 1/3 arc-second National Elevation Dataset (NED) was substituted (which was necessary to complete Iron and Ashland County's Analyses). A 5m cell size was chosen for our elevation data. This means that each pixel in the elevation data was 5m x 5m on the ground. A

5m pixel size required us to develop our raw LIDAR data at 5m cells and re-sample our areas with NED coverage (10m cell size) to match our LIDAR data. Due to the varying collection methods and temporal differences of the individual county LiDAR datasets, there were varying degrees of cohesiveness between neighbor counties (or even states, as along the Minnesota/Wisconsin border). Based on how the LiDAR data had been post-processed (hydro-flattened vs. not hydro-flattened), some counties data had up to a 12m (40ft) of difference in elevation where it adjoined a neighbor county. These inaccuracies created artificial “walls” or “falls” across water bodies, which needed correction for creation of a depth grid. Erroneous elevation data was carefully removed from county datasets (where it existed) and was replaced by neighboring county data, which was more likely to contain accurate elevation values. Once the elevation inaccuracies were thoroughly cleaned, the data was mosaiced into a single seamless and contiguous surface. This elevation surface could then be run through FEMA’s HAZUS-MH software to develop the 100-year and 500-year depth grids used in the analysis.

### TERRAIN HYDROPROCESSING (PRE-PROCESSING)


Hydrologic conditioning (HC) is the process of modifying a digital elevation model (DEM) to alter flow routing and drainage. The most common practice of HC is to remove “digital dams” or barriers within the DEM that block the hypothetical flow of water typically associated with road crossings and other obstructions. One method of removing barrier features is to “burn” the stream through the obstruction to force flow downstream using “cutlines.” Cutlines are manually placed in areas when an obstruction to flow occurs that should be “burned through”. This will more accurately depict the flow of water over the earth’s surface. Accurate elevation data is critical for this analysis to be accurate. The DEMs used in this report, were obtained from a variety of local, state and national datasets. Hydro conditioning was conducted using the

DEM RASTER (UNFILLED)






FLOW DIRECTION




FLOW ACCUMULATION RASTER




Agricultural Conservation Planning Framework (ACPF) GIS toolset, developed by the United States Department of Agriculture – Agricultural Research Service (USDA-ARS). Processing was conducted on the ArcGIS® 10.5.1 platform.

FILLED RASTER



FLOW NETWORK



The first step of this process is to add the DEM raster file of the area that will be analyzed to ArcMap®. The DEM must be represented in meters for the following steps to work correctly. This allows the D8 Terrain Processing tool to be run. This tool only requires an unfilled DEM of




the Flood analysis area and performs a series of operations to derive key output layers which will be used in the cutline burning process. The D8 tool first performs a fill operation on the DEM which raises the elevation values within all the depressions so that so that water will “pour” out of any depression and will create a continuous flow network across the watershed. Second, the tool applies a D8 Flow Routing algorithm to the filled DEM to create a flow direction raster. Each pixel is assigned a number that is associated with a direction that the water is flowing. The next step uses the flow direction raster to generate a flow accumulation raster. This flow accumulation raster adds up all the contributing pixels that “flow” into other pixels. Lastly, the D8 Terrain processing tool creates a hillshade raster that is used for visual purposes when analyzing the DEM. The objective of the next step (Flow Network Definition) is to generate a Flow Network based on the flow direction and flow accumulation raster created by the first tool. A value of 10 acres was given to the area threshold which helps create a rough overlay of rivers and streams in the area. The smaller the threshold value, the more detailed the stream network will be. There is a fine line between being too detailed and being too broad. In glacial landscapes, like northwest Wisconsin, an area threshold of 10 acres is recommended.



32	64	128
16		1
8	4	2

#### DEPTH GRID RASTER




The third step involves using the Identify Impeded Flow tool to hydro-condition the original unfilled DEM raster. It is an iterative process by which the topographic data in the DEM is modified to more accurately represent water flow. This tool generates a depth grid raster that represents the differences between the unfilled and filled DEM developed in the previous terrain processing tool. The depth grid raster can be used as a visual aid for the manual hydro-conditioning process to identify obstructions to flow that should be “burned through” by placing cutlines. Several steps have to be taken before the final tool can be run. There are various layers that need to be added, as well as changes in symbology that will aid in the

identification of potential culvert locations. High quality aerial imagery, accurate road data and hydrology lines are added in ArcGIS®. Aerial imagery can help confirm whether a culvert is present or not. Updated road and stream data is also helpful in identifying road-stream crossings where a culvert is likely to be present.


## PLACING CUTLINES

Using the hillshade, DEM, depth grid raster, roads, and flowlines as a guide, cutlines were manually placed at locations where our data indicated the likely presence of a culvert. Cutlines were drawn from a *higher* to a *lower* elevation using the DEM to verify elevation. A new feature class was created containing the region-wide cutlines.


OBSTRUCTED FLOW (LIKELY CULVERT OR BRIDGE)




CUTLINE, WITH DEPTH GRID RASTER



FINAL DEM WITH CUTLINES (UPDATED DEPTH GRID)




FINAL DEM WITH CULVERT "BURNED" INTO DEM







## TERRAIN PROCESSING (HAZUS-MH)

Due to the large file size of LIDAR-based DEMs and processing limitations of HAZUS-MH, terrain processing was conducted at the individual county scale. The project area composite DEM was used as the base elevation model from which each county study region was created. The HAZUS-MH flood hazard analysis consists of three stages: stream delineation, hydrologic analysis to determine stream discharge, and hydraulic analysis to determine flood depth and extent.






**Study Region DEM**  
(Douglas County)



**Study Region  
Watersheds**  
(Douglas County)






**Delineating Stream  
Network**  
(Douglas County)

HAZUS-MH computes a synthetic stream network based on the drainage areas calculated from the DEM. An input for parameter for the threshold drainage area allows the user to define the minimum accumulation area draining to a stream network. The smaller the threshold drainage area, the more detailed the stream network generated in HAZUS. Processing time is also a consideration when using the complex and topographically detailed LIDAR-based DEMs. While using a very small drainage area (0.5 square miles) created a more detailed stream network, it also occasionally resulted in erroneous data when processing flood depth grids creating an artificial "gridding effect" in the output raster. Using a larger drainage area of 5.0 square miles proved to be most effective in characterizing rural stream networks, while reducing or eliminating the gridding effect. Using a 5 square mile drainage threshold value also produced a synthetic stream network which very accurately reflected the actual 1:24,000 stream network. For urban areas, the threshold drainage area was reduced to 0.5 square miles without generating the gridding effect, so it appears that region size and/or processing capability may be a limiting factor in determining optimal threshold drainage area.

## HYDOLOGIC ANALYSIS

The objective of hydrologic analysis in HAZUS-MH is to calculate rainfall-runoff characteristics for watersheds and identify discharge values in streams. HAZUS-MH implements hydrologic analysis through built-in regression equations to determine discharge-frequency relationships for each reach and include gage and main stream adjustment. Regression equations within HAZUS-MH include derived variables including catchment area, mean catchment elevation and slope, and channel length; along with default localized parameters including temperature, precipitation, soil type, forest cover and snowfall. The HAZUS default database contains stream gage records from across the United States which are used to adjust the regression results based on comparison with other watersheds across the country with similar hydrologic characteristics. Upon completion of the hydrologic analysis, an output peak discharge table is generated with discharges computed at each reach's upstream and downstream nodes for return periods of 2, 5, 10, 25, 50, 100 and 500 years.

FLID	POINT	AREA	Q2	Q5	Q10	Q25	Q50	Q100	Q200	Q500	OBJECTID
17	9	6.873548	585	1210	1687	2365	2906	3460	3969	4584	18
18	10	8.296452	114	247	349	492	503	717	836	993	19



## HYDRAULIC ANALYSIS

HAZUS-MH uses the derived discharge values and stream channel morphology calculated under the hydrologic analysis to compute flood elevations at stream cross-sections. Within HAZUS-MH, the hydraulic analysis is performed using Manning's equation with a friction slope equal to the slope of the reach to estimate flood elevations. Inputs include discharge, cross-section descriptions [channel slope, cross-section geometry and friction factors for inundated areas], and 2-D flow fields, varying Manning's n, bridge geometries, expansion/contraction coefficients and subcritical/super-critical flow. Outputs include flood elevations at cross-sections, energy head, flood velocity, flood depths and extents. The model is greatly simplified in HAZUS-MH.

Inputs include peak discharge, cross-section geometries, 1-D flow field and constant Manning's  $n$  for sub-critical flow. Only flood elevations at cross-sections, flood depth and extent grids are generated.

HAZUS estimates the initial floodplain by buffering the reaches [buffer distance =  $10 * Q^{0.5}$ ]. Flow centerlines are determined and cross-section lines are placed normal to the flow centerline at intervals of 1000 feet. Manning's equation determines the flood elevations at the stream cross-sections and HAZUS interpolates elevations between cross-sections to create a flood surface. DEM  $z$  (height) values are subtracted from the flood surface elevation to produce a flood depth grid, which depicts inundation areas and the estimated depth of floodwater along corresponding reaches.

Reach ID	Discharge (cfs)	n-value
1	10,000	0.020
3	10,000	0.020
5	10,000	0.160
6	10,000	0.020
7	10,000	0.020
9	10,000	0.020
11	10,000	0.020
12	10,000	0.020
13	10,000	0.020
15	10,000	0.160
18	10,000	0.160
19	10,000	0.160
25	10,000	0.160
26	10,000	0.160
27	10,000	0.160


HAZUS-MH allows for the incorporation of user-defined depth grids from third-party sources, such as Hydrologic Engineering Centers River Analysis System (HEC-RAS) files or depth grids interpolated from FEMA Digital Flood Insurance Rate Maps.

Hydraulic analysis may be performed for a single return period, multiple return periods or for a specific discharge, if available. USGS stream gage sites typically collect discharge data, which can be used to interpolate projected inundation for a given river stage. Unfortunately, this region of Wisconsin – while having an abundance of rivers and streams – has relatively few stream gages. There are 45 gage sites with a historical record varying from 192 to 32,300 day and 12 active recording sites within the seven-county project area.

### Failed Reaches


In running the riverine hydraulic analysis using HAZUS-MH, there were river reaches that the software was unable to process. These are considered failed reaches, with not output generated. HAZUS-MH developers classify failed reaches as *"...reaches that have been processed in the hydraulics process, but for some reason, do not produce a flood depth grid."*<sup>1</sup> In lieu of the software not being able to build a depth grid for these reaches (using the 5m LiDAR data), portions of a previously developed depth grid, using 10m USGS National Elevation Dataset (NED), were used as surrogates. These 10m reaches were resampled down to a 5m cell size to match the LiDAR generated depth grid. There were also a few cases where the reach processing failed in both the 5m and the 10m scenarios. In these cases, no depth grid was available for these reaches. The distribution of failed reaches, by return period, is illustrated in the table below.


<sup>1</sup> HAZUS-MH User Manual, p 3-71



Return Period	Reaches failed in LiDAR Elevation Data	Reaches failed in LiDAR & NED Elevation Data
100- Year Flood Event	39	12
500-Year Flood Event	56	5









## FLOOD DEPTH GRIDS


A HAZUS-MH flood depth grid is created by subtracting (cell-by-cell) the ground elevation, contained in the DEM grid, from the flood elevations at cross sections. This raster data set contains grid cells which depict the depth of water (in feet) within the inundation zone (flood hazard boundary).





## DEPTH GRID ANOMALIES

Overall, depth grid generation in HAZUS-MH met expectations relative to the spatial area of inundation and flood depth.




### Random depth grid features

Isolated, disconnected areas generated by HAZUS-MH in the riverine hydraulics process. In this example, the area in question is disconnected from adjacent hydrology and modeled flood depth is dramatically inconsistent with nearby areas. This modeled feature also indicates some degree of clipping. Where encountered, these areas were manually removed from the flood depth grid.



### Clipping

Areas where no flood depth grid was generated in HAZUS-MH. Missing areas are often exhibit elements of symmetry not typically encountered in natural features. In this example, the depth grid appears to be clipped in alignment with a squared feature. These areas were not removed from the flood depth grids or altered. Based on consultation with the FEMA HAZUS-MH Help Desk, it appears that these anomalies may be due to processing limitations within the HAZUS-MH software.




### Banding

Unusual variations in the flood depth grid where unexpected changes in inundation depth are indicated. In some cases, banding does occur at locations where cut lines were placed. This expected to some degree as the flow is being constricted to the width of the cut line drawn. Other banding errors appear to be random and are not associated with the placement of cut lines. These areas were not removed from the flood depth grids or altered.

## DEPTH GRID MOSAIC PROCESS

Due to processing limitations within HAZUS-MH, a single region-wide depth grid could not be created using the software. The data set was too large and the software's memory limitations were exceeded. The HAZUS-MH support help desk advised to either increase the cell size of our elevation data (lowering its resolution, in which case LIDAR data would cease to be relevant) or break the region into smaller sections, and develop the depth grids individually. To develop a regional depth grid, the hydraulic and hydrological processing was completed at the census tract level, by county, and the cities and villages were processed individually. Once these individual depth grids were completed, they were mosaiced together, using a mosaic method in which the largest cell value (or flood depth) was used for areas with overlapping coverage.






## LOSS ESTIMATION


Loss estimation modelling was conducted using an ArcGIS® Python® Script developed by the Oregon Department of Geology and Mineral Industries (DOGAMI). Developed in 2018, this script uses the Python programming language to estimate losses from user defined features (UDFs). It was developed specifically for users of high-resolution depth grids, developed from LIDAR data. Using this script allowed our analysis workflow several time saving measures, over the traditional HAZUS-MH method. These improvements included eliminating the creation of duplicate data and geoprocesses, bypassing entry of our UDFs into the HAZUS Comprehensive Data Management System (CDMS) for standardization, and processing power. The script analyzes UDFs at roughly 10 times the speed of using the HAZUS-MH software. Like HAZUS-MH, the script calculates damages to buildings, content, & inventory through depth damage functions and also models debris generation. The script was developed

using identical methodology for assessing damage to UDFs and debris generation, as outlined in the HAZUS technical manual (FEMA, 2011). However, the DOGAMI does not take into account the analysis of the default HAZUS-MH essential facilities inventory. Our research found the default HAZUS-MH inventory lacking for our region and we developed our own essential facility and infrastructure inventories. The inventories we developed are more robust, complete, and spatially accurate than the inventories included in the HAZUS-MH software. In addition to damage and debris generation, the DOGAMI script also calculates minimum and maximum replacement time (in days), adding a time element to the analysis. This replacement time analysis is not available using HAZUS-MH.



## DAMAGE-DEPTH FUNCTIONS

Figure 11: DAMAGE DEPTH CURVES, RESIDENTIAL 1 OCCUPANCY CLASS



In the DOGAMI script, flood damages to structures are estimated based on building values (estimated fair market value) and flood depth. The script uses the same flood depth damage functions (DDF's) as HAZUS-MH and can be customized if supplemental local information is available. Damage depth curves for use structure type and occupancy class to estimate the percent of the building value that is damaged. Flood depth damage curves relate feet of inundation with percent of building damage depending on the structure type and occupancy class. These curves are derived from national data; however, because the curves are applied to regional building types and basin specific hydrology, the results are applicable to the basin. Content and inventory damages are based on structure value (fair market value) and the type of structure evaluated.

Flood depth grids created in HAZUS-MH were imported into the DOGAMI script, along with user defined facility (UDF) point files. UDF point data contained structure attribute information needed to execute the analysis, including occupancy class, foundation type, building height (stories) and content values (fair market value). The script then processed the input data to derive loss estimates.

## RESULTS SUMMARY

The analysis concluded that 1,022 structures would be impacted under the 100-year scenario and 1,318 structures under the 500-year scenario. A 100-year flood has an annual exceedance probability of 1%, meaning it's likely to occur once every 100 years. The annual exceedance probability of a 500-year flood is 0.2%, meaning an event at this magnitude is likely to occur once every 500 years. Regionwide, loss estimates under the 100-year scenario were \$15.2M and \$24.0M under the 500-year scenario. The model estimates that 12 critical community assets/facilities would be impacted under the 100-year scenario and 17 under the 500-year scenario.

**Table 5: ESTIMATED LOSSES BY COUNTY, 100-YR FLOOD EVENT**

County	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
ASHLAND	92	\$ 582,162	\$ 456,098	\$ 47,840	1,002
BAYFIELD	78	\$ 796,776	\$ 340,749	\$ -	1,139
BURNETT	138	\$ 2,034,886	\$ 923,344	\$ 31,034	1,508
DOUGLAS	67	\$ 644,579	\$ 632,320	\$ -	506
IRON	45	\$ 399,383	\$ 579,651	\$ 113,681	682
SAWYER	396	\$ 7,640,836	\$ 5,867,389	\$ 204,919	6,001
WASHBURN	206	\$ 3,129,779	\$ 1,865,586	\$ 41,355	2,205
<b>GRAND TOTAL</b>	<b>1022</b>	<b>\$ 15,228,401</b>	<b>\$ 10,665,137</b>	<b>\$ 438,829</b>	<b>13,043</b>

**Table 6: ESTIMATED LOSSES BY COUNTY, 500-YR FLOOD EVENT**

County	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
ASHLAND	114	\$ 875,091	\$ 738,537	\$ 124,599	1,408
BAYFIELD	114	\$ 1,610,034	\$ 611,690	\$ 207	1,848
BURNETT	180	\$ 2,767,118	\$ 1,449,384	\$ 39,815	1,993
DOUGLAS	100	\$ 1,120,682	\$ 733,852	\$ -	943
IRON	48	\$ 249,664	\$ 196,964	\$ 9,924	443
SAWYER	475	\$ 11,874,777	\$ 8,857,823	\$ 318,409	12,054
WASHBURN	287	\$ 5,500,003	\$ 3,629,578	\$ 188,619	3,493
<b>GRAND TOTAL</b>	<b>1,318</b>	<b>\$ 23,997,369</b>	<b>\$ 16,217,828</b>	<b>\$ 681,573</b>	<b>22,182</b>

**Table 7: ESTIMATED LOSSES BY OCCUPANCY CLASS, 100-YR FLOOD EVENT**

Occupancy Class	Ashland	Bayfield	Burnett	Douglas	Iron	Sawyer	Washburn	Grand Total
AGRI							6	6
COM1	3		2		4	6	3	18
COM10							1	1
COM2	1				1		5	7
COM3	3	1	3			2	10	19
COM4						5	1	6
COM8	2	6	1	5	2	18	4	38
EDU1							3	3
GOV1	3	3	1			4	8	19
GOV2			1			2		3
IND2	5					1		6
REL1				1			3	4
RES1	66	62	124	55	36	326	143	812
RES2	6	2	4	5		5	2	24
RES3A	2							2
RES3D	1							1
RES4		4	2	1	2	26	17	52
RES6						1		1
<b>TOTAL</b>	<b>92</b>	<b>78</b>	<b>138</b>	<b>67</b>	<b>45</b>	<b>396</b>	<b>206</b>	<b>1022</b>

Roughly 80 percent of the potentially affected structures are single family homes (RES1). Estimated impacts to businesses were notable in both return periods, with more than 8 percent of potentially affected structures classified as either commercial or industrial. Most businesses potentially impacted tend to be small businesses (COM 8, entertainment & recreation), although some larger businesses were also identified. Potential impacts to general government services (GOV1) include wastewater treatment facilities, town halls, Wisconsin Department of Natural Resource facilities and park/recreation assets. Critical assets which are potentially impacted include electrical substations and dams.



**Table 8: ESTIMATED LOSSES BY OCCUPANCY CLASS, 500-YR FLOOD EVENT**

Occupancy Class	Ashland	Bayfield	Burnett	Douglas	Iron	Sawyer	Washburn	Grand Total
AGRI						2	9	11
COM1	3	1	2		1	5	8	20
COM10							1	1
COM2	1		1				5	7
COM3	3	1	3			1	14	22
COM4	1					6	1	8
COM5	1					1	1	3
COM8	4	7	2	4	2	23	6	48
EDU1							3	3
GOV1	5	3	2			4	9	23
GOV2			1			2		3
IND2	6	1				2		9
IND6							1	1
REL1			1	1			3	5
RES1	82	92	161	87	40	384	206	1052
RES2	5	3	3	6	1	12	3	33
RES3A	2							2
RES3D	1							1
RES4		6	4	2	4	32	17	65
RES6						1		1
<b>TOTAL</b>	<b>114</b>	<b>114</b>	<b>180</b>	<b>100</b>	<b>48</b>	<b>475</b>	<b>287</b>	<b>1318</b>

## STRUCTURES IMPACTED

This value represents a count of the number of buildings which intersect the flood depth grid for a given return period. In some cases, buildings may intersect the flood boundary but have no projected losses. In these cases, the estimated depth of inundation was insufficient to cause damage.

## ESTIMATED BUILDING LOSSES

The estimated direct economic losses to buildings associated with a given return period. Building values were derived from tax assessment data using the "estimated fair market value" parameter. Estimated Fair Market Value is calculated by dividing the properties total assessed value by the average assessment ratio for the municipality. Damage-depth functions within the model correlate inundation depth from the flood depth grid with the estimated percent structure damage derived from the damage-depth curve. The estimated percent damage is multiplied by the estimated fair market value to obtain the building loss statistic.

**ESTIMATED CONTENT LOSSES**

Building content values are estimated using a multiplier value which is based on occupancy class. The multiplier is applied to the estimated fair market value to derive an estimate of the value of personal property contained within the structure. The default HAZUS-MH DDF lookup table contains the damage-depth curve data used to estimate content losses. Like building loss estimation, content losses are estimated based on flood depth and occupancy class.

Estimated Fair Market Value x Content Value Multiplier = **Estimated Content Value**

Estimated Content Value x Content Loss Percent (from damage-depth curve) = **Estimated Content loss**

**Table 9: ESTIMATED CONTENT LOSSES**

CODE	Occupancy Class	Contents Value (%)	CODE	Occupancy Class	Contents Value (%)
RES 1	Single Family Dwelling	50	COM9	Theaters	100
RES2	Mobile Home	50	COM 10	Parking	50
RKS3	Multi Family Dwelling	50	IND1	Heavy	150
RES4	Temporary Lodging	50	IND2	Light	150
RES5	Institutional Dormitory	50	IND3	Food/Drugs/Chemicals	150
RES6	Nursing Home	50	IND4	Metals/Minerals Processing	150
COM 1	Retail Trade	100	IND5	High Technology	150
COM2	Wholesale Trade	100	IND6	Construction	100
COM3	Personal and Repair Services	100	AGRI	Agriculture	100
COM4	Professional/Technical	100	REL1	Church/Membership	100
COM3	Banks	100	GOV1	General Services	100
COM6	Hospital	150	GOV 2	Emergency Response	150
COM7	Medical Office/Clinic	150	EDU1	Schools/Libraries	100
COM8	Entertainment & Recreation	100	HOU2	Colleges/Universities	150

**ESTIMATED INVENTORY LOSSES**

Depending on Occupancy Class, the business Inventory Cost is calculated based on type of business and the building's square footage. To estimate business inventory losses, percent damage (determined from the depth-damage function) was multiplied by the total inventory value.

Area (square feet) x Annual Sales (per square foot) x Business Inventory Percent of Sales = **Inventory Cost**


Inventory cost x Inventory Damage Percent (from damage-depth curve) = **Estimated Inventory loss**

Table 10: ESTIMATED INTENTORY LOSSES


Occupancy Class	Annual sales per square foot	Business Inventory percent of sales
AGR1	\$ 148	8%
COM1	\$ 53	13%
COM2	\$ 77	10%
IND1	\$ 713	5%
IND2	\$ 226	4%
IND3	\$ 697	5%
IND4	\$ 656	3%
IND5	\$ 437	4%
IND6	\$ 768	2%


### DEBRIS GENERATION


Debris removal includes the clearance, removal, and/or disposal of items such as trees, sand, gravel, building components, wreckage, vehicles, and personal property following a flood event. The HAZUS-MH damage-depth functions used by the DOGAMI script calculate **total debris** is a combination of finish, structure, and foundation debris estimates. This figure is based on occupancy class, square footage, foundation type, and depth-in-structure. Debris removal and cleanup costs vary based on location and the nature of debris materials. FEMA generally does not cover the costs associated with debris removal from private property.


























**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**

**HAZUS**  
EARTHQUAKE • WIND • FLOOD • TOLLING

# FLOOD DEPTH GRID DOUGLAS COUNTY, WI








**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**

**HAZUS**  
EARTHQUAKE • WIND • FLOOD • TSUNAMI


**FLOOD DEPTH GRID  
BAYFIELD COUNTY, WI**












**HAZUS**  
EARTHQUAKE • WIND • FLOOD • TERRORISM

**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**

**FLOOD DEPTH GRID  
BURNETT COUNTY, WI**




# FLOOD DEPTH GRID WASHBURN COUNTY, WI



**HAZUS**  
EARTHQUAKE • WIND • FLOOD • TSUNAMI

**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**

# FLOOD DEPTH GRID SAWYER COUNTY, WI







**BUILDING AND LOSS ESTIMATES**



## ASHLAND COUNTY

### HAZUS 100-YEAR FLOOD LOSS ESTIMATES - ASHLAND COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
C. OF MELLEN	17	\$ 74,495.00	\$ 77,857.00	\$ 7,326.00	234
T. OF AGENDA	2	\$ 33,789.00	\$ 11,816.00	\$ -	13
T. OF ASHLAND	1	\$ -	\$ -	\$ -	0
T. OF CHIPPEWA	21	\$ 207,621.00	\$ 72,087.00	\$ -	144
T. OF GINGLES	1	\$ 7,859.00	\$ 2,607.00	\$ -	1
T. OF GORDON	8	\$ 70,128.00	\$ 20,295.00	\$ -	117
T. OF JACOBS	10	\$ 31,921.00	\$ 46,933.00	\$ 10,413.00	135
T. OF MARENGO	1	\$ -	\$ -	\$ -	5
T. OF MORSE	1	\$ 34,296.00	\$ 19,188.00	\$ -	7
T. OF PEEKSVILLE	2	\$ 3,415.00	\$ 1,204.00	\$ -	7
T. OF SANBORN	2	\$ 4,978.00	\$ 1,871.00	\$ -	7
T. OF SHANAGOLDEN	3	\$ 4,827.00	\$ 1,829.00	\$ -	15
T. OF WHITE RIVER	1	\$ -	\$ -	\$ -	1
V. OF BUTTERNUT	22	\$ 108,833.00	\$ 200,411.00	\$ 30,101.00	316
<b>GRAND TOTAL</b>	<b>92</b>	<b>\$ 582,162.00</b>	<b>\$ 456,098.00</b>	<b>\$ 47,840.00</b>	<b>1002</b>

### HAZUS 500-YEAR FLOOD LOSS ESTIMATES - ASHLAND COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
C. OF MELLEN	12	\$ 86,218.00	\$ 112,561.00	\$ 12,514.00	237
T. OF AGENDA	2	\$ 50,609.00	\$ 17,150.00	\$ -	21
T. OF ASHLAND	2	\$ 7,995.00	\$ 3,140.00	\$ -	3
T. OF CHIPPEWA	24	\$ 263,865.00	\$ 85,691.00	\$ -	171
T. OF GINGLES	1	\$ 8,967.00	\$ 2,844.00	\$ -	1
T. OF GORDON	8	\$ 89,271.00	\$ 25,171.00	\$ -	115
T. OF JACOBS	16	\$ 86,810.00	\$ 264,883.00	\$ 36,561.00	428
T. OF MARENGO	3	\$ 7,590.00	\$ 1,796.00	\$ -	22
T. OF PEEKSVILLE	2	\$ 7,226.00	\$ 2,551.00	\$ -	7
T. OF SANBORN	12	\$ 127,432.00	\$ 70,234.00	\$ -	55
T. OF SHANAGOLDEN	4	\$ 41,208.00	\$ 14,072.00	\$ -	20
T. OF WHITE RIVER	2	\$ -	\$ -	\$ 17,201.00	3
V. OF BUTTERNUT	26	\$ 97,900.00	\$ 138,444.00	\$ 58,323.00	325
<b>GRAND TOTAL</b>	<b>114</b>	<b>\$ 875,091.00</b>	<b>\$ 738,537.00</b>	<b>\$ 124,599.00</b>	<b>1,408</b>



T. BARKSDALE

# REGIONAL FLOOD STUDY

## T47 & 48N, R4W, ASHLAND COUNTY

Lake Superior

C. ASHLAND


T. SANBORN

T. EILEEN

T. GINGLES

T. KELLY

T. WHITE RIVER



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY  
HAZUS



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ⚡ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T47 & 48N, R3W, ASHLAND COUNTY





- |   |   |   |  |
|---|---|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background-color: #000080; margin-right: 5px;"></div> 100 YR<br/> <div style="width: 20px; height: 20px; background-color: #800080; margin-right: 5px;"></div> 500 YR </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|---|--|



# REGIONAL FLOOD STUDY

## T47 & 48N, R2W, ASHLAND COUNTY




- |   |   |   |  |
|---|---|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background: linear-gradient(to top, blue, purple); margin-right: 5px;"></div> <div style="text-align: center;">             100 YR<br/>             500 YR           </div> </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|---|--|




**REGIONAL FLOOD STUDY**  
T45 & 46N, R4W, ASHLAND COUNTY

**Legend:**

- 1. Flood Zone (Shaded Area)
- 2. Flood Zone (Shaded Area)
- 3. Flood Zone (Shaded Area)
- 4. Flood Zone (Shaded Area)
- 5. Flood Zone (Shaded Area)
- 6. Flood Zone (Shaded Area)
- 7. Flood Zone (Shaded Area)
- 8. Flood Zone (Shaded Area)
- 9. Flood Zone (Shaded Area)
- 10. Flood Zone (Shaded Area)
- 11. Flood Zone (Shaded Area)
- 12. Flood Zone (Shaded Area)
- 13. Flood Zone (Shaded Area)
- 14. Flood Zone (Shaded Area)
- 15. Flood Zone (Shaded Area)
- 16. Flood Zone (Shaded Area)
- 17. Flood Zone (Shaded Area)
- 18. Flood Zone (Shaded Area)
- 19. Flood Zone (Shaded Area)
- 20. Flood Zone (Shaded Area)
- 21. Flood Zone (Shaded Area)
- 22. Flood Zone (Shaded Area)
- 23. Flood Zone (Shaded Area)
- 24. Flood Zone (Shaded Area)
- 25. Flood Zone (Shaded Area)
- 26. Flood Zone (Shaded Area)
- 27. Flood Zone (Shaded Area)
- 28. Flood Zone (Shaded Area)
- 29. Flood Zone (Shaded Area)
- 30. Flood Zone (Shaded Area)
- 31. Flood Zone (Shaded Area)
- 32. Flood Zone (Shaded Area)
- 33. Flood Zone (Shaded Area)
- 34. Flood Zone (Shaded Area)
- 35. Flood Zone (Shaded Area)
- 36. Flood Zone (Shaded Area)
- 37. Flood Zone (Shaded Area)
- 38. Flood Zone (Shaded Area)
- 39. Flood Zone (Shaded Area)
- 40. Flood Zone (Shaded Area)
- 41. Flood Zone (Shaded Area)
- 42. Flood Zone (Shaded Area)
- 43. Flood Zone (Shaded Area)
- 44. Flood Zone (Shaded Area)
- 45. Flood Zone (Shaded Area)
- 46. Flood Zone (Shaded Area)
- 47. Flood Zone (Shaded Area)
- 48. Flood Zone (Shaded Area)
- 49. Flood Zone (Shaded Area)
- 50. Flood Zone (Shaded Area)
- 51. Flood Zone (Shaded Area)
- 52. Flood Zone (Shaded Area)
- 53. Flood Zone (Shaded Area)
- 54. Flood Zone (Shaded Area)
- 55. Flood Zone (Shaded Area)
- 56. Flood Zone (Shaded Area)
- 57. Flood Zone (Shaded Area)
- 58. Flood Zone (Shaded Area)
- 59. Flood Zone (Shaded Area)
- 60. Flood Zone (Shaded Area)
- 61. Flood Zone (Shaded Area)
- 62. Flood Zone (Shaded Area)
- 63. Flood Zone (Shaded Area)
- 64. Flood Zone (Shaded Area)
- 65. Flood Zone (Shaded Area)
- 66. Flood Zone (Shaded Area)
- 67. Flood Zone (Shaded Area)
- 68. Flood Zone (Shaded Area)
- 69. Flood Zone (Shaded Area)
- 70. Flood Zone (Shaded Area)
- 71. Flood Zone (Shaded Area)
- 72. Flood Zone (Shaded Area)
- 73. Flood Zone (Shaded Area)
- 74. Flood Zone (Shaded Area)
- 75. Flood Zone (Shaded Area)
- 76. Flood Zone (Shaded Area)
- 77. Flood Zone (Shaded Area)
- 78. Flood Zone (Shaded Area)
- 79. Flood Zone (Shaded Area)
- 80. Flood Zone (Shaded Area)
- 81. Flood Zone (Shaded Area)
- 82. Flood Zone (Shaded Area)
- 83. Flood Zone (Shaded Area)
- 84. Flood Zone (Shaded Area)
- 85. Flood Zone (Shaded Area)
- 86. Flood Zone (Shaded Area)
- 87. Flood Zone (Shaded Area)
- 88. Flood Zone (Shaded Area)
- 89. Flood Zone (Shaded Area)
- 90. Flood Zone (Shaded Area)
- 91. Flood Zone (Shaded Area)
- 92. Flood Zone (Shaded Area)
- 93. Flood Zone (Shaded Area)
- 94. Flood Zone (Shaded Area)
- 95. Flood Zone (Shaded Area)
- 96. Flood Zone (Shaded Area)
- 97. Flood Zone (Shaded Area)
- 98. Flood Zone (Shaded Area)
- 99. Flood Zone (Shaded Area)
- 100. Flood Zone (Shaded Area)








# REGIONAL FLOOD STUDY

## T45 & 46N, R3W, ASHLAND COUNTY



- POTENTIAL FLOOD IMPACTS**

  - AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT
- MODELED FLOOD DEPTH**

100 YR 500 YR
- CRITICAL FACILITIES**



  - EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT
- BASE FEATURES**

  - U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY




# REGIONAL FLOOD STUDY

## T45 & 46N, R2W, ASHLAND COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY




# REGIONAL FLOOD STUDY

## T43 & 44N, R4W, ASHLAND COUNTY



- |   |   |  |  |
|---|---|--|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background-color: #0000FF; margin-right: 5px;"></div> 100 YR             <div style="width: 20px; height: 20px; background-color: #800080; margin-left: 10px; margin-right: 5px;"></div> 500 YR </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|--|--|






# REGIONAL FLOOD STUDY

## T43 & 44N, R3W, ASHLAND COUNTY

C. MELLE



- POTENTIAL FLOOD IMPACTS**



  - AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT
- MODELED FLOOD DEPTH**

100 YR 500 YR
- CRITICAL FACILITIES**

  - EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT
- BASE FEATURES**

  - U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY







- | POTENTIAL FLOOD IMPACTS  | MODELED FLOOD DEPTH   | CRITICAL FACILITIES   | BASE FEATURES   |
|--|---|---|---|
| <ul style="list-style-type: none"><li>● AGRICULTURE</li><li>● COMMERCIAL</li><li>● RESIDENTIAL</li><li>● GOVERNMENT</li><li>● INDUSTRIAL</li><li>● EDUCATIONAL</li><li>● OTHER</li></ul> | <ul style="list-style-type: none"><li>100 YR</li><li>500 YR</li></ul> | <ul style="list-style-type: none"><li>■ EDUCATION</li><li>■ COUNTY GOVERNMENT CENTER</li><li>■ FIRE &amp; EMS</li><li>■ HOSPITAL</li><li>■ LAW ENFORCEMENT</li><li>■ LOCAL GOVERNMENT</li><li>⚡ SUBSTATION</li><li>◆ WASTEWATER TREATMENT</li></ul> | <ul style="list-style-type: none"><li>— U.S. HIGHWAY</li><li>— STATE HIGHWAY</li><li>— COUNTY HIGHWAY</li><li>— LOCAL ROADS</li><li>— STREETS</li><li>— RIVERS &amp; STREAMS</li><li>— LAKES</li><li>— CITIES &amp; VILLAGES</li><li>— TOWNS</li><li>— COUNTY</li></ul> |
| <ul style="list-style-type: none"><li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li><li>— POSSIBLE IMPACT SEGMENT</li></ul>   |   |   |   |




# REGIONAL FLOOD STUDY

## T43N, RIW, ASHLAND COUNTY

T. ANDERSON



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## T41 & 42N, R4W, ASHLAND COUNTY





- |   |   |   |  |
|---|---|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background-color: #000080; margin-right: 5px;"></div> 100 YR             <div style="width: 20px; height: 20px; background-color: #800080; margin-left: 10px; margin-right: 5px;"></div> 500 YR </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|---|--|



# REGIONAL FLOOD STUDY

## T41 & 42N, R3W, ASHLAND COUNTY





- |   |   |   |  |
|---|---|---|--|
| <p><b>POTENTIAL FLOOD IMPACTS</b></p> <ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <p><b>MODELED FLOOD DEPTH</b></p> <div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background-color: #000080; margin-right: 5px;"></div> 100 YR             <div style="width: 20px; height: 20px; background-color: #800080; margin-left: 10px; margin-right: 5px;"></div> 500 YR </div> | <p><b>CRITICAL FACILITIES</b></p> <ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <p><b>BASE FEATURES</b></p> <ul style="list-style-type: none"> <li>▬ U.S. HIGHWAY</li> <li>▬ STATE HIGHWAY</li> <li>▬ COUNTY HIGHWAY</li> <li>▬ LOCAL ROADS</li> <li>▬ STREETS</li> <li>▬ RIVERS &amp; STREAMS</li> <li>▬ LAKES</li> <li>▬ CITIES &amp; VILLAGES</li> <li>▬ TOWNS</li> <li>▬ COUNTY</li> </ul> |
|---|---|---|--|




# REGIONAL FLOOD STUDY

## T41 & 42N, R2W, ASHLAND COUNTY




- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT


- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY






# REGIONAL FLOOD STUDY

## T41 & 42N, RIW, ASHLAND COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## T41 & 42N, R1E, ASHLAND COUNTY




- |   |  |   |  |
|---|--|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background: linear-gradient(to top, blue, purple); margin-right: 5px;"></div> <div style="text-align: center;">             100 YR<br/>500 YR </div> </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|--|---|--|



# REGIONAL FLOOD STUDY

## CITY OF ASHLAND, ASHLAND COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:42,690

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ↗ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES


- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY

# REGIONAL FLOOD STUDY

## VILLAGE OF BUTTERNUT, ASHLAND COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:13,780

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ↗ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES


- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY CITY OF MELLEN, ASHLAND COUNTY




NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY  
HAZUS

N  
1:11,040

## POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

## MODELED FLOOD DEPTH



## CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

## BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY

## BAYFIELD COUNTY

### HAZUS 100-YEAR FLOOD LOSS ESTIMATES - BAYFIELD COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
T. OF BARKSDALE	3	\$ 3,160.00	\$ 1,252.00	\$ -	31
T. OF BARNES	25	\$ 386,859.00	\$ 137,575.00	\$ -	313
T. OF BAYFIELD	2	\$ 30,064.00	\$ 9,891.00	\$ -	17
T. OF BAYVIEW	1	\$ -	\$ -	\$ -	6
T. OF BELL	7	\$ 844.00	\$ 9,553.00	\$ -	44
T. OF CABLE	2	\$ 24,705.00	\$ 8,864.00	\$ -	6
T. OF CLOVER	6	\$ 32,384.00	\$ 11,146.00	\$ -	44
T. OF DELTA	2	\$ 54,462.00	\$ 17,211.00	\$ -	15
T. OF DRUMMOND	8	\$ 127,962.00	\$ 47,133.00	\$ -	84
T. OF GRAND VIEW	3	\$ 15,400.00	\$ 4,026.00	\$ -	36
T. OF IRON RIVER	2	\$ 28,498.00	\$ 12,049.00	\$ -	20
T. OF KELLY	1	\$ 18,585.00	\$ 14,018.00	\$ -	27
T. OF KEYSTONE	1	\$ 1,680.00	\$ 161.00	\$ -	41
T. OF LINCOLN	7	\$ 33,580.00	\$ 12,866.00	\$ -	48
T. OF ORIENTA	2	\$ 15,115.00	\$ 6,402.00	\$ -	44
T. OF PORT WING	5	\$ 16,898.00	\$ 6,698.00	\$ -	360
V. OF MASON	1	\$ 6,580.00	\$ 41,904.00	\$ -	3
<b>GRAND TOTAL</b>	<b>78</b>	<b>\$ 796,776.00</b>	<b>\$ 340,749.00</b>	<b>\$ -</b>	<b>1,139</b>



## HAZUS 500-YEAR FLOOD LOSS ESTIMATES - BAYFIELD COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
T. OF BARKSDALE	3	\$ 3,160.00	\$ 1,245.00	\$ 0	31
T. OF BARNES	37	\$ 777,918.00	\$ 271,633.00	\$ 0	718
T. OF BAYFIELD	4	\$ 66,238.00	\$ 21,015.00	\$ 0	40
T. OF BAYVIEW	2	\$ 0	\$ 0	\$ 0	18
T. OF BELL	9	\$ 2,785.00	\$ 19,087.00	\$ 0	46
T. OF CABLE	4	\$ 45,260.00	\$ 20,142.00	\$ 0	25
T. OF CLOVER	7	\$ 40,251.00	\$ 12,818.00	\$ 0	49
T. OF DELTA	3	\$ 84,348.00	\$ 27,697.00	\$ 0	19
T. OF DRUMMOND	12	\$ 197,339.00	\$ 66,737.00	\$ 0	121
T. OF EILEEN	1	\$ 490.00	\$ 980.00	\$ 207.00	4
T. OF GRAND VIEW	4	\$ 17,950.00	\$ 6,897.00	\$ 0	54
T. OF IRON RIVER	5	\$ 247,964.00	\$ 66,407.00	\$ 0	142
T. OF KELLY	1	\$ 21,468.00	\$ 18,015.00	\$ 0	27
T. OF KEYSTONE	1	\$ 1,680.00	\$ 161.00	\$ 0	41
T. OF LINCOLN	7	\$ 60,070.00	\$ 18,486.00	\$ 0	57
T. OF NAMAKAGON	2	\$ 0	\$ 0	\$ 0	22
T. OF ORIENTA	2	\$ 5,680.00	\$ 2,304.00	\$ 0	31
T. OF DULU	1	\$ 0	\$ 0	\$ 0	2
T. OF PORT WING	7	\$ 23,871.00	\$ 8,798.00	\$ 0	372
T. OF TRIPP	1	\$ 6,236.00	\$ 2,268.00	\$ 0	26
V. OF MASON	1	\$ 7,326.00	\$ 47,000.00	\$ 0	3
<b>GRAND TOTAL</b>	<b>114</b>	<b>\$ 1,610,034.00</b>	<b>\$ 611,690.00</b>	<b>\$ 207.00</b>	<b>1848</b>




# REGIONAL FLOOD STUDY

## T51 & 52N, R3, 4 & 5W, BAYFIELD COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT




- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - DAM
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## T49 & 50N, R9W, BAYFIELD COUNTY



**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**  
HAZUS

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- SUBSTATION
- WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T49 & 50N, R8W, BAYFIELD COUNTY



**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**

**HAZUS**




1:76,990

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T49 & 50N, R7W, BAYFIELD COUNTY



**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**  
HAZUS



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY


## T49, 50 & 51N, R6W, BAYFIELD COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY




# REGIONAL FLOOD STUDY

## T49, 50 & 51N, R5W, BAYFIELD COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## T48, 49 & 50N, R4W, BAYFIELD COUNTY





- |   |   |   |  |
|---|---|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 100px; background: linear-gradient(to top, blue, purple); margin-right: 5px;"></div> <div style="text-align: center;">             100 YR<br/>500 YR           </div> </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|---|--|



# REGIONAL FLOOD STUDY

## T47 & 48N, R9W, BAYFIELD COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- SUBSTATION
- WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY




# REGIONAL FLOOD STUDY

## T47 & 48N, R8W, BAYFIELD COUNTY




- |   |   |  |  |
|---|---|--|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background-color: #000080; margin-right: 5px;"></div> 100 YR<br/> <div style="width: 20px; height: 20px; background-color: #800080; margin-right: 5px;"></div> 500 YR </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>■ SUBSTATION</li> <li>■ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|--|--|






**REGIONAL FLOOD STUDY**  
T47 & 48N, R7W, BAYFIELD COUNTY




- |   |   |   |   |
|---|---|---|---|
| <b>POTENTIAL FLOOD IMPACTS</b>  | <b>MODELED FLOOD DEPTH</b>  | <b>CRITICAL FACILITIES</b>  | <b>BASE FEATURES</b>  |
| <ul style="list-style-type: none"><li>● AGRICULTURE</li><li>● COMMERCIAL</li><li>● RESIDENTIAL</li><li>● GOVERNMENT</li><li>● INDUSTRIAL</li><li>● EDUCATIONAL</li><li>● OTHER</li><li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li><li>▬ POSSIBLE IMPACT SEGMENT</li></ul> | <ul style="list-style-type: none"><li>100 YR</li><li>500 YR</li></ul> | <ul style="list-style-type: none"><li>■ EDUCATION</li><li>■ COUNTY GOVERNMENT CENTER</li><li>■ FIRE &amp; EMS</li><li>■ HOSPITAL</li><li>■ LAW ENFORCEMENT</li><li>■ LOCAL GOVERNMENT</li><li>▲ DAM</li><li>⚡ SUBSTATION</li><li>◆ WASTEWATER TREATMENT</li></ul> | <ul style="list-style-type: none"><li>▬ U.S. HIGHWAY</li><li>▬ STATE HIGHWAY</li><li>▬ COUNTY HIGHWAY</li><li>▬ LOCAL ROADS</li><li>▬ STREETS</li><li>▬ RIVERS &amp; STREAMS</li><li>▬ LAKES</li><li>▬ CITIES &amp; VILLAGES</li><li>▬ TOWNS</li><li>▬ COUNTY</li></ul> |



[illegible]

- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - DAM
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
-  U.S. HIGHWAY
  -  STATE HIGHWAY
  -  COUNTY HIGHWAY
  -  LOCAL ROADS
  -  STREETS
  -  RIVERS & STREAMS
  -  LAKES
  -  CITIES & VILLAGES
  -  TOWNS
  -  COUNTY





# REGIONAL FLOOD STUDY T47 & 48N, R5W, BAYFIELD COUNTY




- |   |  |   |  |
|---|--|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><ul style="list-style-type: none"> <li>100 YR</li> <li>500 YR</li> </ul> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|--|---|--|






- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ➔ POSSIBLE IMPACT SEGMENT
- MODELED FLOOD DEPTH**
- 100 YR
  - 500 YR
- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT
- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY





# REGIONAL FLOOD STUDY

## T45 & 46N, R8W, BAYFIELD COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH





### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- SUBSTATION
- WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY





**POTENTIAL FLOOD IMPACTS**

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

**MODELED FLOOD DEPTH**

100 YR 500 YR


**CRITICAL FACILITIES**

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

**BASE FEATURES**


- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY






# REGIONAL FLOOD STUDY

## T45 & 46N, R6W, BAYFIELD COUNTY




- | POTENTIAL FLOOD IMPACTS   | MODELED FLOOD DEPTH   | CRITICAL FACILITIES   | BASE FEATURES   |
|---|---|---|---|
| <ul style="list-style-type: none"><li>● AGRICULTURE</li><li>● COMMERCIAL</li><li>● RESIDENTIAL</li><li>● GOVERNMENT</li><li>● INDUSTRIAL</li><li>● EDUCATIONAL</li><li>● OTHER</li><li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li><li>▨ POSSIBLE IMPACT SEGMENT</li></ul> | <ul style="list-style-type: none"><li>100 YR</li><li>500 YR</li></ul> | <ul style="list-style-type: none"><li>■ EDUCATION</li><li>■ COUNTY GOVERNMENT CENTER</li><li>■ FIRE &amp; EMS</li><li>■ HOSPITAL</li><li>■ LAW ENFORCEMENT</li><li>■ LOCAL GOVERNMENT</li><li>⚡ SUBSTATION</li><li>◆ WASTEWATER TREATMENT</li></ul> | <ul style="list-style-type: none"><li>▬ U.S. HIGHWAY</li><li>▬ STATE HIGHWAY</li><li>▬ COUNTY HIGHWAY</li><li>▬ LOCAL ROADS</li><li>▬ STREETS</li><li>▬ RIVERS &amp; STREAMS</li><li>▬ LAKES</li><li>▬ CITIES &amp; VILLAGES</li><li>▬ TOWNS</li><li>▬ COUNTY</li></ul> |






# REGIONAL FLOOD STUDY

## T45 & 46N, R5W, BAYFIELD COUNTY



**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**  
**HAZUS**  
MAPPING TOOL V. 2.2

- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▬ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## T43 & 44N, R9W, BAYFIELD COUNTY




<b>POTENTIAL FLOOD IMPACTS</b> <ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul>	<b>MODELED FLOOD DEPTH</b> <div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background-color: #000080; margin-right: 5px;"></div> 100 YR             <div style="width: 20px; height: 20px; background-color: #800080; margin-left: 10px; margin-right: 5px;"></div> 500 YR </div>	<b>CRITICAL FACILITIES</b> <ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul>	<b>BASE FEATURES</b> <ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul>
---	---	---	--



# REGIONAL FLOOD STUDY

## T43 & 44N, R8W, BAYFIELD COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- SUBSTATION
- WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T43 & 44N, R7W, BAYFIELD COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- POSSIBLE ROAD/BRIDGE IMPACT AREA
- ~ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T43 & 44N, R6W, BAYFIELD COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T43 & 44N, R5W, BAYFIELD COUNTY




- |   |  |  |  |
|---|--|--|--|
| <p><b>POTENTIAL FLOOD IMPACTS</b></p> <ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <p><b>MODELED FLOOD DEPTH</b></p> <div style="display: flex; align-items: center;"> <div style="width: 20px; height: 100px; background: linear-gradient(to top, blue, purple);"></div> <div style="margin-left: 5px;"> <p>100 YR</p> <p>500 YR</p> </div> </div> | <p><b>CRITICAL FACILITIES</b></p> <ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>⚡ SUBSTATION</li> <li>💧 WASTEWATER TREATMENT</li> </ul> | <p><b>BASE FEATURES</b></p> <ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|--|--|--|



# REGIONAL FLOOD STUDY

## CITY OF BAYFIELD, BAYFIELD COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY


HAZUS

N  
1:9,000

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▬ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES


- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- ▬ U.S. HIGHWAY
- ▬ STATE HIGHWAY
- ▬ COUNTY HIGHWAY
- ▬ LOCAL ROADS
- ▬ STREETS
- ▬ RIVERS & STREAMS
- ▬ LAKES
- ▬ CITIES & VILLAGES
- ▬ TOWNS
- ▬ COUNTY

# REGIONAL FLOOD STUDY

## VILLAGE OF MASON, BAYFIELD COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY


HAZUS

N  
1:8,280

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## CITY OF WASHBURN, BAYFIELD COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY


HAZUS



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY

## BURNETT COUNTY

### HAZUS 100-YEAR FLOOD LOSS ESTIMATES - BURNETT COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
T. OF ANDERSON	2	\$ 52,889.00	\$ 15,732.00	\$ -	19
T. OF BLAINE	3	\$ 76,410.00	\$ 22,371.00	\$ -	14
T. OF DANIELS	17	\$ 334,046.00	\$ 139,606.00	\$ 31,034.00	215
T. OF DEWEY	3	\$ 73,699.00	\$ 22,561.00	\$ -	20
T. OF GRANTSBURG	6	\$ 79,290.00	\$ 42,726.00	\$ -	41
T. OF JACKSON	1	\$ 3,080.00	\$ 848.00	\$ -	15
T. OF LA FOLLETTE	7	\$ 95,250.00	\$ 30,262.00	\$ -	47
T. OF LINCOLN	4	\$ 31,426.00	\$ 11,021.00	\$ -	51
T. OF MEENON	24	\$ 441,722.00	\$ 202,826.00	\$ -	227
T. OF OAKLAND	10	\$ 243,533.00	\$ 89,340.00	\$ -	74
T. OF ROOSEVELT	2	\$ 3,039.00	\$ 755.00	\$ -	9
T. OF RUSK	3	\$ 190,444.00	\$ 84,858.00	\$ -	371
T. OF SAND LAKE	2	\$ 14,680.00	\$ 2,631.00	\$ -	18
T. OF SIREN	13	\$ 304.00	\$ 557.00	\$ -	54
T. OF SWISS	3	\$ 32,077.00	\$ 63,298.00	\$ -	21
T. OF TRADE LAKE	25	\$ 260,784.00	\$ 155,163.00	\$ -	177
T. OF UNION	4	\$ 71,090.00	\$ 31,156.00	\$ -	62
T. OF WEBB LAKE	3	\$ 13,440.00	\$ 1,215.00	\$ -	24
T. OF WOOD RIVER	3	\$ 851.00	\$ 344.00	\$ -	11
V. OF GRANTSBURG	3	\$ 16,832.00	\$ 6,074.00	\$ -	38
<b>GRAND TOTAL</b>	<b>138</b>	<b>\$ 2,034,886.00</b>	<b>\$ 923,344.00</b>	<b>\$ 31,034.00</b>	<b>1,508</b>





## HAZUS 500-YEAR FLOOD LOSS ESTIMATES - BURNETT COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
T. OF ANDERSON	3	\$ 55,845.00	\$ 16,428.00	\$ -	31
T. OF BLAINE	3	\$ 86,663.00	\$ 24,475.00	\$ -	19
T. OF DANIELS	20	\$ 367,347.00	\$ 157,089.00	\$ 39,815.00	263
T. OF DEWEY	3	\$ 77,503.00	\$ 23,469.00	\$ -	20
T. OF GRANTSBURG	8	\$ 207,878.00	\$ 87,262.00	\$ -	155
T. OF JACKSON	1	\$ 3,080.00	\$ 1,131.00	\$ -	15
T. OF LA FOLLETTE	7	\$ 149,945.00	\$ 45,669.00	\$ -	55
T. OF LINCOLN	4	\$ 45,420.00	\$ 16,956.00	\$ -	51
T. OF MEENON	29	\$ 634,770.00	\$ 481,258.00	\$ -	304
T. OF OAKLAND	12	\$ 304,648.00	\$ 110,214.00	\$ -	91
T. OF ROOSEVELT	1	\$ -	\$ -	\$ -	6
T. OF RUSK	7	\$ 209,604.00	\$ 90,125.00	\$ -	397
T. OF SAND LAKE	4	\$ 31,066.00	\$ 12,261.00	\$ -	26
T. OF SCOTT	1	\$ 6,806.00	\$ 2,674.00	\$ -	9
T. OF SIREN	25	\$ 7,771.00	\$ 4,778.00	\$ -	135
T. OF SWISS	6	\$ 64,238.00	\$ 75,859.00	\$ -	51
T. OF TRADE LAKE	28	\$ 344,636.00	\$ 192,624.00	\$ -	201
T. OF UNION	6	\$ 113,355.00	\$ 42,411.00	\$ -	78
T. OF WEBB LAKE	6	\$ 25,048.00	\$ 50,903.00	\$ -	37
T. OF WOOD RIVER	3	\$ 6,725.00	\$ 3,173.00	\$ -	11
V. OF GRANTSBURG	3	\$ 24,770.00	\$ 10,625.00	\$ -	38
<b>GRAND TOTAL</b>	<b>180</b>	<b>\$ 2,767,118.00</b>	<b>\$ 1,449,384.00</b>	<b>\$ 39,815.00</b>	<b>1,993</b>

# REGIONAL FLOOD STUDY

T41 & 42N, R16 & 17W, BURNETT COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS

## POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

## MODELED FLOOD DEPTH




## CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

## BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY






# REGIONAL FLOOD STUDY

## T41 & 42N, R15W, BURNETT COUNTY

Minnesota



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- SUBSTATION
- WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T41 & 42N, R14W, BURNETT COUNTY





- |   |  |   |  |
|---|--|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><ul style="list-style-type: none"> <li>100 YR</li> <li>500 YR</li> </ul> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|--|---|--|



# REGIONAL FLOOD STUDY

T39 & 40N, R19W, BURNETT COUNTY



**POTENTIAL FLOOD IMPACTS**

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

**MODELED FLOOD DEPTH**

100 YR 500 YR

**CRITICAL FACILITIES**



- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

**BASE FEATURES**


- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY

# REGIONAL FLOOD STUDY

## T39 & 40N, R18W, BURNETT COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY




# REGIONAL FLOOD STUDY

## T39 & 40N, R17W, BURNETT COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



T. SWISS

# REGIONAL FLOOD STUDY

## T39 & 40N, R16W, BURNETT COUNTY

T. UNION

T. OAKLAND

T. JACKSON

V. WEBSTER


T. LINCOLN

T. MEENON


T. SAND LAKE

T. SIREN

T. LA FOLLETTE



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▬ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY




# REGIONAL FLOOD STUDY T39 & 40N, R15W, BURNETT COUNTY



**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**  
**HAZUS**

- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▬ POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT




- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY









REGIONAL FLOOD STUDY  
T37 & 38N, R20W, BURNETT COUNTY





# REGIONAL FLOOD STUDY

## T37 & 38N, R19W, BURNETT COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- ▬ U.S. HIGHWAY
- ▬ STATE HIGHWAY
- ▬ COUNTY HIGHWAY
- ▬ LOCAL ROADS
- ▬ STREETS
- ▬ RIVERS & STREAMS
- ▬ LAKES
- ▬ CITIES & VILLAGES
- ▬ TOWNS
- ▬ COUNTY



# REGIONAL FLOOD STUDY

## T37 & 38N, R18W, BURNETT COUNTY



- ### POTENTIAL FLOOD IMPACTS

  - AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▬ POSSIBLE IMPACT SEGMENT
- ### MODELED FLOOD DEPTH

  - 100 YR
  - 500 YR
- ### CRITICAL FACILITIES



  - EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ⚡ SUBSTATION
  - 💧 WASTEWATER TREATMENT
- ### BASE FEATURES

  - U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY




# REGIONAL FLOOD STUDY

## T38N, R17W, BURNETT COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT






- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY



## T38N, R16W, BURNETT COUNTY







# REGIONAL FLOOD STUDY

## T38N, R15W, BURNETT COUNTY



- |   |   |   |  |
|---|---|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 100px; background: linear-gradient(to top, blue, purple); margin-right: 5px;"></div> <div style="text-align: center;"> <p>100 YR</p> <p>500 YR</p> </div> </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|---|--|





- ### POTENTIAL FLOOD IMPACTS

  - AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT
- ### MODELED FLOOD DEPTH

100 YR 500 YR
- ### CRITICAL FACILITIES


  - EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT
- ### BASE FEATURES

  - U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## VILLAGE OF GRANTSBURG, BURNETT COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:22,130

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- DAM
- SUBSTATION
- WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## VILLAGE OF SIREN, BURNETT COUNTY



**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**  
**HAZUS**




1:17,540

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- POSSIBLE ROAD/BRIDGE IMPACT AREA
- ↗ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES


- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY

# REGIONAL FLOOD STUDY

## VILLAGE OF WEBSTER, BURNETT COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:17,880

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



## DOUGLAS COUNTY

### HAZUS 100-YEAR FLOOD LOSS ESTIMATES - DOUGLAS COUNTY



Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
<b>C. OF SUPERIOR</b>	1	\$ 6,921.00	\$ 53,406.00	\$ -	1
<b>T. OF AMNICON</b>	1	\$ -	\$ -	\$ -	6
<b>T. OF BRULE</b>	4	\$ 79,874.00	\$ 28,370.00	\$ -	48
<b>T. OF CLOVERLAND</b>	1	\$ 12,280.00	\$ 4,545.00	\$ -	12
<b>T. OF DAIRYLAND</b>	2	\$ 1,497.00	\$ 204.00	\$ -	11
<b>T. OF GORDON</b>	11	\$ 148,401.00	\$ 54,252.00	\$ -	120
<b>T. OF HAWTHORNE</b>	2	\$ 2,366.00	\$ 328.00	\$ -	7
<b>T. OF HIGHLAND</b>	9	\$ 171,427.00	\$ 291,975.00	\$ -	61
<b>T. OF LAKESIDE</b>	5	\$ 3,425.00	\$ 1,354.00	\$ -	33
<b>T. OF OAKLAND</b>	2	\$ 1,224.00	\$ 481.00	\$ -	9
<b>T. OF SOLON SPRINGS</b>	7	\$ 22,372.00	\$ 13,894.00	\$ -	42
<b>T. OF SUPERIOR</b>	1	\$ 7,738.00	\$ 44,091.00	\$ -	2
<b>T. OF WASCOTT</b>	11	\$ 121,747.00	\$ 101,514.00	\$ -	85
<b>V. OF LAKE NEBAGAMON</b>	2	\$ 6,988.00	\$ 4,493.00	\$ -	12
<b>V. OF SOLON SPRINGS</b>	8	\$ 58,319.00	\$ 33,413.00	\$ -	57
<b>GRAND TOTAL</b>	<b>67</b>	<b>\$ 644,579.00</b>	<b>\$ 632,320.00</b>	<b>\$ -</b>	<b>506</b>

## HAZUS 500-YEAR FLOOD LOSS ESTIMATES - DOUGLAS COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
<b>T. OF AMNICON</b>	5	\$ 37,647.00	\$ 12,569.00	\$ -	52
<b>T. OF BRULE</b>	6	\$ 125,417.00	\$ 41,279.00	\$ -	90
<b>T. OF CLOVERLAND</b>	1	\$ 18,787.00	\$ 6,224.00	\$ -	12
<b>T. OF DAIRYLAND</b>	4	\$ 19,836.00	\$ 10,735.00	\$ -	16
<b>T. OF GORDON</b>	20	\$ 212,537.00	\$ 76,255.00	\$ -	232
<b>T. OF HAWTHORNE</b>	2	\$ 3,540.00	\$ 492.00	\$ -	7
<b>T. OF HIGHLAND</b>	10	\$ 205,229.00	\$ 331,217.00	\$ -	78
<b>T. OF LAKESIDE</b>	10	\$ 124,559.00	\$ 36,483.00	\$ -	98
<b>T. OF OAKLAND</b>	4	\$ 6,208.00	\$ 2,427.00	\$ -	16
<b>T. OF SOLON SPRINGS</b>	7	\$ 29,223.00	\$ 17,244.00	\$ -	42
<b>T. OF SUPERIOR</b>	1	\$ 3,627.00	\$ 504.00	\$ -	5
<b>T. OF WASCOTT</b>	18	\$ 243,095.00	\$ 91,206.00	\$ -	217
<b>V. OF LAKE NEBAGAMON</b>	2	\$ 12,224.00	\$ 7,415.00	\$ -	12
<b>V. OF OLIVER</b>	1	\$ 1,465.00	\$ 533.00	\$ -	7
<b>V. OF SOLON SPRINGS</b>	8	\$ 69,848.00	\$ 40,444.00	\$ -	57
<b>GRAND TOTAL</b>	<b>100</b>	<b>\$ 1,120,682.00</b>	<b>\$ 733,852.00</b>	<b>\$ -</b>	<b>943</b>



REGIONAL FLOOD STUDY  
T49N, R13, 14 & 15W, DOUGLAS COUNTY




NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY  
HAZUS

POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

MODELED FLOOD DEPTH



CRITICAL FACILITIES



- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY

# REGIONAL FLOOD STUDY

T49N, R10 & 11W, DOUGLAS COUNTY



**POTENTIAL FLOOD IMPACTS**

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

**MODELED FLOOD DEPTH**

100 YR 500 YR

**CRITICAL FACILITIES**

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


**BASE FEATURES**

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T47 & 48N, R15W, DOUGLAS COUNTY



**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**

**HAZUS**




1:85,980

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ⚡ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



Minnesota

V. OLIVER

C. SUPERIOR

V. SUPERIOR

# REGIONAL FLOOD STUDY


T47 & 48N, R14W, DOUGLAS COUNTY

T. PARKLAND

T. SUPERIOR

T. OAKLAND

T. SUMMIT



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY  
HAZUS




1:85,830

## POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

## MODELED FLOOD DEPTH



## CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


## BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T47 & 48N, R13W, DOUGLAS COUNTY



**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**  
HAZUS



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY




# REGIONAL FLOOD STUDY

## T47 & 48N, R12W, DOUGLAS COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▬ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY




# REGIONAL FLOOD STUDY

## T47 & 48N, R11W, DOUGLAS COUNTY





- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY





- | POTENTIAL FLOOD IMPACTS  | MODELED FLOOD DEPTH   | CRITICAL FACILITIES   | BASE FEATURES   |
|--|---|---|---|
| <ul style="list-style-type: none"><li>● AGRICULTURE</li><li>● COMMERCIAL</li><li>● RESIDENTIAL</li><li>● GOVERNMENT</li><li>● INDUSTRIAL</li><li>● EDUCATIONAL</li><li>● OTHER</li></ul> | <ul style="list-style-type: none"><li>100 YR</li><li>500 YR</li></ul> | <ul style="list-style-type: none"><li>■ EDUCATION</li><li>■ COUNTY GOVERNMENT CENTER</li><li>■ FIRE &amp; EMS</li><li>■ HOSPITAL</li><li>■ LAW ENFORCEMENT</li><li>■ LOCAL GOVERNMENT</li><li>▲ DAM</li><li>⚡ SUBSTATION</li><li>◆ WASTEWATER TREATMENT</li></ul> | <ul style="list-style-type: none"><li>— U.S. HIGHWAY</li><li>— STATE HIGHWAY</li><li>— COUNTY HIGHWAY</li><li>— LOCAL ROADS</li><li>— STREETS</li><li>— RIVERS &amp; STREAMS</li><li>— LAKES</li><li>— CITIES &amp; VILLAGES</li><li>— TOWNS</li><li>— COUNTY</li></ul> |
| <ul style="list-style-type: none"><li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li><li>— POSSIBLE IMPACT SEGMENT</li></ul>   |   |   |   |




# REGIONAL FLOOD STUDY

## T45 & 46N, R15W, DOUGLAS COUNTY

Minnesota

Minnesota




NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY  
HAZUS



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY




# REGIONAL FLOOD STUDY

## T45 & 46N, R14W, DOUGLAS COUNTY





- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY







- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT
- MODELED FLOOD DEPTH**
- 100 YR
  - 500 YR
- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT
- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## T45 & 46N, R12W, DOUGLAS COUNTY





- |   |   |   |  |
|---|---|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background-color: #000080; margin-right: 5px;"></div> 100 YR<br/> <div style="width: 20px; height: 20px; background-color: #800080; margin-right: 5px;"></div> 500 YR </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|---|--|



# REGIONAL FLOOD STUDY

## T45 & 46N, R11W, DOUGLAS COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- WASTEWATER TREATMENT

### BASE FEATURES


- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T45 & 46N, R10W, DOUGLAS COUNTY

V. LAKE  
NEBAGAMON




**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**  
HAZUS

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



REGIONAL FLOOD STUDY  
T43 & 44N, R15W, DOUGLAS COUNTY


T. SUMMIT

Minnesota

T. DAIRYLAND

Minnesota

T. BLAINE




NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY  
HAZUS



POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▬ POSSIBLE IMPACT SEGMENT

MODELED FLOOD DEPTH



CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- SUBSTATION
- WASTEWATER TREATMENT

BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



T. SUMMIT

# REGIONAL FLOOD STUDY

T43 & 44N, R14W, DOUGLAS COUNTY



T. GORDON

T. DAIRYLAND

T. WASCOTT


T. BLAINE

T. MINONG




- |   |  |  |  |
|---|--|--|--|
| <p><b>POTENTIAL FLOOD IMPACTS</b></p> <ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <p><b>MODELED FLOOD DEPTH</b></p> <div style="display: flex; align-items: center;"> <div style="width: 20px; height: 40px; background: linear-gradient(to top, blue, purple); margin-right: 5px;"></div> <div style="text-align: center;"> <p>100 YR</p> <p>500 YR</p> </div> </div> | <p><b>CRITICAL FACILITIES</b></p> <ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <p><b>BASE FEATURES</b></p> <ul style="list-style-type: none"> <li>▬ U.S. HIGHWAY</li> <li>▬ STATE HIGHWAY</li> <li>▬ COUNTY HIGHWAY</li> <li>▬ LOCAL ROADS</li> <li>▬ STREETS</li> <li>▬ RIVERS &amp; STREAMS</li> <li>▬ LAKES</li> <li>▬ CITIES &amp; VILLAGES</li> <li>▬ TOWNS</li> <li>▬ COUNTY</li> </ul> |
|---|--|--|--|





# **REGIONAL FLOOD STUDY** **T43 & 44N, R13W, DOUGLAS COUNTY**



- |   |   |  |  |
|---|---|--|--|
| <p><b>POTENTIAL FLOOD IMPACTS</b></p> <ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▬ POSSIBLE IMPACT SEGMENT</li> </ul> | <p><b>MODELED FLOOD DEPTH</b></p> <div style="display: flex; align-items: center;"> <div style="width: 20px; height: 100px; background: linear-gradient(to top, blue, purple); margin-right: 5px;"></div> <div style="text-align: center;"> <p>100 YR</p> <p>500 YR</p> </div> </div> | <p><b>CRITICAL FACILITIES</b></p> <ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>⚡ SUBSTATION</li> <li>💧 WASTEWATER TREATMENT</li> </ul> | <p><b>BASE FEATURES</b></p> <ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|--|--|



# REGIONAL FLOOD STUDY

## T43 & 44N, R12W, DOUGLAS COUNTY



T. SOLON SPRINGS

T. GORDON


T. WASCOTT

T. MINONG

T. FROG CREEK




- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT


- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY






# REGIONAL FLOOD STUDY

## T43 & 44N, R1W, DOUGLAS COUNTY





- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY






- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT
- MODELED FLOOD DEPTH**
- 100 YR
  - 500 YR
- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT
- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## VILLAGE OF LAKE NEBAGAMON, DOUGLAS COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:35,370

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## VILLAGE OF OLIVER, DOUGLAS COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:14,220

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY


## VILLAGE OF POPLAR, DOUGLAS COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY  
HAZUS



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT




- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - DAM
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY

# REGIONAL FLOOD STUDY

## VILLAGE OF SOLON SPRINGS, DOUGLAS COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:15,780

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## CITY OF SUPERIOR, DOUGLAS COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY


HAZUS



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▬ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES


- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY

# REGIONAL FLOOD STUDY

## VILLAGE OF SUPERIOR, DOUGLAS COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY


HAZUS



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ✓ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



## IRON COUNTY

### HAZUS 100-YEAR FLOOD LOSS ESTIMATES - IRON COUNTY



Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
<b>C. OF HURLEY</b>	15	\$ 161,962.00	\$ 313,406.00	\$ 55,712.00	221
<b>C. OF MONTREAL</b>	1	\$ 1,440.00	\$ 353.00	\$ -	12
<b>T. OF ANDERSON</b>	1	\$ 6,840.00	\$ 52.00	\$ -	15
<b>T. OF CAREY</b>	1	\$ 2,806.00	\$ 1,407.00	\$ -	11
<b>T. OF GURNEY</b>	1	\$ 5,669.00	\$ 1,662.00	\$ -	14
<b>T. OF KIMBALL</b>	4	\$ 91,227.00	\$ 121,798.00	\$ 57,969.00	286
<b>T. OF MERCER</b>	12	\$ 123,583.00	\$ 138,339.00	\$ -	67
<b>T. OF OMA</b>	10	\$ 5,856.00	\$ 2,634.00	\$ -	56
<b>GRAND TOTAL</b>	<b>45</b>	<b>\$ 399,383.00</b>	<b>\$ 579,651.00</b>	<b>\$ 113,681.00</b>	<b>682</b>

### HAZUS 500-YEAR FLOOD LOSS ESTIMATES - IRON COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
<b>C. OF HURLEY</b>	5	\$ 33,748.00	\$ 28,777.00	\$ 9,924.00	62
<b>C. OF MONTREAL</b>	1	\$ 5,660.00	\$ 1,936.00	\$ -	12
<b>T. OF CAREY</b>	1	\$ -	\$ -	\$ -	7
<b>T. OF GURNEY</b>	4	\$ 9,031.00	\$ 3,900.00	\$ -	70
<b>T. OF KIMBALL</b>	3	\$ 14,200.00	\$ 8,079.00	\$ -	86
<b>T. OF MERCER</b>	20	\$ 159,628.00	\$ 144,041.00	\$ -	131
<b>T. OF OMA</b>	14	\$ 27,397.00	\$ 10,231.00	\$ -	75
<b>GRAND TOTAL</b>	<b>48</b>	<b>\$ 249,664.00</b>	<b>\$ 196,964.00</b>	<b>\$ 9,924.00</b>	<b>443</b>

# REGIONAL FLOOD STUDY


## T47 & 48N, R1E & 1W, IRON COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- ▬ U.S. HIGHWAY
- ▬ STATE HIGHWAY
- ▬ COUNTY HIGHWAY
- ▬ LOCAL ROADS
- ▬ STREETS
- ▬ RIVERS & STREAMS
- ▬ LAKES
- ▬ CITIES & VILLAGES
- ▬ TOWNS
- ▬ COUNTY



# REGIONAL FLOOD STUDY

## T45 & 46N, RIW, IRON COUNTY





- |   |   |  |  |
|---|---|--|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background-color: #000080; margin-right: 5px;"></div> 100 YR             <div style="width: 20px; height: 20px; background-color: #800080; margin-left: 10px; margin-right: 5px;"></div> 500 YR </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|--|--|




# REGIONAL FLOOD STUDY

## T45 & 46N, RIE, IRON COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



REGIONAL FLOOD STUDY  
T4S, 46 & 47N, R2E, IRON COUNTY



**POTENTIAL FLOOD IMPACTS**

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

**MODELED FLOOD DEPTH**

100 YR 500 YR

**CRITICAL FACILITIES**

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- DAM
- SUBSTATION
- WASTEWATER TREATMENT




**BASE FEATURES**

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## T45 & 46N, R3E, IRON COUNTY








# REGIONAL FLOOD STUDY

## T44N, RIW, IRON COUNTY

77



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY T43 & 44N, R1E, IRON COUNTY





- |   |  |   |  |
|---|--|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▬ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 100px; background: linear-gradient(to top, blue, purple);"></div> <div style="margin-left: 5px;">             100 YR<br/>500 YR           </div> </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|--|---|--|




# REGIONAL FLOOD STUDY

## T43 & 44N, R2E, IRON COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT



- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY


## T43 & 44N, R3E, IRON COUNTY

Michigan




- |   |   |   |  |
|---|---|---|--|
| <p><b>POTENTIAL FLOOD IMPACTS</b></p> <ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▬ POSSIBLE IMPACT SEGMENT</li> </ul> | <p><b>MODELED FLOOD DEPTH</b></p> <p>100 YR 500 YR</p> <p>Legend for flood depth: Blue for 100-year flood, Purple for 500-year flood.</p> | <p><b>CRITICAL FACILITIES</b></p> <ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <p><b>BASE FEATURES</b></p> <ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|---|---|--|



[illegible]



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▬ POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - DAM
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY






- |   |   |   |   |
|---|---|---|---|
| <b>POTENTIAL FLOOD IMPACTS</b>  | <b>MODELED FLOOD DEPTH</b>  | <b>CRITICAL FACILITIES</b>  | <b>BASE FEATURES</b>  |
| <ul style="list-style-type: none"><li>● AGRICULTURE</li><li>● COMMERCIAL</li><li>● RESIDENTIAL</li><li>● GOVERNMENT</li><li>● INDUSTRIAL</li><li>● EDUCATIONAL</li><li>● OTHER</li><li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li><li>▨ POSSIBLE IMPACT SEGMENT</li></ul> | <ul style="list-style-type: none"><li>100 YR</li><li>500 YR</li></ul> | <ul style="list-style-type: none"><li>■ EDUCATION</li><li>■ COUNTY GOVERNMENT CENTER</li><li>■ FIRE &amp; EMS</li><li>■ HOSPITAL</li><li>■ LAW ENFORCEMENT</li><li>■ LOCAL GOVERNMENT</li><li>⚡ SUBSTATION</li><li>◆ WASTEWATER TREATMENT</li></ul> | <ul style="list-style-type: none"><li>— U.S. HIGHWAY</li><li>— STATE HIGHWAY</li><li>— COUNTY HIGHWAY</li><li>— LOCAL ROADS</li><li>— STREETS</li><li>— RIVERS &amp; STREAMS</li><li>— LAKES</li><li>— CITIES &amp; VILLAGES</li><li>— TOWNS</li><li>— COUNTY</li></ul> |




**REGIONAL FLOOD STUDY**  
T41 & 42N, R3E, IRON COUNTY

The map displays flood zones in blue and pink, with various lakes and rivers labeled. Key locations include T. Mercer and T. Sherman. Roads are marked with numbers like 51, 47, 182, and 182. The map is bordered by Price County to the south and Vilas County to the east.



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - DAM
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
-  U.S. HIGHWAY
  -  STATE HIGHWAY
  -  COUNTY HIGHWAY
  -  LOCAL ROADS
  -  STREETS
  -  RIVERS & STREAMS
  -  LAKES
  -  CITIES & VILLAGES
  -  TOWNS
  -  COUNTY




# REGIONAL FLOOD STUDY

## T41 & 42N, R4E, IRON COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT




- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## CITY OF HURLEY, IRON COUNTY




**NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY**  
**HAZUS**  
v2.1



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES


- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY

# REGIONAL FLOOD STUDY

## CITY OF MONTREAL, IRON COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY


HAZUS



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▬ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



## SAWYER COUNTY



### HAZUS 100-YEAR FLOOD LOSS ESTIMATES - SAWYER COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
C. OF HAYWARD	74	\$ 737,521.00	\$ 1,198,313.00	\$ 54,855.00	1,148
T. OF BASS LAKE	17	\$ 217,456.00	\$ 132,725.00	\$ -	79
T. OF COUDERAY	10	\$ 124,348.00	\$ 52,225.00	\$ -	238
T. OF DRAPER	27	\$ 423,219.00	\$ 225,693.00	\$ -	396
T. OF EDGEWATER	1	\$ 12,699.00	\$ 4,590.00	\$ -	22
T. OF HAYWARD	54	\$ 1,431,369.00	\$ 1,085,157.00	\$ 150,064.00	799
T. OF HUNTER	22	\$ 278,549.00	\$ 359,083.00	\$ -	196
T. OF LENROOT	8	\$ 219,409.00	\$ 114,158.00	\$ -	146
T. OF DJIBWA	65	\$ 1,625,699.00	\$ 1,046,697.00	\$ -	1,166
T. OF RADISSON	28	\$ 578,273.00	\$ 630,180.00	\$ -	365
T. OF ROUND LAKE	19	\$ 291,070.00	\$ 171,627.00	\$ -	207
T. OF SAND LAKE	1	\$ 21,721.00	\$ 6,400.00	\$ -	35
T. OF SPIDER LAKE	10	\$ 185,065.00	\$ 81,159.00	\$ -	189
T. OF WEIRGOR	32	\$ 961,916.00	\$ 445,413.00	\$ -	715
T. OF WINTER	24	\$ 522,158.00	\$ 291,376.00	\$ -	268
V. OF COUDERAY	1	\$ 3,533.00	\$ 2,370.00	\$ -	18
V. OF EXELAND	3	\$ 6,831.00	\$ 20,223.00	\$ -	14
<b>GRAND TOTAL</b>	<b>396</b>	<b>\$ 7,640,836.00</b>	<b>\$ 5,867,389.00</b>	<b>\$ 204,919.00</b>	<b>6,001</b>

## HAZUS 500-YEAR FLOOD LOSS ESTIMATES - SAWYER COUNTY


Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
<b>C. OF HAYWARD</b>	89	\$ 1,078,738.00	\$ 2,090,656.00	\$ 99,341.00	1,259
<b>T. OF BASS LAKE</b>	21	\$ 790,190.00	\$ 448,629.00	\$ -	163
<b>T. OF COUDERAY</b>	10	\$ 139,435.00	\$ 55,820.00	\$ -	271
<b>T. OF DRAPER</b>	30	\$ 492,648.00	\$ 256,883.00	\$ -	444
<b>T. OF EDGEWATER</b>	5	\$ 101,125.00	\$ 83,522.00	\$ -	1,665
<b>T. OF HAYWARD</b>	59	\$ 1,562,087.00	\$ 1,070,954.00	\$ 219,068.00	916
<b>T. OF HUNTER</b>	22	\$ 350,745.00	\$ 471,898.00	\$ -	216
<b>T. OF LENROOT</b>	11	\$ 260,454.00	\$ 135,519.00	\$ -	205
<b>T. OF DJIBWA</b>	77	\$ 3,290,933.00	\$ 1,874,476.00	\$ -	4,188
<b>T. OF RADISSON</b>	40	\$ 1,104,390.00	\$ 958,279.00	\$ -	903
<b>T. OF ROUND LAKE</b>	32	\$ 434,130.00	\$ 245,134.00	\$ -	389
<b>T. OF SAND LAKE</b>	1	\$ 20,748.00	\$ 6,319.00	\$ -	35
<b>T. OF SPIDER LAKE</b>	11	\$ 225,678.00	\$ 101,805.00	\$ -	200
<b>T. OF WEIRGOR</b>	34	\$ 1,251,924.00	\$ 574,025.00	\$ -	805
<b>T. OF WINTER</b>	29	\$ 757,348.00	\$ 451,975.00	\$ -	363
<b>V. OF COUDERAY</b>	1	\$ 5,669.00	\$ 3,663.00	\$ -	18
<b>V. OF EXELAND</b>	3	\$ 8,535.00	\$ 28,266.00	\$ -	14
<b>GRAND TOTAL</b>	<b>475</b>	<b>\$ 11,874,777.00</b>	<b>\$ 8,857,823.00</b>	<b>\$ 318,409.00</b>	<b>12,054</b>






<p><b>POTENTIAL FLOOD IMPACTS</b></p> <ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▬ POSSIBLE IMPACT SEGMENT</li> </ul>	<p><b>MODELED FLOOD DEPTH</b></p> <p>100 YR 500 YR</p>	<p><b>CRITICAL FACILITIES</b></p> <ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul>	<p><b>BASE FEATURES</b></p> <ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul>
---	--	---	--





**REGIONAL FLOOD STUDY**  
**T41 & 42N, R8W, SAWYER COUNTY**




- |   |   |   |   |
|---|---|---|---|
| <b>POTENTIAL FLOOD IMPACTS</b>  | <b>MODELED FLOOD DEPTH</b>  | <b>CRITICAL FACILITIES</b>  | <b>BASE FEATURES</b>  |
| <ul style="list-style-type: none"><li>● AGRICULTURE</li><li>● COMMERCIAL</li><li>● RESIDENTIAL</li><li>● GOVERNMENT</li><li>● INDUSTRIAL</li><li>● EDUCATIONAL</li><li>● OTHER</li><li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li><li>▨ POSSIBLE IMPACT SEGMENT</li></ul> | <ul style="list-style-type: none"><li>100 YR</li><li>500 YR</li></ul> | <ul style="list-style-type: none"><li>■ EDUCATION</li><li>■ COUNTY GOVERNMENT CENTER</li><li>■ FIRE &amp; EMS</li><li>■ HOSPITAL</li><li>■ LAW ENFORCEMENT</li><li>■ LOCAL GOVERNMENT</li><li>⚡ SUBSTATION</li><li>◆ WASTEWATER TREATMENT</li></ul> | <ul style="list-style-type: none"><li>— U.S. HIGHWAY</li><li>— STATE HIGHWAY</li><li>— COUNTY HIGHWAY</li><li>— LOCAL ROADS</li><li>— STREETS</li><li>— RIVERS &amp; STREAMS</li><li>— LAKES</li><li>— CITIES &amp; VILLAGES</li><li>— TOWNS</li><li>— COUNTY</li></ul> |



# REGIONAL FLOOD STUDY


## T41 & 42N, R7W, SAWYER COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ♦ WASTEWATER TREATMENT

### BASE FEATURES



- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



T. CABLE

# REGIONAL FLOOD STUDY


T41 & 42N, R6W, SAWYER COUNTY



## POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

## MODELED FLOOD DEPTH



## CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- 💧 WASTEWATER TREATMENT



## BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY




# REGIONAL FLOOD STUDY

## T41 & 42N, R5W, SAWYER COUNTY




- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT


- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY





# REGIONAL FLOOD STUDY

## T39 & 40N, R9W, SAWYER COUNTY





- | POTENTIAL FLOOD IMPACTS  | MODELED FLOOD DEPTH   | CRITICAL FACILITIES   | BASE FEATURES   |
|--|---|---|---|
| <ul style="list-style-type: none"><li>● AGRICULTURE</li><li>● COMMERCIAL</li><li>● RESIDENTIAL</li><li>● GOVERNMENT</li><li>● INDUSTRIAL</li><li>● EDUCATIONAL</li><li>● OTHER</li></ul> | <ul style="list-style-type: none"><li>100 YR</li><li>500 YR</li></ul> | <ul style="list-style-type: none"><li>■ EDUCATION</li><li>■ COUNTY GOVERNMENT CENTER</li><li>■ FIRE &amp; EMS</li><li>■ HOSPITAL</li><li>■ LAW ENFORCEMENT</li><li>■ LOCAL GOVERNMENT</li><li>▲ DAM</li><li>⚡ SUBSTATION</li><li>◆ WASTEWATER TREATMENT</li></ul> | <ul style="list-style-type: none"><li>▬ U.S. HIGHWAY</li><li>▬ STATE HIGHWAY</li><li>▬ COUNTY HIGHWAY</li><li>▬ LOCAL ROADS</li><li>▬ STREETS</li><li>▬ RIVERS &amp; STREAMS</li><li>▬ LAKES</li><li>▬ CITIES &amp; VILLAGES</li><li>▬ TOWNS</li><li>▬ COUNTY</li></ul> |
| <ul style="list-style-type: none"><li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li><li>▬ POSSIBLE IMPACT SEGMENT</li></ul>   |   |   |   |



# REGIONAL FLOOD STUDY

## T39 & 40N, R8W, SAWYER COUNTY





- |   |  |  |  |
|---|--|--|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▬ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 100px; background: linear-gradient(to top, blue, purple);"></div> <div style="margin-left: 5px;">             100 YR<br/>500 YR           </div> </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|--|--|--|



# REGIONAL FLOOD STUDY


## T39 & 40N, R7W, SAWYER COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH




### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES


- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY







# REGIONAL FLOOD STUDY

## T39 & 40N, R6W, SAWYER COUNTY



- |   |  |   |  |
|---|--|---|--|
| <p><b>POTENTIAL FLOOD IMPACTS</b></p> <ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▬ POSSIBLE IMPACT SEGMENT</li> </ul> | <p><b>MODELED FLOOD DEPTH</b></p> <div style="display: flex; align-items: center;"> <div style="width: 20px; height: 100px; background: linear-gradient(to top, blue, purple);"></div> <div style="margin-left: 5px;"> <p>100 YR</p> <p>500 YR</p> </div> </div> | <p><b>CRITICAL FACILITIES</b></p> <ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <p><b>BASE FEATURES</b></p> <ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|--|---|--|









T. ROUND LAKE

T. CHIPPEWA

# REGIONAL FLOOD STUDY

## T39 & 40N, R4W, SAWYER COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



T. CHIPPEWA

# REGIONAL FLOOD STUDY



T39 & 40N, R3W, SAWYER COUNTY

Price County

T. DRAPER



Price County

T. WINTER



- |  |   |   |   |
|--|---|---|---|
| <b>POTENTIAL FLOOD IMPACTS</b>   | <b>MODELED FLOOD DEPTH</b>  | <b>CRITICAL FACILITIES</b>  | <b>BASE FEATURES</b>  |
| <ul style="list-style-type: none"><li>AGRICULTURE</li><li>COMMERCIAL</li><li>RESIDENTIAL</li><li>GOVERNMENT</li><li>INDUSTRIAL</li><li>EDUCATIONAL</li><li>OTHER</li></ul> | <ul style="list-style-type: none"><li>100 YR</li><li>500 YR</li></ul> | <ul style="list-style-type: none"><li>EDUCATION</li><li>COUNTY GOVERNMENT CENTER</li><li>FIRE &amp; EMS</li><li>HOSPITAL</li><li>LAW ENFORCEMENT</li><li>LOCAL GOVERNMENT</li><li>DAM</li><li>SUBSTATION</li><li>WASTEWATER TREATMENT</li></ul> | <ul style="list-style-type: none"><li>U.S. HIGHWAY</li><li>STATE HIGHWAY</li><li>COUNTY HIGHWAY</li><li>LOCAL ROADS</li><li>STREETS</li><li>RIVERS &amp; STREAMS</li><li>LAKES</li><li>CITIES &amp; VILLAGES</li><li>TOWNS</li><li>COUNTY</li></ul> |
| <ul style="list-style-type: none"><li>POSSIBLE ROAD/BRIDGE IMPACT AREA</li><li>POSSIBLE IMPACT SEGMENT</li></ul>   |   |   |   |








- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT
- MODELED FLOOD DEPTH**
- 100 YR
  - 500 YR
- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT
- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY T37 & 38N, R8W, SAWYER COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT


- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY T37 & 38N, R7W, SAWYER COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT





- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY

## T37 & 38N, R6W, SAWYER COUNTY





<b>POTENTIAL FLOOD IMPACTS</b> <ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>— POSSIBLE IMPACT SEGMENT</li> </ul>	<b>MODELED FLOOD DEPTH</b> <div style="display: flex; align-items: center;"> <div style="width: 20px; height: 100px; background: linear-gradient(to top, blue, white);"></div> <div style="margin: 0 5px;">100 YR</div> <div style="width: 20px; height: 100px; background: linear-gradient(to top, purple, white);"></div> <div style="margin: 0 5px;">500 YR</div> </div>	<b>CRITICAL FACILITIES</b> <ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul>	<b>BASE FEATURES</b> <ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul>
---	--	---	--




# REGIONAL FLOOD STUDY

## T37 & 38N, R5W, SAWYER COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT




- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY




# REGIONAL FLOOD STUDY

## T37 & 38N, R4W, SAWYER COUNTY



- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▬ POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - DAM
  - SUBSTATION
  - WASTEWATER TREATMENT

- BASE FEATURES**
-  U.S. HIGHWAY
  -  STATE HIGHWAY
  -  COUNTY HIGHWAY
  -  LOCAL ROADS
  -  STREETS
  -  RIVERS & STREAMS
  -  LAKES
  -  CITIES & VILLAGES
  -  TOWNS
  -  COUNTY



# REGIONAL FLOOD STUDY

## T37 & 38N, R3W, SAWYER COUNTY


T. DRAPER

T. WINTER

Price County

Price County

Rusk County



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES


- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY

# REGIONAL FLOOD STUDY

## VILLAGE OF COUDERAY, SAWYER COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY


HAZUS

N  
1:9,840

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## VILLAGE OF EXELAND, SAWYER COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:10,190

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## CITY OF HAYWARD, SAWYER COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:20,590

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## VILLAGE OF RADISSON, SAWYER COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:6,960

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▬ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## VILLAGE OF WINTER, SAWYER COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY


HAZUS



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ✓ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



## WASHBURN COUNTY

### HAZUS 100-YEAR FLOOD LOSS ESTIMATES - WASHBURN COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
C. OF SHELL LAKE	50	\$ 603,169.00	\$ 468,019.00	\$ 6,639.00	527
C. OF SPOONER	10	\$ 29,239.00	\$ 141,682.00	\$ -	281
T. OF BARRONETT	1	\$ 87.00	\$ 2,004.00	\$ 464.00	121
T. OF BASHAW	2	\$ 41,527.00	\$ 12,650.00	\$ -	34
T. OF BASS LAKE	1	\$ -	\$ -	\$ -	7
T. OF BIRCHWOOD	1	\$ 138,917.00	\$ 69,137.00	\$ -	37
T. OF CASEY	5	\$ 42,281.00	\$ 15,693.00	\$ -	25
T. OF CHICOG	6	\$ 40,935.00	\$ 39,467.00	\$ -	31
T. OF CRYSTAL	8	\$ 30,235.00	\$ 11,488.00	\$ -	253
T. OF EVERGREEN	4	\$ 18,615.00	\$ 7,277.00	\$ -	24
T. OF MINONG	12	\$ 128,102.00	\$ 178,247.00	\$ -	71
T. OF SPOONER	6	\$ 27,356.00	\$ 10,653.00	\$ -	32
T. OF SPRINGBROOK	1	\$ -	\$ -	\$ -	5
T. OF STONE LAKE	1	\$ -	\$ -	\$ -	3
T. OF TREGO	64	\$ 1,849,403.00	\$ 792,291.00	\$ -	523
V. OF BIRCHWOOD	13	\$ 160,202.00	\$ 67,720.00	\$ -	120
V. OF MINONG	21	\$ 19,711.00	\$ 49,258.00	\$ 34,252.00	111
<b>GRAND TOTAL</b>	<b>206</b>	<b>\$ 3,129,779.00</b>	<b>\$ 1,865,586.00</b>	<b>\$ 41,355.00</b>	<b>2,205</b>





## HAZUS 500-YEAR FLOOD LOSS ESTIMATES - WASHBURN COUNTY

Municipality	Structures Impacted	Estimated Building Losses	Estimated Content Losses	Estimated Inventory Losses	Debris Generated (tons)
C. OF SHELL LAKE	64	\$ 1,176,475.00	\$ 1,513,642.00	\$ 146,416.00	784
C. OF SPOONER	13	\$ 101,451.00	\$ 192,011.00	\$ -	306
T. OF BARRONETT	1	\$ 571.00	\$ 3,132.00	\$ 3,037.00	121
T. OF BASHAW	4	\$ 52,899.00	\$ 16,408.00	\$ -	91
T. OF BASS LAKE	3	\$ 41,358.00	\$ 12,012.00	\$ -	38
T. OF BIRCHWOOD	1	\$ 166,181.00	\$ 80,020.00	\$ -	37
T. OF CASEY	7	\$ 52,944.00	\$ 19,359.00	\$ -	38
T. OF CHICOG	6	\$ 104,648.00	\$ 66,486.00	\$ -	35
T. OF CRYSTAL	13	\$ 40,996.00	\$ 17,181.00	\$ 1,216.00	461
T. OF EVERGREEN	4	\$ 59,972.00	\$ 22,873.00	\$ -	24
T. OF LONG LAKE	1	\$ -	\$ -	\$ -	7
T. OF MINONG	28	\$ 534,049.00	\$ 306,735.00	\$ -	240
T. OF SPOONER	10	\$ 143,252.00	\$ 60,687.00	\$ -	64
T. OF SPRINGBROOK	2	\$ 13,103.00	\$ 9,964.00	\$ -	7
T. OF STINNETT	2	\$ -	\$ -	\$ -	8
T. OF STONE LAKE	1	\$ 1,503.00	\$ 591.00	\$ -	3
T. OF TREGO	79	\$ 2,710,953.00	\$ 1,116,618.00	\$ -	901
V. OF BIRCHWOOD	15	\$ 262,634.00	\$ 104,403.00	\$ -	146
V. OF MINONG	33	\$ 37,014.00	\$ 87,456.00	\$ 37,950.00	182
<b>GRAND TOTAL</b>	<b>287</b>	<b>\$ 5,500,003.00</b>	<b>\$ 3,629,578.00</b>	<b>\$ 188,619.00</b>	<b>3,493</b>

# REGIONAL FLOOD STUDY

## T41 & 42N, R13W, WASHBURN COUNTY





- |   |  |  |  |
|---|--|--|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><ul style="list-style-type: none"> <li>100 YR</li> <li>500 YR</li> </ul> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>■ SUBSTATION</li> <li>■ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|--|--|--|



# REGIONAL FLOOD STUDY

## T41 & 42N, R12W, WASHBURN COUNTY





- |   |  |   |  |
|---|--|---|--|
| <b>POTENTIAL FLOOD IMPACTS</b><br><ul style="list-style-type: none"> <li>● AGRICULTURE</li> <li>● COMMERCIAL</li> <li>● RESIDENTIAL</li> <li>● GOVERNMENT</li> <li>● INDUSTRIAL</li> <li>● EDUCATIONAL</li> <li>● OTHER</li> <li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li> <li>▨ POSSIBLE IMPACT SEGMENT</li> </ul> | <b>MODELED FLOOD DEPTH</b><br><div style="display: flex; align-items: center;"> <div style="width: 20px; height: 100px; background: linear-gradient(to top, blue, purple);"></div> <div style="margin-left: 5px;">             100 YR<br/>500 YR           </div> </div> | <b>CRITICAL FACILITIES</b><br><ul style="list-style-type: none"> <li>■ EDUCATION</li> <li>■ COUNTY GOVERNMENT CENTER</li> <li>■ FIRE &amp; EMS</li> <li>■ HOSPITAL</li> <li>■ LAW ENFORCEMENT</li> <li>■ LOCAL GOVERNMENT</li> <li>▲ DAM</li> <li>⚡ SUBSTATION</li> <li>◆ WASTEWATER TREATMENT</li> </ul> | <b>BASE FEATURES</b><br><ul style="list-style-type: none"> <li>— U.S. HIGHWAY</li> <li>— STATE HIGHWAY</li> <li>— COUNTY HIGHWAY</li> <li>— LOCAL ROADS</li> <li>— STREETS</li> <li>— RIVERS &amp; STREAMS</li> <li>— LAKES</li> <li>— CITIES &amp; VILLAGES</li> <li>— TOWNS</li> <li>— COUNTY</li> </ul> |
|---|--|---|--|



# REGIONAL FLOOD STUDY

## T41 & 42N, RIW, WASHBURN COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ➔ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT



### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY




# REGIONAL FLOOD STUDY

## T41 & 42N, RIDW, WASHBURN COUNTY




- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT


- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY







# REGIONAL FLOOD STUDY

## T39 & 40N, R13W, WASHBURN COUNTY



- |   |   |   |   |
|---|---|---|---|
| <b>POTENTIAL FLOOD IMPACTS</b>  | <b>MODELED FLOOD DEPTH</b>  | <b>CRITICAL FACILITIES</b>  | <b>BASE FEATURES</b>  |
| <ul style="list-style-type: none"><li>● AGRICULTURE</li><li>● COMMERCIAL</li><li>● RESIDENTIAL</li><li>● GOVERNMENT</li><li>● INDUSTRIAL</li><li>● EDUCATIONAL</li><li>● OTHER</li><li>▨ POSSIBLE ROAD/BRIDGE IMPACT AREA</li><li>▨ POSSIBLE IMPACT SEGMENT</li></ul> | <ul style="list-style-type: none"><li>100 YR</li><li>500 YR</li></ul> | <ul style="list-style-type: none"><li>■ EDUCATION</li><li>■ COUNTY GOVERNMENT CENTER</li><li>■ FIRE &amp; EMS</li><li>■ HOSPITAL</li><li>■ LAW ENFORCEMENT</li><li>■ LOCAL GOVERNMENT</li><li>▲ DAM</li><li>⚡ SUBSTATION</li><li>◆ WASTEWATER TREATMENT</li></ul> | <ul style="list-style-type: none"><li>— U.S. HIGHWAY</li><li>— STATE HIGHWAY</li><li>— COUNTY HIGHWAY</li><li>— LOCAL ROADS</li><li>— STREETS</li><li>— RIVERS &amp; STREAMS</li><li>— LAKES</li><li>— CITIES &amp; VILLAGES</li><li>— TOWNS</li><li>— COUNTY</li></ul> |







- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT
- MODELED FLOOD DEPTH**
- 100 YR
  - 500 YR
- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - SUBSTATION
  - WASTEWATER TREATMENT
- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY




# REGIONAL FLOOD STUDY

## T39 & 40N, R11W, WASHBURN COUNTY




- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - POSSIBLE IMPACT SEGMENT



- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ▲ DAM
  - ⚡ SUBSTATION
  - ◆ WASTEWATER TREATMENT

- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY





# REGIONAL FLOOD STUDY

## T39 & 40N, R10W, WASHBURN COUNTY

T. SPRINGBROOK


T. BASS LAKE

T. CRYSTAL

T. STONE LAKE

T. BIRCHWOOD

T. SAND LAKE



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY  
HAZUS

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- SUBSTATION
- WASTEWATER TREATMENT




### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY




# REGIONAL FLOOD STUDY

## T37 & 38N, R13W, WASHBURN COUNTY








# REGIONAL FLOOD STUDY

## T37 & 38N, R12W, WASHBURN COUNTY



**POTENTIAL FLOOD IMPACTS**

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

**MODELED FLOOD DEPTH**

100 YR 500 YR



**CRITICAL FACILITIES**

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ⚡ SUBSTATION
- 💧 WASTEWATER TREATMENT

**BASE FEATURES**

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY







- POTENTIAL FLOOD IMPACTS**
- AGRICULTURE
  - COMMERCIAL
  - RESIDENTIAL
  - GOVERNMENT
  - INDUSTRIAL
  - EDUCATIONAL
  - OTHER
  - ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
  - ▨ POSSIBLE IMPACT SEGMENT
- MODELED FLOOD DEPTH**
- 100 YR
  - 500 YR
- CRITICAL FACILITIES**
- EDUCATION
  - COUNTY GOVERNMENT CENTER
  - FIRE & EMS
  - HOSPITAL
  - LAW ENFORCEMENT
  - LOCAL GOVERNMENT
  - ⚡ SUBSTATION
  - 💧 WASTEWATER TREATMENT
- BASE FEATURES**
- U.S. HIGHWAY
  - STATE HIGHWAY
  - COUNTY HIGHWAY
  - LOCAL ROADS
  - STREETS
  - RIVERS & STREAMS
  - LAKES
  - CITIES & VILLAGES
  - TOWNS
  - COUNTY



# REGIONAL FLOOD STUDY


## T37 & 38N, RIOW, WASHBURN COUNTY



### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- SUBSTATION
- WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## VILLAGE OF BIRCHWOOD, WASHBURN COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:10,000

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▨ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- ▬ U.S. HIGHWAY
- ▬ STATE HIGHWAY
- ▬ COUNTY HIGHWAY
- ▬ LOCAL ROADS
- ▬ STREETS
- ▬ RIVERS & STREAMS
- ▬ LAKES
- ▬ CITIES & VILLAGES
- ▬ TOWNS
- ▬ COUNTY



# REGIONAL FLOOD STUDY

## VILLAGE OF MINONG, WASHBURN COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:11,650

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ▬ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- ▬ U.S. HIGHWAY
- ▬ STATE HIGHWAY
- ▬ COUNTY HIGHWAY
- ▬ LOCAL ROADS
- ▬ STREETS
- ▬ RIVERS & STREAMS
- ▬ LAKES
- ▬ CITIES & VILLAGES
- ▬ TOWNS
- ▬ COUNTY



# REGIONAL FLOOD STUDY

## CITY OF SHELL LAKE, WASHBURN COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:28,770

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- POSSIBLE ROAD/BRIDGE IMPACT AREA
- POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT


### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



# REGIONAL FLOOD STUDY

## CITY OF SPOONER, WASHBURN COUNTY



NORTHWEST WISCONSIN  
FLOOD IMPACT STUDY

HAZUS




1:28,310

### POTENTIAL FLOOD IMPACTS

- AGRICULTURE
- COMMERCIAL
- RESIDENTIAL
- GOVERNMENT
- INDUSTRIAL
- EDUCATIONAL
- OTHER
- ▨ POSSIBLE ROAD/BRIDGE IMPACT AREA
- ↗ POSSIBLE IMPACT SEGMENT

### MODELED FLOOD DEPTH



### CRITICAL FACILITIES

- EDUCATION
- COUNTY GOVERNMENT CENTER
- FIRE & EMS
- HOSPITAL
- LAW ENFORCEMENT
- LOCAL GOVERNMENT
- ▲ DAM
- ⚡ SUBSTATION
- ◆ WASTEWATER TREATMENT

### BASE FEATURES

- U.S. HIGHWAY
- STATE HIGHWAY
- COUNTY HIGHWAY
- LOCAL ROADS
- STREETS
- RIVERS & STREAMS
- LAKES
- CITIES & VILLAGES
- TOWNS
- COUNTY



## MITIGATION MECHANISMS

### ECONOMIC IMPACT ON RURAL COMMUNITIES

A large part of the Northwest region of Wisconsin is currently classified as being rural. Wisconsin's rural areas account for much of the state's economic and social well-being. Although disproportionate to its population, rural areas provide natural resources that much of the state and country relies on for food, energy, water, forests, recreation, national character, and quality of life. Rural economics and the integrity of the community are intricately connected to these natural systems.

Very heavy precipitation events have intensified in recent decades in most U.S. regions and this trend is projected to continue. Projected changes in flood frequency based on climate projections and hydrologic models have recently begun to emerge and suggest that flood frequency and severity increases may occur in the Northeast and Midwest. Increasing heavy precipitation is an important contributing factor, but flood magnitude changes also depend on specific watershed conditions (including soil moisture, impervious area, and other human-caused alterations). Many rural communities are already facing considerable risk to their infrastructures, livelihoods, and quality of life from observed and projected changes in the climate. This climate volatility will progressively make the way of life harsher for many of those living in Northwest Wisconsin.

### RURAL ECONOMIES

Rural communities are intricately tied to natural resources for their livelihoods and social structures. Major flooding due to increased precipitation is already currently affecting rural communities in Northwest Wisconsin. They will progressively increase over the years and will impact the abilities of rural economic activities (like forestry and recreation) to thrive.

Rural communities are often characterized by their natural resources and associated economic activity. Dominant economic drivers include agriculture, forestry, energy, outdoor recreation, and tourism. In addition, many rural areas with appealing landscapes are increasingly reliant on second-home owners and retirees for their tax base and community activities. Changes in seasonality and intensity of precipitation will increase costs of runoff containment. Because many rural communities are less diverse than urban areas in their economic activities, changes in the viability of one traditional economic sector will place disproportionate stresses on community stability.


Businesses are often the center of small communities' economies, drawing in tourism dollars and ensuring a healthy community. The loss of any one business has disproportionate consequences to the community than being in a large urban area. Businesses accrue economic loss due to flooding through several reasons:

- Direct damage to business property (damage to facility, equipment, vehicles, inventory, etc.).
- Income loss due to closing a business for a period of time.
- Employees unable to report to work due to flooding.
- Income loss due to street closures limiting customer access.



- Income loss due to customers unable to access on or off-street parking.
- Lack of property insurance that covers floods or that includes disruption coverage.

Tourism is another significant contributor to rural economies. Changes in the length and timing of seasons, temperature, precipitation, and severe weather events can have a direct impact on tourism and recreation activities by influencing visitation patterns and tourism-related economic activity. All the counties in the study region have been highlighted as a county based on recreation except for Iron County which is highlighted as a manufacturing county. This indicates the immense role that tourism and recreation plays in these Northwest Wisconsin Counties.



Economic Dependence,  
Source: USDA Economic Research Service 2013

Changing environmental conditions, such as wetland loss and increased risk of natural hazards such as wildfire, flash flooding, storm surge, river flooding, drought, and extremely high temperatures can alter the character and attraction of rural areas as tourist destinations.

Short-term downturns in regional tourism are often experienced after a flooding event. Although the impact on tourism infrastructure and the time needed to return to full operating capacity may be minimal, images of flood affected areas and assumptions of the state of recovery often lead to cancellations in bookings and a significant reduction in tourist numbers.

## RESPONDING TO RISKS

Rural communities face particular geographic and demographic obstacles in responding to and preparing for flooding risks. In particular, physical isolation, limited economic diversity, and higher poverty rates, combined with an aging population, increase the vulnerability of rural communities. Systems of fundamental importance to rural populations are already stressed by remoteness and limited access.

Relatively rapid changes in demographics, economic activity, and climate are particularly challenging in rural communities, where local, agrarian values often run generations deep. Changing rural demographics, influenced by new immigration patterns, fluctuating economic conditions, and evolving community values add to these challenges – especially with regard to the impacts of flooding.

Modern rural populations are generally older, less affluent, and less educated than their urban counterparts. Rural areas are characterized by higher unemployment, more dependence on government transfer payments, less diversified economies, and fewer social and economic resources needed for resilience in the face of major changes. In particular, the combination of an aging population and poverty increases the vulnerability of rural communities to major flooding events.

There has been a trend away from manufacturing, resource extraction, and farming to amenity-



based economic activity in many rural areas of the United States. Expanding amenity-based economic activities in rural areas include recreation and leisure, e-commuting residents, tourism, and second home and retirement home development. This shift has stressed traditional cultural values and put pressure on infrastructure and natural amenities that draw people to rural areas. Changes in climate and weather are likely to increase these stresses. Rural components of transportation systems are particularly vulnerable to risks from flooding. Since rural areas often have fewer transportation options and fewer infrastructure redundancies, any disruptions in road, rail, or air transport will deeply affect rural communities.

Power and communication outages resulting from extreme events often take longer to repair in rural areas, contributing to the isolation and vulnerability of elderly residents who may not have cell phones. The lack of cellular coverage in some rural areas can create problems for emergency response during power failures.

Rural communities rely on various transportation modes, both for export and import of critical goods. Frequent flooding will result in increased erosion and maintenance costs for local road and rail systems, as well as changes in stream flows and predictability that will result in increased maintenance costs for waterways. Events that affect rail traffic would be particularly damaging to rural communities that depend upon these systems to get commodities to market.

Health and emergency response systems also face additional demands from substantial direct and indirect health risks associated with flooding events. Indirect risks, particularly those posed by emerging and reemerging infectious diseases, are more difficult to assess, but pose looming threats to economically challenged communities where health services are limited. Direct threats (such as storm events and coastal and riparian flooding) tend to be more associated with specific local vulnerabilities, so the risks are somewhat easier to assess.

The socioeconomic and demographic characteristics of rural areas interact with flooding to create health concerns that differ from those of urban and suburban communities. Older populations with lower income and educational levels in rural areas spend a larger portion of their income on health care than their urban counterparts. Moreover, health care access declines as geographic isolation increases. Overall, rural residents already have higher rates of age-adjusted mortality, disability, and chronic disease than do urban populations. These trends are likely to be exacerbated by flooding events.

Governments in rural areas are generally ill-prepared to respond quickly and effectively to large-scale events, although individuals and voluntary associations often show significant resilience. Health risks are exacerbated by limitations in the health service systems characteristic of rural areas, including the distance between rural residents and health care providers and the reduced availability of medical specialists.

The effects of flooding on mental health merit special consideration. Rural residents are already at a heightened risk from mental health issues because of the lack of access to mental health providers. The primary care physicians who form the backbone of rural health care often have heavy caseloads and lack specialized training in mental health issues. Additionally, patients referred to mental health specialists often experience significant delays.

The frequency and distribution of infectious diseases is also projected to increase with rising



temperatures and associated seasonal shifts. Increased rates of mutation and increased resistance to drugs and other treatments are already evident in the behavior of infectious disease-causing bacteria and viruses. In addition, changes in temperature, surface water, humidity, and precipitation affect the distribution and abundance of disease-carriers and intermediate hosts, and result in larger distributions for many parasites and diseases. Rural residents who spend significant time outdoors have an increased risk of exposure to these disease-carriers, like ticks and mosquitoes.

## ADAPTATION

Responding to additional challenges from flooding impacts will require significant adaptation within rural transportation and infrastructure systems, as well as health and emergency response systems. Governments in rural communities have limited institutional capacity to respond to, plan for, and anticipate flooding impacts.

Extreme events (such as storms and floods) are expected to have widespread impacts on the provision of services from state, regional, local, and tribal governments. Emergency management, energy use and distribution systems, transportation and infrastructure planning, and public health will all be affected.

Rural governments often depend heavily on volunteers to meet community challenges like fire protection or flood response. In addition, rural communities have limited locally available financial resources to help deal with the effects of climate change. Small community size tends to make services expensive or available only by traveling some distance.

Local governance structures tend to de-emphasize planning capacity compared to urban areas. While 73% of metropolitan counties have land-use planners, only 29% of rural counties not adjacent to a metropolitan county have one or more planners. Moreover, rural communities are not equipped to deal with major infrastructure expenses. Even in communities where there is increasing awareness of flooding risks and interest in comprehensive adaptation planning, lack of funding, human resources, access to information, training, and expertise provide significant barriers for many rural communities.

If rural communities are to respond adequately to future flooding events, they will likely need help assessing their risks and vulnerabilities, prioritizing and coordinating projects, funding and allocating financial and human resources, and deploying information-sharing and decision support tools. There is still little systematic research on the vulnerability of rural communities and there is a need for additional empirical research in this area. Impacts due to flooding will cross community and regional lines, making solutions dependent upon meaningful participation of numerous stakeholders from federal, state, local, and tribal governments, science and academia, the private sector, non-profit organizations, and the general public.

Effective adaptation measures are closely tied to specific local conditions and needs and take into account existing social networks. The economic and social diversity of rural communities affects the ability of both individuals and communities to adapt to flooding, and underscores the need to assess flooding impacts on a local basis. The quality and availability of natural resources, legacies of past use, and changing industrial needs affect the economic, environmental, and social conditions of rural places and are critical factors to be assessed.



Successful adaptation to flooding requires balancing immediate needs with long-term development goals, as well as development of local-level capacities to deal with flooding.

Potential flood mitigation responses are likely to significantly affect rural communities, with both positive and negative effects. Decisions regarding adaptation responses for both urban and rural populations can occur at various scales (federal, state, local, tribal, private sector, and individual) but need to take interdependencies into account. Many decisions that significantly affect rural communities may not be under the control of local governments or rural residents. Given that timing is a critical aspect of adaptation, as well as mitigation, engaging rural residents early in decision processes about investments in public infrastructure, protection of shorelines, changes in insurance provision, or new management initiatives can influence individual behavior and choice in ways that enhance positive outcomes of adaptation and mitigation.

## LOCAL RESPONSES TO FLOODING IN NORTHERN WI

When the July 11th, 2016 storm hit Northwest Wisconsin, it caused damage to multiple roads and streets, hampering work commutes and truck routes alike. The Wisconsin Department of Transportation and Ashland County had to create a new detour for car traffic that was about 40 miles longer than the normal route that connected the City of Ashland to the City of Mellen. After a couple of weeks, a shorter alternative route was created. However, it wasn't until several months later that the route between the two Cities was fully operational. This closure impacted thousands of motorists every day and had an unknown impact on the movement of goods through the region.

In the same storm that year, Saxon Harbor in Iron County experienced tremendous losses and damages to its harbor. Dozens of boats, trucks, and boat slips were damaged beyond repair. A county campground that brought in campers from around the state was destroyed as well. Business for Harbor Lights, a 40-year-old local restaurant, has been down 60% according to its owner. The harbor and campground are not expected to be fully running until the summer of 2019, nearly three years after the flooding event. The impacts of this flood have a significant economic impact for Iron County. Saxon Harbor earned \$130,000 annually in revenue from camping and docking fees. Approaching close to three years of zero income represents a significant financial hit for Iron County that is home to about 5,700 people. Furthermore, the loss of around 2,000 people visiting the area on a summer weekend has had indirect economic consequences to the county.

Although damage to county, state, and federal roads have significant impacts on residents and industry, damage to forest roads can just as equally hamper and disable movement of lumber for the timber industry. This is especially prevalent in Northern Wisconsin where the timber industry makes up a large part of the economy. Making things even more difficult for the distribution of timber is that often time's overweight permits are suspended for truckers traveling through the region after a severe flood. Trucks can only haul 80,000 pounds and they often have longer detours than passenger vehicles. Great Lakes Timber Professionals Association Executive Director Henry Schienebeck said, "The suspension of permits is a good thing to preserve roads, but that means logging truck companies will be hauling less and making less money. Because mills don't keep a lot of wood on inventory, it is important to have a steady flow of wood being delivered. Hauling less wood means that it will take more



truckloads to generate the same amount of raw product to them.” Therefore, depending on how long and which roads are closed for repairs, will determine whether the timber companies can keep up with demand.

The June 16th flood in 2018 that hit the region shut down numerous roads and caused millions of dollars in damages throughout the region. The popular U.S. Highway 2 route connecting the City of Superior with parts of Bayfield and Ashland County was damaged and caused it to be closed down for nearly three months during peak tourism season. This major route through northern Wisconsin averages 4,230 people driving east to west each day. The impacts of this flood have been felt by business owners. The owner of Solstice Outdoors in Ashland has stated that business has been down at least 90 percent. When the flood waters carry in clay sediments, it turns the bay red which in turn, discourages potential customers. Dave Sorenson, who runs Dave’s Fishing Charters out of Bayfield, said he is doing about half as much business as a normal summer. Flooding has clear direct and indirect impacts on the economy in many ways. In the following figure, sales tax revenue can be seen over the past five years for the summer months (May-September) in the region. During this span of time, two severe floods impacted the area in July of 2016 and June of 2018. During the year 2016 when the region was impacted by flooding, four counties had lower sales tax revenue than the previous year when there was no major flood.

**Table 18: COUNTY SALES TAX DISTRIBUTION (THOUSANDS \$) – NORTHWEST REGION**

	<b>Ashland</b>	<b>Bayfield</b>	<b>Burnett</b>	<b>Douglas</b>	<b>Iron</b>	<b>Sawyer</b>	<b>Washburn</b>
2018	620	528	506	1791	197	948	606
2017	611	503	478	1690	195	860	571
2016	544	466	437	1617	191	852	547
2015	535	491	440	1924	186	842	551
2014	511	469	412	1884	186	747	534

County Sales Tax Distributions (\$000s) over the summer months from May-September from 2014-2018.

Source: WI Department of Revenue

Not only do washouts, closed stores, and road closures negatively impact businesses, but so does the spread of misinformation following a flooding event. Without relevant and updated information being advertised throughout the region, customers and their dollars will avoid traveling to the region due to unfound assumptions about the state of the region. Ensuring detours are posted as soon as safely is possible while also communicating that the town, city, or region is open for business can help from discouraging customers immediately after a flooding event.



## MITIGATION MEASURES FOR CRITICAL FACILITIES AND INFRASTRUCTURE

### WASTEWATER TREATMENT FACILITIES (WWTF'S)

Wastewater systems collect domestic and industrial liquid waste products and convey them to treatment plants through collection and conveyance systems and pump (lift) stations. These facilities tend to be highly vulnerable to flooding due to the fact that they're generally sited in low lying areas adjacent to waterways. The release of untreated or partially treated sewage is relatively common during major flood events, posing a serious hazard to nearby waterways. The loss of power at wastewater treatment facilities or pumping (lift) stations may also cause a short or long-term disruption of services. Furthermore, floodwaters can inundate electrical equipment and controls at pump stations located wholly or partially below grade and/or in flood-prone areas. The conveyance system (pipeline network) is also vulnerable to flood inundation and flood-borne debris impact damage. Erosion can expose pipes resulting in fracturing and the inflow pressurization during a flood event can also damage pipelines.

### MUNICIPAL WELLHEADS (HIGH CAPACITY WELLS)

A wellhead is the land area which contributes water to municipal wells. The zone of contribution (ZOC) of a well is where recharging precipitation enters a groundwater system and eventually flows to the well. Many communities have established wellhead protection areas (WHPA's) to protect the surface and subsurface area surrounding municipal wells. One of the greatest threats to a community's water supply is contamination, chemical, or biological flooding. Our analysis examined the proximity of estimated inundation areas in relation to the mapped wellhead protection area provided by the Wisconsin Department of Natural Resources and an estimated wellhead protection area of 1,200 radial feet. The 1,200-foot radius is the minimum wellhead protection area permitted by WDNR.

### ELECTRICAL SUBSTATIONS

Electric substations and transmission lines were identified using digital data provided by the Wisconsin Public Service Commission (WPS) and verified using digital orthophotography and field survey. Inundation of a substation can result in an extended power disruption for a large number of customers. Restoring a flooded substation takes significantly longer than repairing a downed power line damaged by high winds or ice storms.

### PIPELINES, PIPELINE PUMP STATIONS, & PIPELINE MAINTENANCE STATIONS

Pipelines in the project area were identified using the National Pipeline Mapping System, which contains information about hazardous liquid and gas transmission pipelines under the jurisdiction of U.S. Department of Transportation, Pipeline and Hazardous Materials Safety Administration (PHMSA). The key concern relative to pipeline safety in the event of a flood is the integrity of the pipeline itself. Exposed lines are subject to sagging and leaking. Flood debris and the hydrodynamic stresses caused by floodwaters can also contribute to line failure and the release of contaminants into the environment.



## **LOCAL GOVERNMENT**

The mapped locations of town halls within the project area. These facilities generally house most operations of the administrative functions of town government.

## **EDUCATIONAL INSTITUTIONS**

The mapped locations of all educational institutions within the project area. Educational institutions are high-value facilities, which serve essential community functions.

## **FIRE AND EMS, HOSPITALS, & LAW ENFORCEMENT**

The mapped locations of all fire departments and emergency medical services (EMS) facilities within the project area. These high-value assets are considered critical community services which would be essential to flood response and recovery.

## **HAZARDOUS MATERIALS SITES**

Hazardous materials are those chemicals, reagents or substances that exhibit physical or health hazards, whether the materials are in a usable or waste state. Neither HAZUS-MH nor the DOGAMI script directly estimate damage caused by the release of hazardous materials, nor does either model estimate the probabilities of such a release occurring. The user can, however, overlay hazardous materials storage locations and the flood depth grid to identify those areas where hazardous materials sites may be exposed to flooding. Hazardous materials storage site data for the project area were obtained from Wisconsin Emergency Management. This information is collected under the federal Emergency Planning and Community Right-to-Know Act (EPCRA). The database for the project area contains records for 527 hazardous materials storage sites, mostly located within cities and villages. Where only a physical address was provided, records were manually geocoded to determine the likely physical location of the identified facility. Given the imprecise nature of the methodology, this analysis should only be considered as a general guide.

## **DAMS/LEVEES**

Dams are included in the utilities assessment as a cartographic input only. HAZUS – MH/DOGAMI do not provide an analysis option for the dam failure hazard.



## CRITICAL FACILITIES AND INFRASTRUCTURE FLOOD ASSESSMENT

Utility	Description	Potential Impacts	
		100-YR	500-YR
<b>Wastewater Treatment Facilities</b>	<p>Flood events can cause extensive damage to wastewater infrastructure.</p> <ul style="list-style-type: none"> <li>▪ Infrastructure damage, possibly resulting in service interruptions</li> <li>▪ Pipe breaks due to washouts, which could result in sewage spills or low water pressure throughout the service area</li> <li>▪ Debris blockage at an intake or unearthed water and wastewater lines due to falling trees</li> <li>▪ Loss of power and communication lines</li> <li>▪ Combined sewer overflows (CSOs)</li> <li>▪ Water quality changes to source waters and treated effluents, including increased turbidity, increased nutrients and other potential contaminants</li> <li>▪ Restricted access to the facility due to debris, flood waters and damage to roadways from washouts and sinkholes</li> <li>▪ Loss of water quality testing capability due to restricted facility and laboratory access and damage to utility equipment</li> </ul>	<p>Port Wing Wastewater Treatment Facility</p> <p>Mellen Wastewater Treatment Facility</p> <p>Butternut Wastewater Treatment Facility</p> <p>Webster Wastewater Treatment Facility</p> <p>Solon Springs Wastewater Treatment Facility</p> <p>Bad River Water/Wastewater Treatment Facility</p>	<p>Port Wing Wastewater Treatment Facility</p> <p>Mellen Wastewater Treatment Facility</p> <p>Butternut Wastewater Treatment Facility</p> <p>Webster Wastewater Treatment Facility</p> <p>Solon Springs Wastewater Treatment Facility</p> <p>Bad River Water/Wastewater Treatment Facility</p>
<b>Municipal Wellheads (High Capacity Wells-within the potential flooding scenario)</b>	High capacity wells provide the primary water supply to communities and businesses in Municipalities throughout the region. Flooding can cause elevated bacteria and/or pollutants in well water.	15 Municipal Wellheads	15 Municipal Wellheads
<b>Municipal Wellheads (High Capacity Wells-within 1,200 feet of a potential flooding scenario)</b>	High capacity wells provide the primary water supply to communities and businesses in Municipalities throughout the region. Flooding can cause elevated bacteria and/or pollutants in well water.	167 Municipal Wellheads	170 Municipal Wellheads
<b>Electrical Substations</b>	Electric substations are critical to the functionality of the electric grid. Their transformers boost the voltage to very high levels which enables efficient transmission across long distances. Substations which are located in flood prone areas potentially put the electrical grid at risk.	<p>Town of Trego (1 substation)</p> <p>Town of White River (1 substation)</p> <p>City of Hayward (1 substation)</p> <p>Village of Butternut (1 substation)</p>	<p>Town of Trego (1 substation)</p> <p>Town of White River (2 substations)</p> <p>City of Hayward (2 substations)</p> <p>Village of Butternut (1 substation)</p> <p>Town of Bell (1 substation)</p>



Utility	Description	Potential Impacts	
		100-YR	500-YR
<b>Pipelines</b>	During floods, the extreme forces of the floodwaters, floating debris, natural erosion and water pressure from high water can adversely affect pipelines. Flood waters may also change the landscape, exposing pipelines and increasing vulnerability to damage. Enbridge Pipelines Inc. operates the Lakehead System pipeline that enters Douglas County in the Town of Superior and extends east through, Bayfield, Ashland and Iron County. It also extends southward through Ashland County and into Clark County. This line is used to transport oil and petroleum related products from Canada to the U.S. Northern Natural Gas operates a natural gas pipeline that extends from Rib Lake northwesterly into Price County.	Town of Superior (8 Crossings) Town of Parkland (3 Crossing) Town of Oakland (10 Crossings) Town of Amnicon (7 Crossings) Village of Poplar (4 Crossings) Town of Maple (2 Crossings) Town of Brule (2 Crossings) Town of Oulu (1 Crossing) Town of Hughes (2 Crossings) Town of Trip (2 Crossings) Town of Iron River (2 Crossings) Town of Barksdale (3 Crossings) Town of Pilsen (2 Crossings) Town of Eileen (7 Crossings) City of Washburn (1 Crossing) Town of Bayview (2 Crossings) Town of Bayfield (1 Crossing) Town of Gingles (6 Crossings) Town of Sanborn (5 Crossings) Town of Morse (3 Crossings) City of Mellen (1 Crossing) Town of Gordon (2 Crossings) Town of Jacobs (1 Crossing) Town of Peeksville (3 Crossings) Village of Butternut (1 Crossing) Town of Saxon (2 Crossings) Town of Kimball (5 Crossings) City of Montreal (1 Crossing) City of Hurley (1 Crossing) Village of Grantsburg (3 Crossings) Town of Solon Springs (2 Crossings) Town of Gordon (2 Crossings) Town of Wascott (1 Crossing) Town of Frog Creek (1 Crossing) Town of Stinnett (4 Crossings) Town of Bass Lake (1 Crossing) Town of Sand Lake (2 Crossings)	Town of Superior (8 Crossings) Town of Parkland (3 Crossing) Town of Oakland (10 Crossings) Town of Amnicon (7 Crossings) Village of Poplar (2 Crossings) Town of Maple (2 Crossings) Town of Brule (2 Crossings) Town of Oulu (1 Crossing) Town of Hughes (2 Crossings) Town of Trip (2 Crossings) Town of Iron River (2 Crossings) Town of Barksdale (3 Crossings) Town of Pilsen (2 Crossings) Town of Eileen (7 Crossings) City of Washburn (1 Crossing) Town of Bayview (2 Crossings) Town of Bayfield (1 Crossing) Town of Gingles (6 Crossings) Town of Sanborn (5 Crossings) Town of Morse (3 Crossings) City of Mellen (1 Crossing) Town of Gordon (2 Crossings) Town of Jacobs (1 Crossing) Town of Peeksville (3 Crossings) Village of Butternut (1 Crossing) Town of Saxon (2 Crossings) Town of Kimball (5 Crossings) City of Montreal (1 Crossing) Village of Grantsburg (3 Crossings) Town of Solon Springs (3 Crossings) Town of Gordon (2 Crossings) Town of Wascott (1 Crossing) Town of Frog Creek (1 Crossing) Town of Stinnett (4 Crossings) Town of Bass Lake (2 Crossings) Town of Sand Lake (2 Crossings)
<b>Local Government</b>	In the event of a flood, town halls can often serve as the headquarters for relief operations. Having a place where information and decisions are disseminated is vital to the resiliency of the community during a flooding event.	Village of Butternut Town Hall Town of Crystal Town Hall	Village of Butternut Town Hall Town of Crystal Town Hall Town of Jacobs Town Hall

Utility	Description	Potential Impacts	
		100-YR	500-YR
<b>Schools</b>	Damaged or flooded schools can disrupt life for entire communities exposing students to potentially life-threatening situations and makes property vulnerable to serious damage or destruction.	None	None
<b>Fire or EMS</b>	Emergency response services are critical to providing for the wellbeing of its residents in times of a flooding event. Being compromised in any way can impact the safety of those in need. Ensuring that these facilities response time won't be slowed will potentially save lives during a flooding event.	None	None
<b>Hospitals</b>	Without a fully functioning hospital, the lives of its residents will be at risk. Flood waters can damage essential equipment, knock out power, or slow medical treatment for its patients. Other direct damages can include losses in infrastructures, lifeline installations, and medical supplies. Indirect costs are unforeseen expense after emergencies such as increased risk of outbreaks due to loss of laboratory or diagnostic support.	None	None
<b>Law Enforcement</b>	The law enforcement's job it to provide a safe environment for people's lives and property during the event of a flood. Looting, crime, and flooded roads create a challenging situation for law enforcement. Flooded police stations will hurt the ability for law enforcement to protect and serve.	None	None
<b>Hazardous Waste</b>	Animal waste, coal ash, toxic chemicals, and untreated human sewage are of great concern to communities facing flooding. Flood waters can spread the pollution that can impact people's health, drinking water, or wellbeing of their property. Each village or town is exposed to hazardous materials traveling on their streets or to industrial installations that could endanger the surrounding populations if they malfunction.	City of Hayward (Auto Waste) Town of Daniels (Auto Waste) Village of Butternut (Manufacturing Waste)	City of Hayward (Auto Waste) Town of Daniels (Auto Waste) Village of Butternut (Manufacturing Waste)



Utility	Description	Potential Impacts	
		100-YR	500-YR
<b>Pipeline Pump/ Maintenance Stations</b>	Flooding can severely hamper the ability of a pump station to operate normally. The loss of even just one pipeline pump station can disrupt distribution patterns as well as put the surrounding environment at risk. Equally as vital is the smooth operation of maintenance stations that keep the pipeline running free of problems. When access is limited or equipment is damaged by flooding, it endangers the integrity of the pipeline.	None	None
<b>Dams/Levees</b>	Dams and levees are artificial barriers constructed across waterways for purposes of water control, storage or diversion. Floods resulting from dam/levee failure are usually associated with heavy precipitation, runoff from snowmelt, or flood conditions. The area immediately below the dam is at greatest risk, as flood discharges decrease as the flood wave moves downstream. Dam or levee failure could result from poor design or construction, operational mistakes and oversights, or the magnitude of floodwaters could simply exceed the design capacity of the structure. Dam or levee failures pose serve threats to life and property in downstream areas. These structures can fail with little or no advance warning.	176 Dams Insufficient data to perform analysis (Dam Failure)	176 Dams Insufficient data to perform analysis (Dam Failure)

**Table 19: CRITICAL FACILITIES/INFRASTRUCTURE/HAZARDOUS MATERIALS STORAGE  
SITE IMPACTS: 100-YEAR FLOOD LOSSES - REGION**

County	Critical Facilities	Infrastructure (count of intersections with flood depth grid)	Hazardous Materials Storage Sites
<b>Ashland</b>	4	56	3
<b>Bayfield</b>	1	75	1
<b>Burnett</b>	1	66	0
<b>Douglas</b>	1	71	0
<b>Iron</b>	0	20	0
<b>Sawyer</b>	0	64	1
<b>Washburn</b>	1	70	0
<b>Grand Total</b>	<b>8</b>	<b>422</b>	<b>5</b>

**Table 20: CRITICAL FACILITIES/INFRASTRUCTURE/HAZARDOUS MATERIALS  
STORAGE SITE IMPACTS: 500-YEAR FLOOD LOSSES - REGION**

County	Critical Facilities	Infrastructure (count of intersections with flood depth grid)	Hazardous Materials Storage Sites
Ashland	6	55	3
Bayfield	1	77	1
Burnett	1	68	0
Douglas	1	68	0
Iron	0	21	0
Sawyer	0	56	1
Washburn	1	74	0
<b>Grand Total</b>	<b>10</b>	<b>419</b>	<b>5</b>

## MODELED IMPACTS TO LOCAL ROADWAYS

**Table 21: Regionwide Potential Roadway Impacts, 100-year Flood Scenario (miles)**

Road Type	Ashland	Bayfield	Burnett	Douglas	Iron	Sawyer	Washburn	Region
US. Highway	0.2	1.0	0.0	0.7	0.7	0.9	1.4	<b>4.8</b>
State Highway	2.0	2.1	2.1	0.8	0.2	4.3	0.3	<b>11.7</b>
County Highway	2.8	2.9	5.1	3.9	1.1	3.2	3.6	<b>22.7</b>
Town Road	26.3	40.0	26.3	22.9	6.7	29.7	24.5	<b>176.3</b>
Street	0.1	0.4	3.5	2.0	0.7	0.4	0.1	<b>7.1</b>
Forest Road	0.0	0.6	0.1	0.4	0.7	0.0	2.9	<b>4.7</b>
<b>Total</b>	<b>31.3</b>	<b>46.9</b>	<b>37.0</b>	<b>30.6</b>	<b>10.1</b>	<b>38.6</b>	<b>32.8</b>	<b>227.3</b>

**Table 22: Regionwide Potential Roadway Impacts, 500-year Flood Scenario (miles)**

Road Type	Ashland	Bayfield	Burnett	Douglas	Iron	Sawyer	Washburn	Region
US. Highway	0.2	1.1	0.0	1.6	0.3	1.5	2.0	<b>6.6</b>
State Highway	2.2	1.6	2.6	0.7	0.5	6.6	0.5	<b>14.8</b>
County Highway	3.3	3.7	5.9	4.7	1.5	4.1	4.6	<b>27.8</b>
Town Road	27.9	47.6	30.2	28.3	8.1	36.8	29.0	<b>207.7</b>
Street	0.1	0.6	3.8	2.5	0.7	0.6	0.1	<b>8.4</b>
Forest Road	0.0	0.6	0.7	0.4	1.7	0.0	3.4	<b>6.7</b>
<b>Total</b>	<b>33.7</b>	<b>55.2</b>	<b>43.2</b>	<b>38.2</b>	<b>12.6</b>	<b>49.6</b>	<b>39.6</b>	<b>272.0</b>

The analysis of potentially impacted roadways found that 227.3 miles of roadway would be impacted by the 100-year scenario and 272.0 miles of roadway under the 500-year



scenario throughout the region. In both flood scenarios, town roads accrued the highest number of potential miles of roadway impacted over all other road types. They accounted for approximately 78 percent of the potentially impacted roadways in a 100-year flood and 76 percent of roadways in a 500-year flood scenario. Bayfield County had the greatest number of potentially impacted miles of roadway in both flood scenarios. In a 100-year flood scenario, Bayfield County would potentially face 46.9 miles of impacted roadways while in a 500-year flood scenario, they could expect 55.2 miles of roadway to be possibly impacted. All counties in the study region had higher number of estimated damaged miles of roadway in a 500-year flood scenario than a 100-year flood scenario.

## STRATEGIES FOR PREPARING FOR RESILIENCY

Natural disasters and their effects will continue to impact Northwest Wisconsin and the local economy. How we respond to these occurrences, or more importantly how we change the landscape must be examined to include a review of existing infrastructure, housing, commercial buildings, and local government facilities to determine potential impact from disaster and what recovery options exist.

Flooding can impact a wide area by inundating buildings and damaging infrastructure. Our economy needs to be resilient in the face of natural disasters. Resiliency is tied to a community and region being able to minimize future risks. Community leaders must engage in identification and assessment of risks that could impede economic activity after a disaster that could result in temporary or even permanent business closures. Aquifer storage and recovery, floodplain and stream restoration, flood diversion and storage, or green infrastructure methods may support communities in reducing the risks associated with the impacts of flood and drought conditions.

The HAZUS analysis has identified impacts to infrastructure, housing, commercial buildings, and local government facilities based on flooding scenarios. County and local community recognition of these impacts is important to implement strategies for future improvements and disaster planning measures. Significant flooding of the transportation network has been identified throughout the county that will negatively impact economic stability during floods. Preparing for future flood events is necessary to protect the economic viability of local business and employment of area residents. While several approaches to resiliency and flood recovery will be necessary, taking steps to incorporate future actions can speed recovery when floods occur and prevent potential flood damage. There are several ways that buildings can be damaged during flooding. These risks include water damage, hydrostatic pressure exerted by water and saturated soils, hydrodynamic pressure caused by moving water, and damage from large objects and debris propelled by water and wind during a storm. Retrofitting existing buildings can help minimize the damage caused during flooding events. Particular care should be taken when considering the impacts of climate change on vulnerable populations. As cited by Boston's Chief Resilience Officer, Dr. Atyia Martin, vulnerable populations can include children, the elderly, the sick, the disabled, renters, low-income communities, minority residents, those with less than a high school education, and those with limited English proficiency.

## FEDERAL PROGRAMS THAT CAN PROVIDE ASSISTANCE PRIOR TO A FLOOD

To accommodate flood water during storm events and in order to reduce the risk that homes, businesses, and critical infrastructure will be damaged, communities can acquire or protect land in flood-prone locations. Communities can partner with private property owners and conservation organizations such as land trusts or other organizations to purchase land outright or acquire conservation easements on undeveloped properties along a riparian corridor. These tools ensure that the land remains in an undeveloped state and retains its ability to accommodate floodwater. Eligible communities may also work with FEMA and Wisconsin Emergency Management to identify properties that have been repeatedly flooded, and when funding is available, coordinate buyouts of those properties through FEMA grant programs. FEMA administers three grant programs to assist communities in mitigating the effects of natural hazards: the [Flood Mitigation Assistance](#) (FMA) Program, the [Hazard Mitigation Grant](#)



[Program](#) (HMGP), and the [Pre-Disaster Mitigation](#) (PDM) grant program. State, Tribal, and local government agencies may apply through the States to receive funds for these programs. FEMA requires these applicants to meet a specific set of requirements when applying for the funds to ensure that proposed projects meet the program requirements, Federal environmental laws and regulations, and cost-effectiveness requirements. FEMA Flood Mitigation Assistance (FMA) Program grants help with planning and performing projects to reduce future flood losses. These may include lifting, buying, or moving National Flood Insurance Program (NFIP)-insured structures. FMA provides funds yearly to reduce or remove risk of flood damage to NFIP insured buildings.

#### **FEMA MITIGATION GRANT PROGRAMS**

<b>Program</b>	<b>Flood Mitigation Assistance Program (FMA)</b>	<b>Hazard Mitigation Grant Program (HMGP)</b>	<b>Pre-Disaster Mitigation Grant Program (PDM)</b>
<b>At a Glance</b>	FEMA Flood Mitigation Assistance Program grants help with planning and performing projects to reduce future flood losses. These may include lifting, buying or moving National Flood Insurance Program (NFIP)-insured structures. FMA provides funds yearly to reduce or remove risk of flood damage to NFIP insured buildings.	FEMA gives Hazard Mitigation Grant Program funding to states to perform long-term hazard reduction after a major disaster. The purpose is to reduce the loss of life and property due to natural disasters. HMGP funds also support reduction and removal of hazards during the immediate recovery from a disaster. Section 404 of the Stafford Act authorizes the program. Funds are for projects to reduce or prevent loss from future disasters. Projects must provide a long-term solution to a problem. One example is lifting a home to reduce the risk of flood damage instead of using sandbags and pumps to fight the flood. Potential savings must be more than the cost of the project. Funds can help protect public or private property.	FEMA provides Pre-Disaster Mitigation Program grants to help plan and direct hazard mitigation projects before a disaster. Funding these plans and projects reduces overall risk to the population and structures. Funded projects also reduce the need for federal funding in actual disasters. FEMA gives funding to states, territories and tribes in line with applicable law and current budget. PDM grants are competitive.

<b>Program</b>	<b>Flood Mitigation Assistance Program (FMA)</b>	<b>Hazard Mitigation Grant Program (HMGP)</b>	<b>Pre-Disaster Mitigation Grant Program (PDM)</b>
<b>Eligible Applicants</b>	State, territorial, and tribal governments, and certain non-profits may apply. Individual homeowners and businesses may not apply but a community may apply on their behalf.	Hazard Mitigation Grant Program funds are available only within a presidentially declared disaster area. State, territorial and tribal governments and certain non-profits may apply. Homeowners and businesses may not apply but a community may apply on their behalf.	State, territorial and tribal governments and certain non-profits may apply. Homeowners and businesses may not apply but a community may apply on their behalf.
<b>Eligible Activities</b>	The FMA allows buying property, destroying, moving or lifting structures. It also allows dry flood proofing of non-residential structures, small local flood reduction projects, and plans to prevent flood damage. Projects must have the effect of reducing the risk of flood to NFIP insured property, buildings, and structures.	A state governor asks for help in a presidentially declared disaster. HMGP funds are available within the declared disaster area. Utility projects must meet the following criteria: <ul style="list-style-type: none"> <li>▪ Conform to the State's Hazard Mitigation Plan.</li> <li>▪ Benefit the disaster area.</li> <li>▪ Meet all environmental requirements.</li> <li>▪ Solve a problem.</li> <li>▪ Be cost-effective.</li> </ul>	The PDM allows buying property and destroying, moving or lifting structures. It also allows dry flood proofing of non-residential structures, small local flood reduction projects and remodeling of existing buildings and facilities. Other types of projects allowed are safe room construction, infrastructure retrofit, soil stabilization, and hazard mitigation planning.
<b>Cost Sharing</b>	Federal: up to 75 percent. Non-federal: 25 percent. Repeat and severe repeat loss properties may be eligible for Federal cost share: up to 100 percent.	Federal: 75 percent. Non-federal: 25 percent. Non-federal matches can mix cash and in-kind sources (for example labor or materials). The non-federal cost share usually cannot include other federal funds.	Federal: up to 75 percent. Non-federal: 25 percent. "Small and impoverished communities" as defined in Section 203 of the Stafford Act may receive 90 percent federal share.



Program	Flood Mitigation Assistance Program (FMA)	Hazard Mitigation Grant Program (HMGP)	Pre-Disaster Mitigation Grant Program (PDM)
<b>Applications</b>	States have primary responsibility for selecting and directing mitigation activities. Funds for the FMA program are limited. The state point of contact for the FMA program is the <a href="#">WI Hazard Mitigation Officer</a> .	Contact your local government to apply for an HMGP grant. Local governments should contact the <a href="#">WI Hazard Mitigation Officer</a> . The state selects eligible projects and sends them to the FEMA Regional Office for review. The time required for review depends on the complexity of the project. The state selects eligible projects and sends them to the FEMA Regional Office where they are reviewed for compliance with Federal laws and regulations. The time required for review depends on the complexity of the project.	States are responsible for selecting and directing mitigation activities. Funds for the PDM program are limited. The state point of contact for the PDM program is the <a href="#">WI Hazard Mitigation Officer</a> .

In most cases, the best thing a homeowner can do to reduce their premiums on flood insurance while mitigating the most flood damage, would be to elevate their structure above the base flood elevation (BFE). Structural elevation oftentimes is not feasible based on various building characteristics. Characteristics may include: townhomes, connected row houses; older homes; mid-rise multi-family buildings, etc. It should also be noted that the one and only method that will prevent any future flooding damage is to move the house to a safe location that is out of the flood plain. This is costly and time consuming, but it will ensure the best results. Because this is difficult for most homeowners to achieve, a variety of other mitigation techniques will be described to reduce flooding damage to one's home.

It is critical that the homeowners follow all the rules and regulations when applying these changes to their home. This may require hiring a qualified contractor, obtaining building permits, or even the need for an elevation or engineering certificate.

## INTERIOR MODIFICATION/ RETROFIT MEASURES

### BASEMENT INFILL

This mitigation technique fills a basement that is below the BFE, up to grade (ground level) with compacted soil or pea gravel. Parts of the basement wall that are not completely covered by fill, will have to have flood openings installed to allow automatic entry and/or exit of flood waters. Any utilities in the basement must be elevated or waterproofed to protect them from damage or loss of function from flooding. This technique has been proven to be effective at reducing damage to the building and its contents. It is critical to ensure the flood openings are routinely maintained so that they will open in a flooding event. This method will lead to a decrease in square footage and of possible living or rental space. Basement infill is a relatively high-cost measure that has an expected life span of 30 to 50 years. Flood insurance premiums could be lowered based on how high the raised height of the lowest floor is. It should be noted that this method is restricted to areas that will experience low flood depths at low velocities.

### ABANDON LOWEST FLOOR

This method requires the homeowner to vacate the lowest floor of a two-floor building. Flood openings will have to be installed to allow automatic entry and/or exit of flood waters. Any utilities in the basement must be elevated to protect them from damage or loss of function from flooding. This technique has been proven to be effective at reducing damage to the building and its contents. It is critical to ensure the flood openings are routinely maintained so that they will open in a flooding event. This technique will lead to a decrease in square footage and of possible living or rental space. Abandoning the lowest floor is a relatively high-cost measure that has an expected life span of 30 to 50 years. Flood insurance premiums could be lowered based on the new lowest floor living level.

### ELEVATE LOWEST INTERIOR FLOOR

This measure elevates the lowest interior floor of a residential building. This usually can only be done in buildings with high ceilings. Any sections below the lowest elevated interior floor walls have to be either filled to create a stem wall or retrofitted with flood openings that allows automatic entry and/or exit of floodwaters. Any utilities in the basement must be elevated to protect them from damage or loss of function from flooding. Raising the lowest floor of buildings has been proven to be effective at reducing damage to the building and its contents.





Home at the end of a block of several elevated homes across street from Darlington's new ball fields. Lots and homes all are raised above the Base Flood Elevation for this neighborhood and were not flooded during the June 2008 flood. **Photo:** Barbara Ellis, FEMA

It is critical to ensure the flood openings are routinely maintained so that they will open in a flooding event. This technique can lead to a decrease in square footage and of possible living or rental space.

Elevating the lowest interior floor is a relatively high-cost measure that has an expected life span of 30 to 50 years. Flood insurance premiums could be lowered based on the new lowest floor living level.

## WET FLOODPROOFING MEASURES

### FLOOD OPENINGS

This technique involves installing openings in foundation, enclosure walls, or garage doors that are below the BFE that allow automatic entry and exit of floodwaters to prevent collapse from the immense pressure created from standing water. Flood openings have been proven to be effective at reducing structural damage to buildings. It is critical to ensure the flood openings are routinely maintained so that they will open in a flooding event. Installing flood openings is a relatively low-cost measure that has an expected life span of 15-20 years. Flood insurance premiums could be lowered if the lowest floor is rated at a higher elevation.

The dwelling depicted below sustained flood damage during Hurricane Sandy in 2012. The homeowner undertook measures to make the dwelling more flood resistant in the future. The structure was retrofitted using some of the techniques featured in this publication. These



techniques include elevating utilities, basement infill, and installation of flood openings. These combined measures will serve to make the dwelling much more flood resistant and have the added benefit of reducing flood insurance premiums

## ELEVATE BUILDING UTILITIES

This method moves all building utility systems and associated equipment (e.g., furnaces, septic tanks, and electric and gas meters) to protect utilities from damage or from loss of function during a flood. Building utility systems can be raised using elevated pedestals, moving equipment to higher floors, and by building an elevated utility room. Elevation of building utilities has been proven to be effective at reducing or eliminating utility damage during a flood.



The elevation of building utility systems may expose them to damage from other natural hazards, such as high winds and earthquakes. This method is a relatively moderate-cost measure that has an expected life span of 15 to 20 years. Discounts are currently available for elevating building utilities based on where they are relocated or anchored down.

## FLOODPROOF BUILDING UTILITIES

This measure floodproofs all building utility systems and associated equipment to protect it from damage or loss of function from flooding. Some techniques include placing outdoor equipment behind flow walls or placing indoor equipment behind a wall or in a watertight, passive utility enclose. This system is subject to restriction related to flood conditions (three-foot maximum flood depth, low velocity, short duration) and building conditions. Floodproofing building utilities can be effective at reducing or preventing utility damage during a flood. It is critical to ensure the floodproofing systems are routinely maintained so that they will close during a flooding event. Floodproofing residential building utility systems is a relatively moderate-to-high-cost measure that has an expected life span of 15 to 20 years. There are currently no discounts or decreases in premiums under the current program.



Elevated electrical panel at the Pecatonica River Trails Campground (Darlington, WI) **Photo courtesy:** WDNR, Michelle Staff

## FLOOD DAMAGE-RESISTANT MATERIALS


This mitigation technique involves the installation of flood damage-resistant materials such as non-paper-faced gypsum board and terrazzo tile flooring for building materials and furnishing below the BFE to reduce damages accrued from flooding events. Flood damage-resistant materials have been proven to be effective at mitigating non-structural damage to buildings in a low-velocity flood. It is critical to use materials and assemblies that meet FEMA requirements.

The use of flood damage-resistant materials is a relatively moderate-cost measure that has an expected life span of 10 to 20 years. There are currently no discounts or decreases in premiums under the current program.

## DRY FLOODPROOFING MEASURES

### PASSIVE DRY FLOODPROOFING SYSTEM

This method involves coating or covering the home to protect it against flood waters. The materials must be impervious to floodwater and certified and constructed to a maximum of three feet above ground level. Dry floodproofing can be an effective way of reducing or eliminating building and contents damage during a flood. Homeowners may need to reinforce walls and floor slabs to withstand the immense pressure the flood waters will create. This setup would also require the installation of a drainage and back-up emergency power system. The use of a dry floodproofing system is a relatively high-cost measure that has an expected life span of 15 to 30 years with extensive annual maintenance costs and is usually reserved for historic sites. There are currently no discounts or decreases in premiums under the current program.



## BARRIER MEASURES

### FLOODWALL WITH GATES AND FLOODWALL WITHOUT GATES

This method creates a floodwall made of reinforced concrete that surrounds the residential building. This should only be constructed to a maximum height of four feet above ground level. The floodwall with gates will have passive flood gates that are designed to open or close






Typical masonry floodwall with engineered closures, which protected the Oak Grove Lutheran School in Fargo, ND, from flooding in 2001 (source: FEMA, Flood Control America, LLC)

automatically when flood waters are present. The floodwall without gates uses vehicle ramps or pedestrian stairs rather than gates to access the property. Sump pumps or an internal storage system along with a back-up emergency power supply are needed to collect and remove floodwater that accumulates behind the floodwalls during a flooding event. This method can be effective at reducing or eliminating building and contents damage during a flood.

Floodwalls are really only cost effective when flood depths do

not exceed approximately four feet. There are also potential community and design restrictions related to building of the floodwall. This is a relatively high-cost measure that has an expected life span of 50 years. Other cost considerations entail professionally designed plans that meet floodplain management requirements, ensure that the floodwall will not divert floodwaters or adversely impact bordering properties and that the floodwall and its drainage system will meet the flood protection design standards. There are currently no discounts or decreases in premiums under the current program.



## LEVEE WITH GATES AND LEVEE WITHOUT GATES

This option is similar to the floodwall, but the barrier is created by installing an earthen levee around a home with a clay or concrete core constructed to a maximum of six feet above ground level. This method can be built with passive flood gates that are designed to open or close automatically when flood waters are present. The levee without gates uses vehicle ramps or pedestrian stairs rather than gates to access the property. Sump pumps or an internal storage

system along with a back-up emergency power supply are needed to collect and remove floodwater that accumulates behind the levee during a flooding event. This method can be effective at reducing or eliminating building and contents damage during a flood. Residential levees can only be designed to withstand low velocity, low debris, and short duration flood events. This is a relatively high-cost measure that has an expected life span of 50 to 100 years. Other cost considerations entail professionally designed plans that meet floodplain management requirements, ensure that the floodwall will not divert floodwaters or adversely impact bordering properties and that the floodwall and its drainage system will meet the flood protection design standards. There are currently no discounts or decreases in premiums under the current program.

## CASE STUDY OF FLOOD MITIGATION TECHNIQUES – DARLINGTON, WI

Darlington, WI — Located in the southwestern corner of Wisconsin, this rural city was founded beside the Pecatonica River and officially given the name of Darlington in 1869. Darlington is also the county seat and home of the Lafayette County Fair. During the past 172 years, this beautiful community has been at odds with the Pecatonica River. Numerous times the river wreaked havoc with its destructive force, leaving a trail of mud, debris and bacteria, contributing financial stress to both families and businesses. Repetitive flooding deteriorated structures and lowered property values. Owners experienced substantial loss of business during the times of flooding, cleanup, and repair. The buildup of mold and mildew in constantly flooded structures led to unhealthy conditions in the buildings. Most of the buildings date back to the mid-1800s and are of considerable historic importance. The continual flooding is well documented and photographed from 1937 and into the 1950s. As townspeople tired of the onslaught of the relentless river, many considered leaving town for good. Others closed long-time businesses and abandoned properties that were quickly becoming unsalable. Property values plummeted. It had become painfully clear that the multiple floods of the past 50 years had taken a terrible toll on Darlington.

After the 1993 flood, the community adopted four goals, as part of a comprehensive plan, in order to retain the historic and community value of Darlington's Main Street as well as to mitigate against future flood damage:

1. Preserve the historic downtown business district
2. Restore the downtown economic base.



Outside of a store in historic Downtown Darlington.  
Photo: WDNR



Pecatonica River Darlington, WI Photo: WDNR



3. Develop an urban river open space park and recreation area.
4. Eliminate or substantially reduce flood damage in the future.



Former Darlington Mayor Bev Anderson and FEMA Mitigation Specialist Chuck Black inspect stanchions and drain cover at top of steps leading in a Main Street business. It is at this point that flood shields are attached when flooding is imminent. Photo: Wisconsin DMA

The success in reaching the city's goals depended on forming an interagency coalition and promoting the cooperation of government — local, state, and federal— and businesses. Multiple agencies contributed grants and/or expertise to the projects. In developing the mitigation goals, officials ensured efforts were locally based by involving civic leaders, business owners, and residents in the planning. The plan included acquisition and demolition of businesses adjacent to the river that are subject to severe flood damage. Historic buildings in the downtown business district were retrofitted while maintaining their historic character. The engineered solution was to build a vestibule area as you step into the front door, at street level. Steps lead up to the elevated first floor level, and a floodwall separates the vestibule level from the first floor. Elevating the old businesses above flood levels was completed by the removal of

entire first floors and filling existing basements with as much as nine feet of compacted pea gravel to new levels of four feet above the original first-floor elevation. New concrete slabs were then poured over the filled basements, with some slabs placed 13 feet above the original basement elevation.

The downtown district wasn't Darlington's only concern though. Adjacent neighborhoods and businesses also were being swamped by flood waters. As part of the town's total mitigation plan, other projects included elevating approximately 55 affected homes and their utilities above the base flood elevation (BFE) and filling in their basements with crushed rock. Some homes had concrete walls erected on the exposed sides prone to flooding. The city acquired and demolished 13 commercial properties and developed a 33-acre business park up and away from the floodplain for relocated and new businesses. The vacated land near the river was turned into a riverside park with a 1.2-mile paved trail, campground, and open green space. A portion of a 39-mile tri-county multi-use trail also runs through the park. To help address the downtown flooding problem, flood shields were designed to prevent flood waters from entering the downtown businesses. Made of a corrosion-proof aluminum, the shields would be clamped to rigid steel stanchions. The stanchions were to be cast into the top concrete entry portals, leading into the structure. Darlington officials approved fabrication of the flood shields at a total cost of about \$200,000. Each of the 150 shields are numbered and lettered for the specific buildings on which they would be installed. Early warning from flood gauges up-river at Calamine, WI, affords Darlington at least eight hours' notice before flood waters reach the town.



Floodproofing the vestibule of a storefront, Photo: FEMA

Property owners were required to purchase flood insurance if they did not already have a policy. A major benefit of the entire project was a dramatic increase in property values city-wide. One city official estimates that property values for the refurbished commercial buildings along the old main street have nearly doubled. During the two most recent Wisconsin floods, those of 2007 and 2008, the City of Darlington was "armored and ready." The flood shields stopped virtually all floodwater from

entering businesses, elevated buildings and utilities prevented further damage, and the residents and business owners were afforded peace of mind in knowing they were protected this time.

This case study highlights that planning and implementing an effective flood mitigation plan in place can save time, money, and the fabric of the local community. Having a reliable warning system is crucial to allow the community to deploy the necessary flood mitigation tools, while also allowing them to evacuate if necessary. Elevating utilities and homes, relocating, the use of flood walls have been proven to mitigate the impacts of flood waters.



Restored and retrofitted building in Downtown Darlington, WI. Photo: FEMA



## FLOOD RECOVERY PROGRAMS

In the event of a flood that has caused damage in a county or community, there are several recovery programs in the state of Wisconsin that can provide assistance. They consist of:

- Federal Emergency Management Agency (FEMA) Public Assistance (PA)
- Mitigation Funding Provided through Section 406 of the Stafford Act
- Federal Emergency Management Agency (FEMA) Individual Assistance
- Wisconsin Disaster Fund (WDF)

### FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) PUBLIC ASSISTANCE (PA)

The FEMA Public Assistance (PA) grant program provides assistance to State, Tribal, and local governments and certain types of private non-profit (PNP) organizations to help reimburse costs associated with damage to public infrastructure such as roads and bridges so that communities can quickly respond to and recover from major disasters or emergencies. FEMA funds the program, which WEM administers in the state. In order to be eligible for a Presidential Disaster Declaration, the event must overwhelm state and local response and recovery efforts, meet countywide damage thresholds (\$3.68 per capita) and meet a statewide damage threshold (\$1.46 per capita) of \$8,303,000.00 using the 2010 census. Once approved by the President, FEMA provides 75% reimbursement of eligible documented costs, the State of Wisconsin provides up to 12.5% of eligible documented costs, and the local government's share is 12.5%. Through the program, FEMA provides supplemental federal disaster grant assistance for debris removal, life-saving emergency protective measures, and the repair, replacement, or restoration of disaster-damaged publicly-owned facilities, and the facilities of certain PNP organizations. The PA program also encourages protection of these damaged facilities from future events by providing assistance for hazard mitigation measures during the recovery process. To request a federal disaster declaration, the Governor must request FEMA to come to the impacted county or counties and conduct a damage assessment of damaged public infrastructure such as roads and bridges. A FEMA inspector will determine if the damage is eligible under the federal program. The information gathered from a damage assessment will be provided to the Governor who will then request the President to approve a federal disaster declaration. Additional information on FEMA's [public assistance program](#) provides responsibilities, resources, fact sheets, and forms about the program.

- ***Local Governments, State or Tribal Agencies, Private Nonprofits:***
  - Perform damage assessments
  - Work with state or tribe to determine funding amount and priorities for HMGP
  - Encourage community members' involvement in hazard mitigation decision-making
  - Prepare and submit the grant application to the state or tribe
  - Determine sources of funding for non-federal match
  - After FEMA approval, sign and implement the grant agreement
  - Issue necessary permits
  - Manage and monitor the progress of the project and ensure compliance
  - Conduct final inspections and prepare for closeout

## MITIGATION FUNDING PROVIDED THROUGH SECTION 406 OF THE STAFFORD ACT

The FEMA PA program provides funding to restore a damaged facility to its pre-disaster design, function, and capacity; however, during the repair work, opportunities to mitigate future damages in cost-effective ways often present themselves. The Section 406 Mitigation Program provides funding to an applicant to reduce potential of future, similar disaster damages. Some examples of this would include:

- Upsizing a repetitively washed out culvert
- Replacing a metal culvert with a cement culvert
- Elevating a road surface
- Elevation of equipment and control in a wastewater treatment plant
- Burying of overhead power lines
- Installing gabion baskets, riprap, or geotextile fabric to reduce or control erosion on a steep slope

There are different means to determine cost-effectiveness of particular mitigation measures. FEMA must approve proposed hazard mitigation projects before they can be incorporated. If you would like to include hazard mitigation into an open or future project, please contact our office for more information. Section 406 provides discretionary authority to fund mitigation measures in conjunction with the repair of the disaster-damaged facilities. These opportunities usually present themselves during the repair efforts. The mitigation measures must be related to eligible disaster-related damages and must directly reduce the potential for future, similar disaster damages to the eligible facility. This work is performed on the parts of the facility that were actually damaged by the disaster and the mitigation provides protection from subsequent events. Mitigation measures must be cost-effective, technically feasible, and in compliance with statutory, regulatory, and executive order requirements. In addition, the measure cannot cause a negative impact to the facility's operation or surrounding areas, or susceptibility to damage from another hazard.

Section 406 hazard mitigation funding and Section 404 Hazard Mitigation Grant Program (HMGP) funding are two distinct programs that can sometimes be used together to more completely fund a hazard mitigation project and promote resilience. Section 406 mitigation funding can be used to restore parts of the facility that were actually damaged by the disaster to provide protection from subsequent events. Section 404 funding can then be used to provide future protection to the undamaged parts of the facility. Leveraging 404 and 406 funds in a concerted effort facilitates project scoping and development while extending the use of limited 404 funds.

## FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) INDIVIDUAL ASSISTANCE

For the State of Wisconsin to qualify an Individual Assistance Declaration, FEMA inspectors would look to confirm 582 (according to CFR 44) homes major damaged or destroyed. Major damage to manufactured homes is described as the residence has been displaced from the foundation, block or piers and other structural components have been damaged. Destroyed is the structure is a total loss; frame is bent, twisted or otherwise compromised; missing the roof covering or the structural ribbing has collapsed for the majority of the roof system. For conventionally built homes, major damage is considered partial failure to structural elements of



the roof, walls, or foundation. Destroyed is complete failure of two or more major structural components (walls, foundation, or roof) or only foundation remains. To request a federal disaster declaration, the Governor must request FEMA to come to the impacted county or counties and conduct a damage assessment of damaged homes and businesses. A FEMA inspector will determine if the damage is eligible under the federal program. The information gathered from a damage assessment will be provided to the Governor who will then request the President to approve a federal disaster declaration.

- **Home/Primary Residence:** FEMA's Individuals and Households Program (IHP) provides financial and/or direct assistance to eligible applicants. FEMA provides housing assistance to individuals and families who have lost their homes as a result of a presidentially-declared disaster. If you are a renter or homeowner you may qualify for assistance. By law, FEMA assistance cannot duplicate the assistance you receive from your insurance company, but you may receive assistance for items not covered by insurance. If your home was impacted by a major disaster, we recommend that you [apply for assistance](#).
  - Meet with community officials to decide on the type of mitigation project for your property
  - Check with the community to see whether community is supporting an application and whether your property can be included
  - Take photographs of damage and/or existing conditions
  - Maintain and organize papers or document damages
  - Complete and submit paperwork in a timely manner as requested by the community to support the grant application
  - Pay part of the project cost, if requested by the community
  - After approval of the project, work with your community to implement the mitigation project
  - Comply with the local community to ensure closeout of the project

In an Individual Assistance Declaration, the Individual Assistance program provides assistance to individuals and households, which may include:

- Housing Assistance includes Temporary Housing such as rental assistance.
- Repair provides financial assistance to help homeowners repair or replace disaster damage to their primary residence not covered by insurance. The assistance is intended to repair the home to a safe and sanitary condition.
- Other Needs Assistance (ONA) provides disaster assistance for some of your other disaster-caused expenses including medical and dental, child care, funeral and burial, essential household items, moving and storage, vehicle, some clean-up items, and other miscellaneous items. More information can be found at [fema.gov/individual-disaster-assistance](https://www.fema.gov/individual-disaster-assistance).
- Crisis Counseling – Assists individuals and communities in recovering from the effects of natural and human-caused disaster through the provision of community-based outreach and psycho-educational services.
- Disaster Case Management - A time-limited process that involves a partnership between a case manager and a disaster survivor to develop and carry out a Disaster Recovery Plan.
- Disaster Unemployment Assistance –Purpose is to provide unemployment benefits and reemployment services to individuals who have become unemployed as a result

- of a Presidential disaster declaration and who are not eligible for regular State Unemployment Insurance.
- Disaster Legal Services – This service is provided for survivors of presidentially declared major disasters only. Disaster legal advice is limited to cases that will not produce a fee.
- Disaster Supplemental Nutrition Assistance Program (D-SNAP) – Through D-SNAP, USDA Food and Nutrition Service (FNS) is able to quickly offer short-term food assistance benefits to families suffering in the wake of a disaster.
- **Business:** FEMA does not offer assistance for small businesses impacted by a presidentially-declared disaster. However, we do partner with the Small Business Administration (SBA), which offers low interest loans for business damages. Learn more about the [business loan application process](#).
- **Secondary Home:** FEMA does not offer assistance for your secondary home. Federal guidelines only allow us to provide housing assistance when your primary residence is impacted by a presidentially-declared disaster.

## WISCONSIN DISASTER FUND (WDF)

The Wisconsin Disaster Fund (WDF) is a state-funded reimbursement program that allows local governmental units – namely, counties, cities, townships, villages, and tribal units of government – to recoup costs incurred while responding to and recovering from disaster events. The state reimburses 70% of eligible costs after the local governmental unit submits a complete WDF application. The fund does not cover individuals, businesses, the agricultural sector, costs associated with snow storms, damages covered by insurance, nor does it provide funds for mitigation activities. The fund does reimburse public disaster costs under three categories of work: debris clearance, protective measures, and road and bridge repair.

### How to Apply

County Emergency Management Directors submit the following documents:

1. Within 24 hours of an event: Affected counties submit a UDSR (“Uniform Disaster Situation Report”) to WEM, which provides basic information regarding the event.
2. Within 30 days of the event: A County Notification Form is submitted to WEM, which lists local jurisdictions seeking WDF reimbursement and their estimated recovery costs.

Within 60 days of the event, local governmental units – known as “Applicants” – submit the following documents after all recovery work is complete:

1. The **Applicant Request for State Public Assistance**.
  - Also, a [Disaster or Emergency Declaration](#) will need to be submitted, which can be a state, county, or local declaration, as long as it covers the Applicant’s jurisdiction.
2. The **Local Documentation “Toolkit”** which allows the WDF office to interpret what the Applicant is claiming on a cost-by-cost basis. This is only submitted when ALL work is complete and documented.
  - All [supporting documentation](#) which includes timesheets for labor costs, invoices and cancelled checks for materials and contract work, and other supporting documents as needed.



The documentation submitted by local Applicants, especially the Toolkit and supporting materials, can be difficult to complete without prior knowledge of the WDF documentation process; therefore, applicants are encouraged to watch the WDF applicant briefing below. After watching the video, Applicants will learn that WDF reimbursement is based on documented costs in labor, equipment usage, purchased materials (such as gravel), and contracted work, as long as the work falls under one of the eligible categories of work: debris clearance, protective measures, and road and bridge repair.

**WDF Contact Information**

Wisconsin Disaster Fund Coordinator

Phone: 608-242-3259

Email: [widisasterfund@wisconsin.gov](mailto:widisasterfund@wisconsin.gov)

**WDF Resources for County Emergency Managers**

[UDSR Form](#) (PDF)

[County Notification Form](#) (Excel download file)

**WDF Resources for Local Applicants**

[Applicant Request for State Public Assistance](#) (Word document download file)

[Applicant Documentation Toolkit](#) (Excel download file)

[Wisconsin Disaster Fund Administrative Plan](#)

[Wisconsin Disaster Fund Guidance Video](#)

Any other questions or concerns should be directed to your corresponding county or tribal emergency manager listed below.

## EXTERNAL COUNTY & TRIBAL EMERGENCY MANAGEMENT DIRECTOR LIST

Last updated July 23, 2018

\*Listed A-Z by County/Tribe

Last Name	First Name	Region	County/Tribe	Business Phone	E-mail Address	Physical Address
Tank	Dorothy	Northwest	Ashland County	(715) 685-7640 ext. 456	dorothy.tank@ashlandcountysheriff.us	220 6th St. East, Ashland, WI 54806
Corbine	Tony	Tribes	Bad River Band	(715) 682-7123	anagrnt@badriver-nsn.gov	Chief Blackbird Center, 72682 Maple St., PO Box 39, Odanah, WI 54861
Victorson	Jan	Northwest	Bayfield County	(715) 373-6113	jvictorson@bayfieldcounty.org	117 E Sixth Street, PO Box 423, Washburn, WI 54891
Tolbert	Jim	Northwest	Burnett County	(715) 349-2171	jtolbert@burnettcounty.org	7140 County Road K, #127, Siren, WI 54872
Kesler	Keith	Northwest	Douglas County	(715) 395-1391	kkesler@douglascountywi.org	1316 N. 14th St. Suite 10, Superior, WI 54880-1674
Ofstad	Stacy	Northwest	Iron County	(715) 561-3266	sofstad@ironcountywi.org	300 Taconite St., Suite 226, Hurley, WI 54534
Riedell	Matthew	Tribes	Lac Courte Orielles Band	(715) 634-0347	Matthew.riedell@lco-nsn.gov	13394 West Trepania Rd., Hayward, WI 54843
Tillmans	Will	Tribes	Red Cliff Chippewa Tribe	(715) 779-3707 ext 2228	None	88385 Pike Road, Hwy 13, Bayfield, WI 54814
Sanchez	Patricia	Northwest	Sawyer County	(715) 634-2004	psanchez@sawyercountygov.org	10610 Main Street, Suite 89, Hayward, WI 54843
Buck	Taylor	Northwest	Washburn County	(715) 468-4730	cbuck@co.washburn.wi.us	421 Hwy 63, PO Box 429, Shell Lake, WI 54871



## PRESIDENTIAL DISASTER DECLARATIONS

It is important to note two types of disaster declarations provided for in the Stafford Act: *emergency declarations* and *major disaster declarations*. Both declaration types authorize the President to provide supplemental federal disaster assistance. However, the events related to the two different types of declaration and scope and amount of assistance differ.

### EMERGENCY DECLARATIONS

The President can declare an emergency for any occasion or instance when the President determines federal assistance is needed. Emergency declarations supplement State and local or Indian tribal government efforts in providing emergency services, such as the protection of lives, property, public health, and safety, or to lessen or avert the threat of a catastrophe in any part of the United States. The total amount of assistance provided for in a single emergency may not exceed \$5 million. The President shall report to Congress if this amount is exceeded.

**Requirements:** The Governor of the affected State or Tribal Chief Executive of the affected Tribe must submit a request to the President, through the appropriate Regional Administrator, within 30 days of the occurrence of the incident. The request must be based upon a finding that the situation is beyond the capability of the State and affected local governments or Indian tribal government and that supplemental federal emergency assistance is necessary to save lives and protect property, public health and safety, or to lessen or avert the threat of a disaster. In addition, the request must include:

- Confirmation that the Governor or Tribal Chief Executive has taken appropriate action under State or Tribal law and directed the execution of the State or Tribal emergency plan;
- A description of the State and local or Indian tribal government efforts and resources utilized to alleviate the emergency;
- A description of other federal agency efforts and resources utilized in response to the emergency; and
- A description of the type and extent of additional federal assistance required.

### MAJOR DISASTER DECLARATIONS

The President can declare a major disaster for any natural event, including any hurricane, tornado, storm, high water, wind-driven water, tidal wave, tsunami, earthquake, volcanic eruption, landslide, mudslide, snowstorm, or drought, or, regardless of cause, fire, flood, or explosion, that the President determines has caused damage of such severity that it is beyond the combined capabilities of state and local governments to respond. A major disaster declaration provides a wide range of federal assistance programs for individuals and public infrastructure, including funds for both emergency and permanent work.

**Requirements:** The Governor of the affected State or Tribal Chief Executive of the affected Tribe must submit the request to the President through the appropriate Regional Administrator within 30 days of the occurrence of the incident. The request must be based upon a finding that the situation is beyond the capability of the State and affected local

governments or Indian tribal government and that supplemental federal assistance is necessary. In addition, the request must include:

- Confirmation that the Governor or Tribal Chief Executive has taken appropriate action under State or Tribal law and directed execution of the State or Tribal emergency plan;
- An estimate of the amount and severity of damage to the public and private sector;
- A description of the State and local or Indian tribal government efforts and resources utilized to alleviate the disaster;
- Preliminary estimates of the type and amount of Stafford Act assistance needed; and
- Certification by the Governor or Tribal Chief Executive that the State and local governments or Indian tribal government will comply with all applicable cost sharing requirements.

## NATIONAL FLOOD INSURANCE PROGRAM (NFIP)

The National Flood Insurance Program is a federal program created by Congress to mitigate future flood losses nationwide through sound, community-enforced building and zoning ordinances and to provide access to affordable, federally-backed flood insurance protection for property owners. The NFIP is designed to provide an insurance alternative to disaster assistance to meet the escalating costs of repairing damage to buildings and their contents caused by floods. Participation in the NFIP is based on an agreement between local communities and the federal government that states that if a community will adopt and enforce a floodplain management ordinance to reduce future flood risks to new construction in Special Flood Hazard Areas (SFHAs), the federal government will make flood insurance available within the community as a financial protection against flood losses. Communities not participating in the NFIP are subject to certain restrictions. If a nonparticipating community has identified flood prone areas, federal financial assistance such as a VA loan or a mortgage from a federally regulated or insured bank will not be available. Also, the community will not be eligible for federal assistance if a federally declared flooding disaster occurs; no direct federally insured loans or grants will be available; and no structures will be eligible for flood insurance.

**Table 23: NFIP PARTICIPATION, REGION**

Community Name	Date of Participation	Current Effective Map Date	Community Name	Date of Participation	Current Effective Map Date
Ashland County	2/15/1978	2/15/1978	Village of Oliver	2/2/2012	2/2/2012
Bayfield County	9/1/1988	12/16/2011	Village of Poplar	9/1/1986	2/2/2012
Burnett County	11/20/1991	8/19/2008	Village of Lake Nebagamon	8/15/1978	2/2/2012
Douglas County	2/4/1981	2/2/2012	Village of Solon Springs	8/15/1978	2/2/2012
Iron County	4/1/1988	4/1/1988	City of Hurley	4/6/1973	11/14/1975
Sawyer County	9/14/1990	9/14/1990	City of Montreal	11/4/1988	11/4/1988
Washburn County	6/8/1998	10/2/2012	City of Hayward	11/1/1979	11/1/1979
City of Ashland	9/30/1977	9/30/1977	Village of Couderay	Suspended	Suspended
City of Mellen	11/19/1986	11/19/1986	Village of Winter	DNP	DNP
Village of Butternut	Unknown	5/14/1976	Village of Radisson	9/1/1986	9/1/1986
City of Bayfield	9/18/1985	12/16/2011	Village of Exeland	9/1/1986	9/1/1986



Community Name	Date of Participation	Current Effective Map Date	Community Name	Date of Participation	Current Effective Map Date
Village of Mason	DNP	DNP	City of Spooner	4/2/1979	10/2/2012
City of Washburn	11/2/1995	12/16/2011	City of Shell Lake	9/16/1988	10/2/2012
Village of Grantsburg	2/2/1989	8/19/2008	Village of Birchwood	9/30/1988	10/2/2012
Village of Webster	8/19/2008	8/19/2008	Village of Minong	9/1/1986	10/2/2012
Village of Siren	8/19/2008	8/19/2008	Red Cliff	12/16/2011	12/16/2011
City of Superior	4/3/1978	2/2/2012	Lac Courte Oreilles	DNP	DNP
Village of Superior	DNP	DNP	Bad River	DNP	DNP

DNP= Community does not participate in the National Flood Insurance Program

## REGULATORY TECHNIQUES

Floodplain zoning applies to counties, cities and villages in Wisconsin. Section 87.30, Wis. Stats., requires that each county, village and city shall zone, by ordinance, all lands subject to flooding. Chapter NR 116, Wis. Admin. Code requires all communities to adopt reasonable and effective floodplain zoning ordinances within their respective jurisdictions to regulate all floodplains where serious flood damage may occur within one year after hydraulic and engineering data adequate to formulate the ordinance becomes available.

## LAND USE PLANNING

Counties in Northwest Wisconsin and several local governments have adopted comprehensive plans. These plans examine existing land use patterns, make recommendations for future development patterns, and contain goals, objectives and actions relating to transportation, housing, economic development, and land use. Each community is required to update comprehensive plans at least once every ten years.

## HAZARD MITIGATION PLANNING

County Hazard Mitigation Plans identify strategies to address flooding and other natural disasters. Mitigation plans are a prerequisite to obtaining mitigation funding through certain FEMA grant programs. While typically prepared at the county scale, local jurisdictions can receive credit for planning by participating in the countywide process.

## PLANNING FOR FLOOD RESILIENCE

It is ideal to start off with what it means to be a flood resilient community. A flood resilient community is one in which residents and institutions have the capacity to prepare for, respond to, and recover from flooding with minimal outside assistance. By becoming more resilient, communities are not just prepared to survive a major event, but are poised to adapt to ever-changing conditions and thrive.

In order to better achieve that outcome, the community can follow several guidelines to becoming a flood resilient community.

- **Manage water where it falls.** Land use activities throughout a watershed should utilize good stormwater management practices that prevent rapid runoff into streams and rivers. This may be as simple as maintaining soil cover and vegetation to slow water down and allow it to soak into the ground. When the soil is covered with buildings, pavement, or other impervious surfaces, engineered stormwater management practices may be needed.
- **Make room for water.** The highest risk areas near rivers, streams, wetlands, and lakes should be kept free from vulnerable development. The natural functions of these areas are to store and slow floodwaters, thus providing relief for other areas.
- **Live with floods.** In flood-prone areas with existing development and areas where future development will be permitted, measures can be taken to enhance safety and reduce the potential for damage.
- **Education the public.** If residents and business owners are knowledgeable about potential flood risks, they can make informed decisions that balance those risks with other concerns.

An independent study by the National Institute of Building Sciences found that every dollar spent on mitigation saves society an average of four dollars. Therefore, it should be seen as a fiduciary responsibility of local government to thoughtfully consider initiatives that reduce the potential impacts of hazards within their jurisdictions.

### WHY PLAN?

Good planning makes better places to live. Effective planning protects the natural environment while enhancing economic well-being and the quality of life in general. Planning helps communities document their current conditions, visualize what their communities could be in the future, and develop strategies to meet those goals.

In keeping with the duty to protect the health, safety, and welfare, local governments should address flood hazards whenever any type of plan is developed for areas with flood risks. Integrating flood safety into a community's plans provides a basis for addressing these issues through policies, practices, regulations, and investment decisions.

### COUNTYWIDE HAZARD MITIGATION PLANS

State and local governments develop Hazard Mitigation Plans to review the hazards facing a community and recommend long-term actions to reduce threats to safety health, and property.



A local Hazard Mitigation Plan that is approved by the Federal Emergency Management Agency (FEMA) is a prerequisite to obtaining FEMA mitigation funding.

Countywide multi-hazard mitigation plans are updated on a five-year cycle. In order to qualify for mitigation grants from the Federal Emergency Management Agency (FEMA), a municipality must participate in the planning process and adopt the hazard mitigation plan. This municipal involvement enables incorporation of local priorities, concerns, and recommendations. In order to facilitate implementation, it is recommended that the findings and recommendations also be integrated into comprehensive plans and municipal operations. The hazard mitigation plan can also be a valuable source of information about local hazards, vulnerability of communities to those hazards, and recommendations for mitigating the risks.

### COMPREHENSIVE PLANNING

A comprehensive plan presents the long-term vision for a municipality, along with goals and policies to help achieve that vision. It is used as a strategic tool for guiding development and investment decisions to achieve a healthy and balanced community. A comprehensive plan serves three key functions:

- **Expression of a community's desires:** Comprehensive plans can address a variety of issues, including land use, housing, community services, public safety, economic development, transportation, infrastructure, natural resources, and recreation.
- **Guide to decision-makers:** The comprehensive plan is the blueprint upon which municipal land use regulations are based.
- **Legal document:** Provides evidence of coordinated effort and rationale for adoption of specified actions.

Municipalities can lay the foundation for improved flood resilience through their comprehensive plans. The plan specifies how a community should be developed and where development should not occur. The planning process provides an opportunity to assess flood risks, integrate flood safety into the community's goals, balance flood risks with other community priorities, and develop strategies for prohibiting or mitigating flood-prone development. Uses of the land can be tailored to match the land's hazards, directing development to areas that are less vulnerable. Hazardous areas can be reserved for parks, golf courses, backyards, wildlife refuges, natural areas, or similar compatible uses.

#### Steps in Comprehensive Planning

1. **Research:** This includes mapping of natural and human-made features; documentation of existing conditions, assessment of probable future trends, anticipation of potential problems, analysis of environmental and economic constraints, and identification of key issues.
2. **Community goals and objectives:** The process of setting goals and objectives should be an open one that includes citizens and groups who have a stake in the outcome. The plan must strike a balance between multiple interdependent issues and diverse viewpoints. A future land use map can be developed to illustrate how the community intends to grow over time.

3. **Policy formation:** Assess the options available for achieving the goals and objectives, including land use regulations, capital projects, development guidelines, and operating procedures.
4. **Plan implementation:** A comprehensive plan is not a law and cannot be enforced. It only has an effect when implemented through regulatory and non-regulatory actions.
5. **Review and updating:** Because conditions change over time, it is important for the community to conduct a periodic review of problems and progress and update the plan when warranted.

## FLOODPLAIN PROTECTION

**Flooding is a natural process.** The amount of water in a stream or river varies seasonally and with intermittent extreme events. Natural features of an undeveloped stream system, including the floodplain, can moderate the severity of extreme events:

- **Stream channels** adjust to changing conditions (amount of water and sediment) to establish a dynamic equilibrium. Relocating a stream or disrupting the natural features within the channel can contribute to increased flooding or erosion damage while the channel adjusts its location and shape to restore a balanced condition.
- **The floodplain** is an important part of a stream system because it provides a place for water to spread out during high flows. This slows down the water and dissipates energy, which reduces the potential for streambank erosion. Storage of water on the floodplain also reduces the amount of flooding that occurs downstream. A river or stream that becomes disconnected from its floodplain due to berms or high banks is often a stream with erosion problems and downstream flooding.
- **Floodplain vegetation** enhances the ability of the floodplain to slow down and store water, while also stabilizing the stream system. Above ground, the trunks and leaves slow down the flow and dissipate energy, while the roots stabilize the soil and banks. Retaining or restoring plants along the bank of a stream, called a riparian buffer, is the easiest and most effective way to protect a stream system.
- **Wetlands** are areas that contain shallow water during all or part of the year. Whether they are located in the floodplain or in upland areas, wetlands store water and slow down the rate at which water reaches streams, and thus alleviate the flood potential. Wetlands also improve water quality and provide habitat for wildlife.

**Natural systems can play a major role in mitigating hazards.** An important flood damage reduction strategy is to preserve and restore the flood protection capacity of natural systems. Retention of natural floodplain features lessens the severity of flooding and also means that those areas do not contain development that will be susceptible to flood damage. Preservation of natural features outside of the floodplain can also help to reduce flooding. Communities may also capitalize on undeveloped land for recreational use, scenic value, and wildlife benefits. What landscape features affect flooding? The amount of flood water depends on the amount of water that drains off the landscape. So, preservation or restoration of natural drainage features anywhere in the landscape can attenuate flood peaks. Natural features to consider include:



- **Wetlands** can be located near streams or in other parts of the watershed. Regardless of location, they are valuable for slowing down and storing water.
- **Forests:** Vegetation throughout the watershed, especially mature forests, uses large amounts of water, reducing the amount that drains into streams. Plants also slow down runoff, especially on slopes, which spreads out the timing of water reaching streams and reduces peak flows. Vegetation also serves as a carbon sink, removing CO<sub>2</sub> from the atmosphere (and thus mitigating climate change). Harvesting of timber, like other land use changes, should incorporate drainage controls to avoid downhill and water quality impacts.
- **Soil:** During rainfall and snow-melt events uncompacted soil absorbs large amounts of moisture. Some water infiltrates downward and recharges groundwater resources. Additional soil moisture is returned to the atmosphere by plants. Any activity that includes grading, soil compaction, or concentration of runoff can contribute to down-slope drainage problems or flooding.
- **Slopes:** Development on steep slopes can be challenging due to difficulties with managing drainage and preventing erosion, as well as safe access roads. Disturbance of vegetation and soils in these areas may contribute to water quality impairment, downslope drainage or sediment problems, and even landslides.

## EMERGENCY ACTION PLAN

The best way to prepare for flooding is to develop a proactive plan for storm response. An Emergency Action Plan outlines procedures and chains of command during any disaster, including flooding, in order to facilitate effective and efficient response. Municipalities can work with county agencies, local fire departments, school districts, and other entities to develop or update a plan.

What is included in an Emergency Action Plan? Although every plan is different, an Emergency Action Plan should include the following:

- Identify known hazards and steps that can be taken to reduce their occurrence or impact.
- Contain a notification system for officials and agencies who are designated to respond to emergencies.
- Describe emergency operations procedures, such as the activation and coordination of resources, and basic strategies for responding to various incidents.
- Describe how the community's resources will be organized, lines of authority, and chain of command.
- Describe the communications systems that will be used.
- Assign responsibilities for various aspects of emergency response.
- Contain resource lists to quickly obtain information, contacts, and equipment.

## RECOVERY PLANNING – BUILD BACK SAFER AND STRONGER

After a flood or other disaster, there may be opportunities and community support for taking actions that reduce the affected areas' exposure to future damages. A Disaster Recovery Plan can allow communities to plan for safe reconstruction following a natural disaster. If a

community identifies in advance the desired land use in various parts of the floodplain, they are prepared to pursue funding for buyouts of flood-damaged structures in areas more suitable for use as open space. The goals of recovery planning are generally to

- Increase the speed of recovery,
- Promote effective use of resources, and
- Increase the opportunity for community betterment.

How-to guidance: "Planning for Post-Disaster Recovery: Next Generation," American Planning Association, PAS Report 576, [www.fema.gov/media-library/assets/documents/103445](http://www.fema.gov/media-library/assets/documents/103445).

When should a Disaster Recovery Plan be prepared? Ideally, the Recovery Planning process is conducted during normal times, without the pressures of disaster response and recovery. However, most municipalities lack the capacity and interest to undertake pre-disaster recovery planning beyond the broad community goals included in Hazard Mitigation and Comprehensive Plans and short-term recovery recommendations in an Emergency Action Plan. It is more likely that Recovery Planning by municipalities will be conducted in the aftermath of a severe flood or other disaster.

**A flood is always an opportunity to highlight where changes are needed.** During and after a flood or other disaster, emergency management activities focus on protecting lives and property, then getting things back to "normal" as quickly as possible. However, if the community is restored to the "normal" that existed before the flood, then the same flood problems are likely to occur again and the opportunity for improving the community and building resilience will be lost.

A post-disaster Recovery Plan must **quickly address the following questions:**

- What areas should be cleared or not restored to pre-disaster conditions?
- What areas should incorporate retrofitting as part of reconstructions?
- What areas could be allowed to repair without delays?
- What changes should be made during rebuilding to make the community more resilient or sustainable?

The **key points to remember** while making these planning decisions are:

- The area will flood again someday.
- It could be worse next time.
- The community can do things to make it better next time.

Incorporating planning into the busy flood recovery process will take time, leadership, and participation of local stakeholders (elected officials, emergency personnel, planners, businesses, human service providers, civic organizations, and—of course—residents). To buy time, a **temporary reconstruction moratorium** can freeze reconstruction in the affected area until decisions can be made about who can rebuild, who must mitigate, and who can make repairs and reoccupy right away.

**Public information and involvement are essential for developing a successful flood recovery plan.** The plan will address subjects that are central to the lives of those who live in the affected area. It will determine where they live and work in the future, and their lives may be held in limbo until the plan is completed. Dealing with the needs and emotional responses from



these residents needs to be conducted in a “listen and gather information” mode rather than a “plan presentation” mode.

## RESOURCES FOR FLOOD RECOVERY AND RECOVERY PLANNING

- “Planning for Post-Disaster Recovery: Next Generation,” American Planning Association, PAS Report 576, [www.fema.gov/media-library/assets/documents/103445](http://www.fema.gov/media-library/assets/documents/103445). How-to guidance for communities to start their mitigation planning and disaster recovery planning processes.
- “Planning and Building Livable, Safe & Sustainable Communities: The Patchwork Quilt Approach,” Natural Hazard Mitigation Association, <http://nhma.info/publications>
- Information about programs that provide technical assistance and funding to support post-disaster recovery.
- “NAI How-To Guide for Planning,” Association of state Floodplain Managers, July 2014, [http://floods.org/ace-images/PlanningFinal6\\_16\\_16.pdf](http://floods.org/ace-images/PlanningFinal6_16_16.pdf). Planning tools and case studies to help communities develop plans that “aim high” and reduce adverse impacts from flooding.
- FEMA webpage, “Part 2. Recovery Planning,” <http://www.fema.gov/resources-plan-post-disaster-recovery>. Links to tools, case studies, example plans, and other resources to help communities with post-disaster recovery planning.

## OTHER LOCAL PLANS AND PROGRAMS

Communities undertake a variety of planning efforts, each focused on particular assets or concerns. Since the objective of each plan is to improve the community in some way, long-term resilience should be a consideration for any local plan. In the flood-prone Northwest region, planning for long-term resilience must include consideration of flood risks. Recommendations in the previous sections of this guide can be used to integrate flood resilience into other local planning efforts, including:

- Watershed plan
- Economic development strategy
- Capital improvement plan
- Local waterfront revitalization plan
- Open space or natural resource plan
- County water quality strategy
- Facility plan

## COMMUNITY RATING SYSTEM

The Community Rating System (CRS) is a FEMA financial incentive program to promote adoption of stronger policies to reduce flood damage. If communities document that they have policies and programs that reduce the risk of flood damage, they can be rewarded with a reduced flood insurance rate for all landowners within the municipality. Information about this program is at:

<https://www.fema.gov/national-flood-insurance-program-community-rating-system>

## ZONING

What is zoning? Zoning is a land use tool that regulates development by dividing a community into zones or districts and setting development criteria for each zone or district. The zoning law specifies the uses that are permitted in each zone, requirements for structural characteristics, site layout requirements, and procedural matters. Dimensional requirements may include minimum lot sizes, building setbacks, lot coverage restrictions, and building height requirements.

Because zoning is a tool for directing different kinds of development to appropriate areas within a community, zoning regulations can be used to prevent flood damage and to protect natural resources by limiting uses in high-risk and environmentally-sensitive areas.

## WATERBODIES AND BUFFERS

What is a riparian buffer? A riparian buffer is the area along a stream, river, or lakeshore where vegetation is retained to act as a buffer between the water and the adjacent land. Because it is natural for streams to flood and for stream channels to change course over time, keeping this buffer area free of development means that buildings and roads are located away from the waterbody in safer locations. Preventing development near streams and lakes also preserves many natural benefits, particularly if the riparian buffer contains a variety of types of plants—trees, shrubs, grasses, and forbs. The beneficial functions of vegetated stream buffers include:

- Slow water during high flows
- Stabilize banks
- Reduce erosion
- Promote sediment deposition in the floodplain
- Filter nutrients and other pollutants
- Moderate water temperature
- Provide wildlife habitat and corridors
- Enhance the scenic beauty

Locating development away from stream and river banks is the most effective way to protect the development from the frequent flooding and erosion that occur along streams. Well-established vegetation on streambanks and in adjacent riparian areas is generally the best and least expensive long-term protection for a stream system. Streams and rivers are active systems that cause flooding and erosion of adjacent areas. Maintaining a vegetated buffer adjacent to streams, rivers, wetlands, and lakes keeps development away from these high-risk areas, while providing multiple benefits for water quality, stream functions, and wildlife. Local ordinances and codes can be used to limit or prohibit certain types of (or all) development within stream corridors or near waterbodies. These local restrictions can be adopted as part of a zoning code, as a stand-alone ordinance, or as part of other regulations.

What is a wetland? Wetlands are areas that are submerged much of the time and support unique forms of vegetation. Because wetlands store stormwater runoff, their preservation can have valuable flood protection benefits. Development in or adjacent to wetlands is regulated by state and federal permit programs, which local governments can support by providing information and assistance as needed. A municipality can also enact a local wetland law.



However, local involvement in regulating wetlands is generally limited to indirect regulation through subdivision and site plan review laws, which should guide development so as to avoid areas of a site that would inappropriately affect a wetland.

## RUNOFF MANAGEMENT

**Runoff can worsen flooding.** If a stream is flooding frequently, it is possible that development in the surrounding area might be contributing to the problem. Development often converts pervious surfaces (such as soil), which might have previously absorbed rainfall, to impervious surface (such as concrete or pavement), which increases stormwater runoff. Grading, lawns, roads, drainage ditches, and other drainage “improvements” can also increase the speed of runoff, resulting in more water reaching the creek at the same time. Managing stormwater onsite reduces additional flow to flood-prone areas, while also protecting water quality.

What is poor drainage or urban flooding? Poor drainage flooding is when heavy rainfall or snowmelt overwhelms drainage systems. This is sometimes called urban flooding (or pluvial flooding), but it occurs in rural areas also. Because damage is caused by runoff before it reaches a stream, it can cause damage far from streams in areas where the flood risk is not shown on floodplain maps. Factors that contribute to flood and erosion damage from poor drainage include:

- Increased runoff due to pavement and other impermeable surfaces that prevent water from soaking into the soil.
- Increased runoff due to removal of vegetation. Bare ground can generate almost as much runoff as pavement, particularly if the soil is compacted. Mowed lawns are not nearly as effective at intercepting and soaking up water as forests.
- Concentrated flow due to grading and construction of drainage ways, which enable water to move at higher velocities, causing erosion and allowing water to reach streams quicker.

What is green infrastructure? “Green infrastructure includes a wide array of practices at multiple scales that manage wet weather and that maintains and restores natural hydrology by infiltrating, evapotranspiring, harvesting and using stormwater. On a regional scale, green infrastructure is the preservation and restoration of natural landscape features, such as forests, floodplains and wetlands, coupled with policies such as infill and redevelopment that reduce overall imperviousness in a watershed. On the local scale, green infrastructure consists of site- and neighborhood-specific practices, such as bioretention, trees, green roofs, permeable pavements and cisterns.” (Source: US Environmental Protection Agency website, <https://www.epa.gov/wifa/learn-about-wifa-program#questions>.)

1. **Avoid or minimize disturbance by preserving natural features or using conservation design techniques.** Preserving contiguous forests, stream buffers, floodplains, and wetlands can slow the rate of runoff and protect water quality by filtering and infiltrating polluted water.
2. **Reduce the impacts of development by decreasing impervious cover.** Reducing impervious surfaces such as buildings, roads, driveways, and parking lots reduces the speeds and volumes of runoff as well as the amount of pollutants that are collected on site and washed into waterbodies.

3. **Manage the remaining impacts of development by using natural features and runoff reduction practices to slow down the runoff, promote infiltration and evapotranspiration, and minimize the need for structural “end-of-pipe” practices.**

Using practices such as bioswales, rain gardens, rain barrels, green roofs, and vegetation can help manage runoff by allowing it to be collected, distributed, and filtered.

The green infrastructure approach for stormwater management should be incorporated into the early stages of review for development and subdivision proposals. Guidance and checklists to assist Planning Boards with this have been prepared by the Genesee/Finger Lakes Regional Planning Council, “Green Infrastructure Planning Design Guidelines,” 2016, [www.gflrpc.org/uploads/5/0/4/0/50406319/giplanningdesignguidelines.pdf](http://www.gflrpc.org/uploads/5/0/4/0/50406319/giplanningdesignguidelines.pdf).

### Areas with known flooding problems

New development should be designed and constructed in a manner that accommodates any known flooding or drainage problems, regardless of whether it is located within a mapped floodplain. This can be achieved by including the following requirement in zoning, site plan review, and subdivision regulations:

“When a land development project is within or adjacent to any area with known flooding problems or known high ground water, the elevations of buildings should be above the observed, anticipated or computed water levels. The effect of such development on upstream and downstream reaches of the watercourse and adjacent properties shall be considered and adequate protective measures shall be implemented.”

### PUBLIC ROADS

By their very nature, road systems are subject to flooding. Roads sometimes follow along waterways, bridges often constrict flood flows, and roadside drainage ditches intercept hillside drainage and concentrate it along the roadway. Flooded and washed out roadways can be extremely hazardous to the traveling public. The National Weather Service reports that **almost half of all flash flood fatalities occur in vehicles.** <sup>2</sup>

In the course of maintaining and repairing public roads, a community may have opportunities to improve flood resilience of the road system and reduce the impact on waterways. “Flood-Resistant Local Road Systems: A Report Based on Case Studies” (American Lifelines Alliance, January 2005, [https://www.floods.org/PDF/ALA\\_Flood\\_Roads\\_January2005.pdf](https://www.floods.org/PDF/ALA_Flood_Roads_January2005.pdf).) identifies the following practices that improve flood resistance:

- **Improving flood resistance: hydraulics:** Improvements to hydraulic performance are examined, and protection against scour is incorporated for every new crossing and for replacements of existing crossings.
- **Record keeping: labor, equipment, and materials:** Documentation of work performed, including labor, equipment, and materials, is maintained by road segment and crossing location; records are filed to facilitate identification of changes in conditions over time.
- **Periodic inspections:** A formalized program of periodic inspection of waterway crossings to identify, document, and monitor, over time, conditions known to contribute to vulnerability to flood damage is essential.



- **Functional partnerships: adjacent communities:** Interjurisdictional partnerships are formed to cost-effectively co-operate to provide for the overall safe functioning of local road networks.
- **Funds for flood recovery:** Provisions are made for some anticipated flood-related expenditures that exceed the normal budget so that funds are not diverted from routine maintenance and scheduled capital improvements.
- **Bridge construction crew and equipment:** In-house crew capabilities and available heavy equipment are sufficient to construct the types and sizes of the most prevalent waterway crossings in the local road system.
- **Partnerships: state and federal agencies:** Awareness of state and federal programs that provide technical and financial assistance is maintained; partnerships are identified and are pursued.
- **Watershed and stream morphology approaches to flood problems:** It is recognized that watersheds and streams are systems and that solutions to site-specific problems may involve off-site elements.
- **Staff development:** Personnel are trained and cross trained, both in-house and through external opportunities, in the skills required to perform agency tasks.

**Roadside ditches** don't just capture road runoff. They also intercept about 20 percent of runoff from adjacent hillslopes. Each ditch provides a high velocity sluiceway that rapidly shunts water, debris, and contaminants into downstream waterways. These ditch networks increase the magnitude of peak stream heights and contribute directly to flooding. Road ditches also contribute to water pollution and degrade aquatic habitat. Information about "re-plumbing" roadside ditches to reduce contributions to flooding can be found in the publication "[Re-plumbing the Chesapeake Watershed: Improving roadside ditch management to meet TMDL water quality goals.](#)"

## CULVERT ASSET MANAGEMENT

The United States of America has the world's biggest transportation network system. The industrial growth during 1950s marked a rapid development in construction of high speed, high-capacity roadway infrastructure. Today, the United States has 3,981,521 miles of roadway of which 46,726 miles belong to national highway system, 2,318,043 miles are paved roadway and 1,624,207 miles are unpaved roadway, which is the largest in the world.

During the construction of these roadways, billions of culverts were installed under them. As the philosophical saying, "out of sight is out of mind," more importance has been given to preserving the physical infrastructure on the surface like roadway, pavements, bridges, guardrails, etc., than underground infrastructure. Various theories, models, framework and management plans are developed to track, inspect, maintain, and repair the surface infrastructure. However, the invisible critical components of culverts have been neglected. The location and condition of these pipes comes to notice only when there is a problem such as settlement or complete failure of a roadway. The deterioration of culvert pipes and other components is a growing problem for transportation agencies. The deterioration of pipes because of their increasing age or change of service conditions such as increasing flow due to changing watershed conditions increases the wear and tear of these pipes. Various structural, hydrological, environmental and economical (lack of proper maintenance) factors, may accelerate the deterioration process.

Drainage infrastructure systems (culverts, storm sewers, outfall, and related drainage elements) represent an integral portion of Department of Transportations' assets that routinely require inspection, maintenance, repair, and renewal. Failure of these systems is costly for DOTs both directly due to the replacement of the failed system and indirectly due to the time and money and even in some cases lives lost for the users of the highway. Therefore, drainage infrastructure systems are in need of special attention in terms of proactive/preventive asset management strategy.

The variety in material types, shapes, backfill materials, types of roads located above, and environmental conditions make every single culvert unique in terms of its behavior and durability. There have been many studies in order to identify the key parameters affecting culvert behavior but the success rate in providing standard solutions to the problems remained to be low. Had the culvert behavior been completely understood it would have been much easier to manage the culvert inventory by timely renewal and repair efforts.

Wide geospatial distribution of drainage infrastructure assets further complicates the management of these assets. Therefore, the first and most important step in the culvert asset management procedure should be the establishment of a database consisting of asset inventory and asset condition information. By monitoring this database, the department of transportation officials will be able to identify the critical culverts before failure and to take necessary steps in a timely manner to repair, rehabilitate, or replace these culverts.

Additional culvert asset management benefits include:

- Up-to-date inventory
- Reducing failures through inspections
- Reducing emergency repair costs and unplanned financial burden
- Better budget planning for repair and replacement
- Long term ability to identify actual life-cycle and performance of various pipe materials



## ROAD AND CULVERT PROBLEMS ASSOCIATED WITH FLOOD WATERS

### PLUNGE POOLS, STREAM BANK SCOUR, & SEDIMENT DEPOSITS

An undersized culvert produces an 'hourglass effect' with the upstream segment widening due to sediment deposition, while at the same time a downstream plunge pool scours a wide area. The formation of a scour hole or streambank erosion on the downstream side of the crossing provides evidence that an existing crossing is undersized and/or not properly aligned (slope or skew). The primary cause of this phenomenon on the downstream is the 'fire-hose' effect of high velocities through the crossing. Scour can also destabilize the end sections and roadbed. If a culvert is not to be replaced, scour hole protections such as riprap and/or grade control should be considered.



Photo: Google Maps®

Scour holes can be seen in the adjacent air photo. They are typical of undersized culverts and are found throughout the region in a variety of topography. The accumulation of sediment on the upstream side of the crossing provides evidence that an existing crossing is undersized. When there is a stage increase of the headwater elevation (ponding) it causes a change in water surface slope. The slower water drops a portion of

its load of suspended solids (gravel and silt). Vegetation can also become established on these deposits, thus compounding the adverse impact to the crossing's hydraulics. There are no long-term solutions other than replacement with a properly designed culvert. Without replacement, maintenance crews can expect to regularly remove these deposits in order to maintain hydraulic capacity. Failure to do so may increase potential for road overtopping.

## DEBRIS ACCUMULATION



Photo: Minnesota Department of Natural Resources

A crossing that does not pass debris is vulnerable to plugging and failure during a flood event. A properly sized crossing will pass debris (including ice). If there is a history of debris maintenance at a location, it indicates the opening is too small. The replacement crossing should be redesigned with a properly sized crossing. Woody debris is a problem in many parts of Wisconsin.

## PERCHED OUTLET



Perched culvert along the North Shore of Lake Superior in Minnesota.  
Photo: MN DNR

Perched crossings are those that have a drop of water level at the downstream end of a culvert. These are common obstacles to upstream movement of aquatic species. This situation can be due to several reasons, including improper invert elevation at installation. If a culvert has both an upstream aggradation deposit and a perched situation, it is due to an undersized culvert. A stream's interrupted bedload capacity, due to an undersized opening, causes both upstream aggradation (sediment deposits) and causes the stream to perch the outlet when water picks up downstream

material as it re-establishes bedload carrying capacity. If a perched culvert has no upstream aggradation, there are velocity issues (downstream scour hole) that have continued unchecked. In flood conditions perched culverts can backcut and undermine the culvert and associated road grade. Options to reestablish fish passage are either complete replacement with properly sized culvert or retro-fitting the outlet with grade control such as rock rapids (series of weirs).



## ROAD OVERTOPPING



An extreme example of what can happen with overtopping. Photo: MN DNR

Increased frequency or higher than predicted water depths during road overtopping is an obvious indicator that the crossing is no longer functioning within the desired parameters. This is caused when floodwaters flow unimpeded across roads. This can be dangerous and costly, causing erosion, shear stress, and scour. This can eventually lead to a breach or washout of the entire roadway. Raising the roadway to prevent overtopping is not a feasible solution, as flood plain law does not allow moving the problem elsewhere by backing up the water.

## CULVERT FAILURE CASE STUDIES

A culvert was partially washed out at U.S Highway 53 near Solon Springs, Wisconsin in June 2018. The damage occurred when the area was hit in excess of ten inches of rain. This closed two southbound lanes for over two weeks during peak tourist season. This cost \$170,000 to replace the two culvert pipes.

The washout on a bridge over the Black River on State Highway 35 near Pattison State Park in Douglas County closed down that area for several weeks. This was hit by the same storm as described previously. There was a partial collapse of the bridge and the north shoulder was washed out. This was a \$950,000 project to repair the pavement, the shoulder along the highway, and to replace concrete slabs that lead to the bridge.



Wisconsin Highway 53 near Solon Springs sustaining damage from the June 18, 2018 flood. Photo: Wisconsin State Patrol and County Emergency Officials



Wisconsin Highway 35 over Black River sustains damage from flash flooding in Pattison State Park in Douglas County on June 18, 2018. Photo: Wisconsin Department of Transportation



A road was completely washed out on U.S Highway 2 at North Fish Creek in Bayfield County in the same storm that impacted the two previous case studies. This closed down this popular northern route for over two months, creating extensive detours and becoming a \$2.2 million project to replace the previous culvert with a bridge. Ideally it should be able to handle a similar sized flood in the future.

On July 11, 2016 a storm dropped upwards of 11 inches onto the 17 square mile watershed that holds Saxon Harbor in Iron County. The flood waters washed out a bridge as well as a 90-foot-long by 10 feet high culvert on Highway A. Both the bridge and culvert have been replaced with an improved bridge that can handle greater amounts of water flow, costing millions of dollars.



U.S. Highway 2 near Ino has been washed out between County Highway G and Tomich Road in Bayfield County on June 18, 2018. Photo: Wisconsin Department of Transportation



Saxon Harbor, Wisconsin, after a devastating storm in early July, 2016. Photo: Wisconsin DNR

A culvert was completely blown out on State Highway 13 near Highbridge, Ashland County, WI in July 2016. It washed out hundreds of cubic yards of fill material. According to the DOT, the highway gets a daily volume of 2,700 vehicles. The replacement of the culvert with a flood resistant bridge carried a price tag of \$2.8 million. The new bridge withstood the flooding in June 2018 that hit the region, accruing minimal damage.




People observe part of Wisconsin Highway 13, washed out after heavy rains, south of Highbridge in Ashland, Wis., Tuesday, July 12, 2016. Storms carrying tornadoes, torrential rain and powerful winds damaged homes, deposited a snowplow in a tree and flooded highways in north-central Minnesota and northern Wisconsin. Photo: Jeff Peters, AP.

The case studies highlighted indicate that flooding is becoming a greater issue that is overwhelming an outdated and undersized culvert system. Other factors, such as corrosion, overloading, ground movement, heaving, etc. may also contribute to failure. Identifying and gauging the amount of damage that certain culverts are prone to flooding is a difficult task. Having a strong approach to infrastructure asset monitoring can greatly reduce risk and costs.

## CREATING A CULVERT INVENTORY

- Having a current inventory of assets.
- Documenting the condition of those assets, using a condition assessment procedure.
- Demonstrating that the assets are being preserved at a determined condition benchmark.
- Estimating the actual cost to maintain and preserve the assets.



To start inventorying culverts, it is ideal to have a generic and effective way of taking and recording data. Collaborating with surrounding communities and counties to create a data sheet that can be used by all parties will help create a uniform dataset that can benefit everyone.



**EXAMPLE INVENTORY FORM**
**Survey ID**  
**Site ID**  
**Road Name**  
**Milepost**  
**Watershed**  
**Stream**


**Date**  
**Time**  
**Book #**  
**Crew**  
**Lat.**  
**Long.**


Culvert Description: Pipes numbered left to right facing downstream

	Units	1	2	3	4	5
Culvert Type						
Culvert Material						
Structure Type						
Inlet Type						
Inlet Apron Length	ft.					
Inlet Width	ft.					
Inlet Height	ft.					
Substrate Depth Inlet	ft.					
Rust Line Height Inlet	ft.					
Sedimentation at Inlet?	Y/N					
Outlet Type						
Outlet Apron Length	ft.					
Outlet Width	ft.					
Outlet Height	ft.					
Outfall Type						
Substrate Depth Outlet	ft.					
Corrugation Depth	in.					
Corrugation Width	in.					
Culvert Length	ft.					
Embedded?	Y/N					
Embedded Depth	ft.					
Condition Rating (5= best)	1 to 5					
Outfall Height	ft.					
Pipe Gradient	%					
Water Depth at Outlet	ft.					
Max Gradient	%					
Length of Max Gradient	ft.					
Stream Gradient	%					
Backwatered?	Y/N					
Stream Approach Angle						

Habitat Elements	Upstream	Downstream	Inlet	Outlet
Dominant substrate				
Subdominant Substrate				

## PHOTOGRAPH LOG PAGE

Maintaining a photograph log page is very important. Having detailed notes and clear photographs can help explain a typical structures or site conditions that cannot be covered in the data sheets. This can save time and money in the long run if done thoroughly. The photograph log page is a log of all photographs in the order they were taken. It is also helpful to record the numbers the camera assigns each photograph. Move obstructions like tree branches out of the way to allow a clear, unobstructed view of the culvert. Make sure the lens is clean, is not fogged, and does not have water droplets on it. Check photographs after taking them to be sure they are in focus and clear of obstructions and contain all the information intended.

Required photographs include:

- Site Marker. The Survey ID, road name, and date are written on a whiteboard and photographed. This is the first photograph taken at each site.
- View of the road surface at the crossing site.
- View from the culvert looking downstream at the tail crest and beyond.
- View from downstream of the tailwater control (or about 50 feet downstream if there is no tailwater), looking upstream at the culvert(s). The photograph should show the culvert outlet type, condition, road embankment, and the tailwater control if present.
- If the site has more than one culvert, take pictures of the culverts as a group and each inlet and outlet separately. If there is a large outlet perch, photograph this with the survey rod for scale.
- View from an upstream location (looking downstream), showing the culvert inlet type, condition, and road embankment. This photograph should show channel roughness (substrate, debris, vegetation, etc.) and culvert inlet conditions.
- Photographs from the inlet and outlet showing the interior of the culvert. These photographs are used to show rust line height, and, if present, culvert damage, multiple grades, and/or obstructions.
- Photographs of the inlet and outlet at close range showing detail of perches, rust lines, and anything else interesting to the site.
- Views from the culvert looking upstream and downstream. These photographs should show vegetation and general channel type directly upstream and downstream of the culvert but outside of the culvert's influence.
- A photograph of typical stream substrate and other channel roughness elements upstream of the culvert's influence. An object of known size, such as a measuring stick or field notebook, should be used as a reference.

Once the process has been completed and the community has a robust culvert inventory, a risk assessment can be conducted to identify suspect culvert locations that are vulnerable to flooding. With the current data for the NW Region of Wisconsin, very little is known about the integrity of thousands of culverts. A strong inventory can save time, money, damage to property, and possible injury and loss of life.

## CURRENTLY EXISTING CULVERT DATA FOR NORTHWEST WISCONSIN

Accurate and recent culvert inventories range in robustness throughout Northwest Wisconsin. Previous identified locations of culverts were used as an aid in the creation of drawing "cutlines"



for the modeling of the flooding scenarios. Areas that were marked as having a culvert, usually had a culvert at that area and allowed an accurate "cutline" to be drawn. The data from the varying sources, often times overlap as both parties will have identified the same culvert. Culvert data can be seen from the following sources. The data created by NWRPC is in part based on the preexisting culvert data.

**Table 24: POTENTIAL CULVERT DATA SOURCES, REGION**

<b>Data Source</b>	<b>Location (County)</b>	<b>Number of Identified Culverts</b>
Ashland County Highway Department (Land Records Office)	Ashland	260
Bad River Watershed Association	Ashland/Bayfield/Iron	1141
Bayfield County Highway Department (Land Records Office), U.S. Fish and Wildlife Service, Bayfield County Land and Conservation Department	Bayfield	302
Douglas County Highway Department (Land Records Office)	Douglas	425
National Bridge Inventory	Ashland, Iron, Sawyer	99
National Forest Service	Ashland, Sawyer	92
*Northwest Regional Planning Commission	Ashland, Barron, Bayfield, Burnett, Douglas, Oneida, Iron, Polk, Price, Rusk, Sawyer, St. Croix, Vilas	14,140
WI Department of Transportation	Ashland, Iron	14
WI Department of Natural Resources	Bayfield, Douglas	136

*\* Denotes data created with the aid of previously existing culvert datasets.*

## **LIMITATIONS OF FINDING "DAMAGED LOCATIONS"**

With the use of this culvert inventory, along with the aid of Lidar data, aerial imagery, and the Agricultural Conservation Planning Framework tool in ArcGIS, potential culvert locations were created and applied to the model. A total of 14,140 culverts were drawn through this manner. It should be noted that these are potential culvert locations and that they have not been field checked or verified. Again, the data created is based on tools used in ArcGIS and aerial imagery. It is purely an estimation of possible impediments to the flow of water. The tools used in ArcGIS help shows areas of ponding on the earth's surface. Areas of ponding would then indicate a likely culvert location, but at times aerial imagery showed evidence of no impediment. The aerial imagery used in this process ranged in release date. This may have allowed time for the installation of culverts after the imagery was published to what is actually there.

## CULVERT SIZING PROCEDURES FOR 1% (100 YEAR FLOOD) PEAK FLOW

There are several methods to estimate the size (diameter) of a culvert that should be installed in a stream crossing that is to be constructed or upgraded. Determining the right size (diameter) culvert first requires estimating the peak flood discharge that can be expected at each stream crossing during the 100-year flood. Once the peak discharge of the streamflow is known, then the size of the culvert can be determined.

### Method 1. The Rational Method of Estimating 100-Year Flood Discharge

This technique is best employed for estimating 100-year flood discharges for small ungauged forested watersheds. This method assumes the stream sites have the same geomorphic and hydrologic characteristics. The information needed can be easily obtained from local rain gages and topographic maps. This method reflects the local environment well and therefore is most effective with watersheds smaller than 200 acres.

### Method 2. The USGS Magnitude and Frequency Method for Estimating 100-Year Flood Discharge


The USGS technique is based on a set of empirical equations based on precipitation and run off data collected from more than 700 stream gaging stations. This method assumes the 100-year design storm uniformly covers large geographic areas and that watershed characteristics are homogenous. This way is beneficial because mean annual precipitation data are readily available, the equations are based on a wide variety of gage data, including rain and snow events, and because the mean basin elevation is easy to determine from USGS topographic maps. However, it generalizes vast geographic areas and can over and under estimate at the local watershed level so it is ideal for larger watershed areas (>100 acres).

### Method 3. Flow Transference Method for Estimating 100-Year Flood Discharge

For proposed stream crossings that are located in or nearby a hydrologically similar watershed that has a long-term gaging station, the 100-year design flood flow can be calculated for the one that has no gaging station. The 100-year discharge is calculated by adjusting for the difference in drainage area between the two watersheds. This is under the assumption that both stream sites have similar geomorphic and hydrologic characteristics. Watersheds that are geographically closer and are more similar will produce better results using this method. Again, once discharge is computed, the size of the culvert can be determined using the Federal Highway Administration (FHWA) Culvert Capacity Nomograph.



Federal Highway Administration chart for sizing concrete pipe culverts with inlet control. Source: FHWA



The FHWA method is a commonly used tool throughout the U.S. to determine the culvert diameter based on calculated design stream flow and headwater depth ration. Depending on the culvert “entrance type” will impact the size of the culvert used. Culvert entrances range from projecting (barrel shaped) inlets to mitered or beveled inlets. Calculating the “Headwater Depth Ratio” for the proposed stream crossing is the next step. This is ratio of the height of the fill where water would begin to spill out of the crossing to the bottom of the culvert to the diameter or rise of the culvert inlet. Using the correct [chart](#) from the FHWA, the correct projected inlet culvert can be determined for a 100-year flood event.

For streams that are especially woody and full of sediment, plugging is a common concern. Using either an oval or arch culvert will reduce the potential for culvert plugging. Another method is to apply secondary treatments such as flared inlets or trash barriers for suspected culverts that are likely to plug.



## MITIGATION TECHNIQUES FOR CULVERTS AND ROADS

### RETAINING WALLS

**Description:** Retaining walls stabilize slopes where erosion and safety is a concern. There are four basic retaining wall classifications: mechanically stabilized backfill, driven cantilever pile, tieback, and gravity.



Here in Mesa Verde National Park, a retaining wall ensures water will not erode the road. Photo: FHWA

**Application:** Retaining walls are primarily used to stabilize inherently weak sections of ground, to minimize damage from surrounding erosive forces, or at any location where a vertical slope is needed. Construction and function vary by ecoregion. Unstable slopes, or slopes eroding continuously into roads, ditches, and streams may benefit from retaining walls. Large fractures forming along a slope may indicate a potential future slump or slide that needs reinforcement.

Retaining walls can be used on both cut and fill slopes and can physically separate roads from channels.


**Considerations:** Along streams, retaining walls may straighten the stream segment, increase water velocity, eliminate vegetation, and decrease shading. This may harm aquatic life, make access to the stream difficult for wildlife, and increase bank erosion, sedimentation and water temperature. Designers must weigh the benefits of controlling sediment production, preserving slopes, and stabilizing roads against other impacts retaining walls may have on a stream. Retaining walls require geotechnical investigations prior to design. Ground water infiltration behind a retaining wall can cause failure if wall drainage is not provided. Construction methods must be true to the design. Aesthetics play an important part in roadway design. Working with landscape architects assures a pleasing and appropriate design. Soil nail walls allow for vertical or near vertical slopes without footings. This minimizes exposure to erosion and reduces the area of environment impacted. The shot-crete facing provides a natural rock appearance and texture, and provides habitat for cliff dwelling wildlife. Construction costs and methods depend on the retaining wall.

**Potential Outcome/Benefits:** Retaining walls stabilize slopes, reduce erosion, and if faced with shot-crete, provide a natural rugged look. Eliminated output of soil and debris to ditch.

## SLOPE ROUNDING AND REVEGETATION

**Description:** Slope rounding and revegetation lays back hillslopes to a natural angle of repose to reduce runoff and sediment transport, and to promote vegetation re-establishment. Seeding or planting often follows slope shaping.

**Application:** Use slope rounding and revegetation where there is potential for the site to erode, slump or fail, and cause damage and/ or create hazardous conditions to roadways, water bodies, structures, and property. This technique works on slopes disturbed by natural events such as fire and landslides, or human-disturbed slopes such as road cuts and fills, borrow areas, waste areas, or timber harvest areas. Size and severity of disturbance, and slope steepness, dictates the level of slope rounding and revegetation required. Project sequence usually requires reshaping hillsides with heavy equipment, spreading grass seed and protective mulch, then implementing soil bioengineering and biotechnical stabilization projects.



The change in slope can reduce the amount of erosion incurred. Photo: Washington State DOT

**Considerations:** Native plant species should be used when replanting to avoid introducing exotic invasive species that could adversely affect other ecosystem components. Using plant species attractive to wildlife may increase the risk of disturbance or mortality by attracting them to the road. Treatments implemented immediately after disturbances reduce negative effects from unstable slope conditions.

Monitor recently completed projects to check plant survival. In areas where excessive runoff and erosion could be a problem, visit sites during and immediately following runoff events. Annual checking and documentation of newly treated sites is recommended. Harsh growing sites may require multiple plantings or temporary irrigation.

**Potential Outcome/Benefits:** Stabilized slopes have minimal onsite and offsite sediment movement, are aesthetically pleasing, and provide better conditions for vegetation re-establishment.

## REVEGETATION



**Revegetation Description:** Roads are often constructed adjacent to streams and floodplains, resulting in excessive degradation and removal of riparian vegetation. Riparian and wetland vegetation are critical to regulating stream microclimate, providing food and cover for wildlife, and controlling erosion and surface runoff. Removal of vegetation for road construction and associated land management activities creates a need for effective riparian-wetland vegetation restoration. Depending on the source of impacts, numerous techniques can be used to re-establish vegetation or allow stressed vegetation to recover.

**Application:** Replanting of riparian areas has been successful nationwide, especially along major stream and river corridors. If hydrology is to be restored, it may be delayed 2–3 years to allow seedlings to become well established.



Revegetation in the beginning stages for Chester Creek, MN. Photo: City of Duluth.

Indicators of appropriate use include: (1) lack of understory vegetation; (2) elevated browse height on trees and shrubs; (3) fragmented forest and riparian corridors; (4) sediment loading and turbidity in adjacent streams; (5) elevated stream temperatures; (6) erosion and soil compaction; (7) the need to enhance effectiveness of wildlife crossing structures.

**Considerations:**

Techniques to reduce compaction and erosion may need to be applied to

accelerate vegetation recovery. Replanting riparian forest considerations are: soil permeability, hydrologic alterations, wind-borne seed sources, adjacent forest blocks, current recreational use, and wildlife and fish species present. Restoration will be most effective if the replanted site is reconnected to the adjacent stream or river channel. If the replanted site is connected to other forest blocks, wildlife requiring large forest blocks will benefit. Additional considerations are the presence of sensitive species or current recreational use of the area.

**Potential Outcome/Benefits:** Improved riparian vegetation, increased wildlife and fisheries habitat, improved water quality, decreased erosion, decreased fragmentation, larger habitat blocks for area-sensitive wildlife species if the replanted site is connected to other forest blocks

## SOIL BIOENGINEERING

**Soil Bioengineering Description:** Biotechnical stabilization and soil bioengineering stabilization both use live vegetation as important structural as well as aesthetic components. Soil bioengineering is a specialized subset of biotechnical stabilization that uses live plant parts


(roots and stems) as the main structural and mechanical elements in a slope protection system to stabilize surface erosion features and shallow rapid landslides. Soil bioengineering treatments provide sufficient stability so that native vegetation and surrounding plants can gain a foothold to eventually take over this role. Successful implementation of soil bioengineering stabilization requires knowledge of the factors governing the mass and surficial reinforcements and drains, and the hydraulic and mechanical effects of slope vegetation.

### Application:

Live staking is branch cuttings inserted into the ground to stabilize shallow earthen slips and slumps.

Live cribwalls are box-like structures constructed of timbers, backfilled with soil, then planted with branch cuttings extending outward. Cribwalls cannot resist large, lateral earth stresses.

Live fascines are long bundles of branch cuttings bound together into cigar-like structures to reduce surface erosion on steep rocky slopes where digging is difficult. On long or steep slopes, intense runoff can undermine fascines near drainage channels.



Live cribwall construction. Source: U.S. Forest Service

Brushlayering can stabilize hillslopes and channel banks with horizontal and vertical plantings of live plant cuttings. Buried cuttings provide immediate site reinforcement. Secondary soil stabilization occurs as buried stems take root, and leafed-out cuttings provide a natural look.

Branchpacking is used to repair small slumps or holes by alternating layers of live branch cuttings and compacted backfill. As plant cuttings grow, trapped sediment refills holes, and roots increase soil stability. This technique is not effective in slump areas greater than four feet deep or five feet wide.

Gully repair in small gullies can be accomplished by alternating layers of live branch cuttings and compacted soil. This technique immediately reinforces soil, reduces runoff velocities, and provides erosion barriers.

Log terracing uses earthen terraces reinforced with logs to reduce slope length and steepness. Terraces provide stable areas for plantings that further stabilize the sites.

**Considerations:** Soil bioengineering is an effective solution that may need to be used with a geotechnically engineered system. Plant species vary depending on ecoregion and soil conditions.

**Potential Outcome/Benefits:** Soil bioengineering techniques stabilize surface erosion and shallow rapid landslides, reduce excess surface/subsurface drainage, and strengthen soils.



## INVASIVE SPECIES

**Description:** Exotic plants and animals can disrupt ecological processes with invasive behavior or growth patterns. Roaded riparian areas and wetlands are particularly vulnerable because roads facilitate infestation. Brown-headed cowbirds follow roads up riparian areas and lay their eggs in other birds' nests. Invasive mussels damage water systems and native species. Noxious weeds crowd out native species and cause erosion by reducing soil cover.

**Application:** The following control strategies apply primarily to noxious weeds, but some apply to all invasive species.

Prevention: Power wash equipment before entering worksites; inspect and pre-treat infested access roads, gravel and borrow sources for weeds prior to use; limit active road construction sites to necessary vehicles. Limit grain-feeding livestock near riparian areas to reduce spread of brown-headed cowbirds.

Identification: Consult with local extension office, county weed superintendent, or forest weed specialist on weeds currently at worksites; know potential invaders from adjacent areas; watch for all life stages.

Prioritization: Differentiate invasive weed species from more common non-invasives. Attack small or outlying populations or new invaders first.

Develop threshold strategies: competitive species (control), moderately competitive (suppress or contain), non-competitive (defer).

Treatment: Fill in bare ground with fast growing native cover species, weed-free mulch, geotextiles or crushed rock. Over-seed with certified weed-free compatible or native seed. Fertilize to encourage competitive growth of native species. Use biological controls to control seed production on existing widespread weed populations, and herbicides for a definitive response in smaller populations.

Monitoring: Evaluate effectiveness of integrated pest management programs. Map existing and expanding populations or new invasions. Modify treatment to increase control.

**Considerations:** Pre-treating access roads and borrow sources will not deplete existing noxious weed seed banks. Identification of noxious species can be a problem because early growth stages and some native non-invasive species look similar. During treatment program development, consider erosion potential, high water tables or surface water, sensitive plants, recreation areas, cost, equipment or skill needs, and application timing. Factor cost and timing into monitoring effectiveness.

**Potential Outcome/Benefits:** Protection or restoration of existing native biodiversity, erosion control and forage production for livestock and wildlife.

## BIOTECHNICAL STABILIZATION

**Description:** Biotechnical stabilization and soil bioengineering both use live vegetation as important structural as well as aesthetic components. Biotechnical stabilization uses mechanical elements in combination with plants to arrest and prevent slope failures and erosion, and biological and mechanical elements are integrated and complementary. Biotechnical stabilization integrates living vegetation and inert structural or mechanical components such as concrete, wood, stone, and geofabrics to reinforce soil and stabilize slopes. Geofabrics are made from synthetic polymers or from natural materials such as jute and coir.

**Application:** Engineers usually use inert systems for slope stabilization and erosion control. Reasons for widespread use include availability, ease of installation, familiarity, existence of standards, and acceptance by specifiers. Inert materials are presumed to have predictable and invariant properties, but even inert materials slowly degrade, decompose, and decay with time. Vegetation can be incorporated into any of the following retaining structures, revetments, or inert ground covers that are porous or that have openings (interstices).

### Retaining Structures:

- Rock breast walls
- Gravity walls (gabions, crib, and bin walls)
- Articulated block walls
- Reinforced earth structures (stacked and backfilled three dimensional webs)

### Revetment Systems:

- Riprap (quarry stone, rubble, natural rock)
- Gabion mattresses
- Concrete facings (gunnite and concrete filled mattresses)
- Cellular confinement systems (three-dimensional webs that cover the surface and are backfilled with aggregate above)
- Articulated block systems (concrete blocks linked by cables or other methods)

### Ground Covers:

- Artificial mulches (fiberglass roving and cellulose fibers)
- Blankets, mats, and nettings (slope coverings that protect the surface and promote/enhance the growth of vegetation)
- Cellular confinement systems (three-dimensional honeycomb webs that cover the surface and are backfilled with soil or aggregate)

**Considerations:** Many inert systems or products lend themselves to integrated or combined use with vegetation. For plant survival, moisture and sunlight must be available.

**Potential Outcome/Benefits:** Biotechnical methods can stabilize cut and fill slopes along highways or streambanks.

## ROADWAY DIPS



**Roadway Dips Description:** Roadway dips modify roadway drainage by altering the road template and allowing surface flows to frequently disperse across the road.

**Application:** Roadway dips have applications nationwide, even on steep grades. They disperse surface water flows and reduce erosion in areas where sediment loading to a water body is a concern. Roadway dips may replace or supplement culverts for cross drainage, especially where existing culverts fail often or require high maintenance. Roadway dips may help solve erosion, ditch sloughing, culvert failures, cascading effects from overtopping culverts, high maintenance costs, and hydrologic disconnectivity.

**Considerations:** Roadway dip design and construction vary by road management objectives. Consider traffic limitations and install the proper length of dip to ensure that the design vehicle can be accommodated (logging truck, chip van, horse trailers, cattle trucks). See design manuals for dip spacing and depth. Depending on traffic volume and kind, warning signs may be needed to alert drivers to road changes. Dips may be used up to 10–15% road slope. Steeper slopes require longer dips. In some cases, riprap and/or asphalt can be used to harden the dip and disperse water for wet weather conditions or year-round roads. Roadway dip spacing is critical. Placement may be at ditch relief culverts or change in grade. This technique reduces maintenance, and it is important for grader operators to understand the need for the dip so they do not blade out the structure.

**Potential Outcome/Benefits Roadway:** dips reduce maintenance costs, sediment transport, the need for culverts, and the risk of catastrophic road or slope failure. They can lower traffic speeds to facilitate wildlife crossings.

## LOW WATER CROSSINGS, OVERTOPPING, AND FORDS

**Description:** Low water crossings pass water and transport debris over a road continuously or intermittently. Types of low water crossings include vented fords, un-vented fords, and low water bridges. These structures can range from simple, stream-grade elevation, native-surfaced crossings to larger more massive structures. Allowing water to overtop roads is one of the most cost-effective options to mitigate flood damage. If successful, a flood can simply inundate a road and then recede with minimal damage to the integrity of the roadway.

**Application:** Low water crossings may be used on lower standard roads where continuous access is not required. They are ideal for channel systems that transport debris and bed load



The low-lying elevation of U.S. Highway 2 and intact floodplain allowed flood flows to spread out and overtop the road without causing major damage. Photo: WI Emergency Management

during high water events and for roads that will not receive periodic maintenance. Low water crossings require special designs to pass fish and aquatic organisms.

**Considerations:** Low water crossings construction materials include riprap, concrete, asphalt, Jersey barriers, and native materials. Geosynthetics may be used to provide separation of materials, subgrade support and restraint.

**Potential Outcome/Benefits:** Benefits include lower construction costs, reduced maintenance and potential for catastrophic road failure. Ponding water

increases infiltration. Decreased fill heights result in fewer cleared acres and maintained riparian vegetation diversity. A low water crossing over a culvert disperses flow, reduces water velocity, and channel bank erosion. The potential consequences of catastrophic road failure are less due to reduced fill amounts, lower water velocity, and more erosion-resistant construction materials

## PERMEABLE FILL WITH CULVERT ARRAY

**Permeable Fill with Culvert Array Description:** Permeable fills are generally used to cross meadows and promote the passage of sheet and subsurface flows with minimum flow concentration and maximum spreading. The road base and/or subbase is constructed of relatively large, preferably angular, uniformly graded rock to allow uninterrupted ground and surface water flow. Culverts within the permeable fill and above the drainage grade allow ponding of the water and percolation through the fill.



Photo: U.S. Forest Service

The installing of culvert with the invert elevation at a higher elevation than the meadow elevation can promote seepage and infiltration.

**Application:** Roads crossing wet meadows act as barriers to subsurface and sheet flow, resulting in altered hydrology and a loss of meadow functions. This technique may be used on ephemeral channels or meadow systems to promote water passage and maintain and restore wet meadow systems, or in high

meadow areas that do not experience significant flooding. This technique is not recommended



in flash flood prone areas, or for fish bearing perennial streams unless passage is provided in the main channel. Permeable fill can be used in areas where the road restricts ground water flow, causing drier conditions in downslope areas.

**Considerations:** When a multiple culvert array is used, the culvert spacing should imitate the natural flood plain so flows are not restricted to a narrow section of the meadow. Design culverts to carry 100-year storm events. Install all culverts at the same elevation to avoid headcutting at the lower ones. Culverts may require outlet energy dissipaters. Fill heights should be kept to a minimum to reduce consolidation pressures on underlying soils. To reduce costs, keep culverts short and minimize fill volume. In areas with large woody debris or significant bedload, adding an overtopping structure or ford, will provide passage of water and debris. Design culverts to allow unrestricted passage for all life stages of amphibians, fish or small wildlife.

**Potential Outcome/Benefits:** Permeable fills can maintain and/or restore natural wet meadow hydrology and result in maintained or restored wildlife habitat, vegetation diversity, and water storage.

## RAISED CULVERT INLETS

**Description:** Culvert inlet elevations are raised by constructing a dike around the culvert or by installing a culvert elbow.

**Application:** Raised culvert inlets installed on ephemeral channels keep water on the land longer and promote infiltration. These techniques are applicable in all ecoregions. Inlets can be installed onto new or existing installations. Locate these on low gradient stream systems, in large or small floodplains. They can create and enhance wetlands in a watershed. Indicators include vertical instability such as head cutting and eroding banks in straight stretches, loss of meander patterns, lowered groundwater tables, and a change or loss of upstream riparian and wet meadow vegetation. Prefabricated elbows and bands are inexpensive and easy to install. A variety of materials, including rock, timbers, concrete drop inlets, or multiplate culverts, succeed as dikes.

**Considerations:** Some results of raised culvert inlets may be:

- Creation of a wetland environment
- Reduced passage of fish, aquatic organisms and small animals
- Restricted transport of debris and bedload
- A fixed water level

**Potential Outcome/Benefits:** Increased riparian vegetation vigor and diversity, reduced flood flashiness, sediment basin creation above the culvert, raised water table and increased infiltration and reduced headcutting.

## ENERGY DISSIPATERS AND DEBRIS RACKS

**Description:** Energy dissipaters and aprons, used at culvert inlets and outlets, reduce water velocities, and prevent erosion. Dissipaters include riprap, vegetated ditches, concrete or steel baffles, and tiger teeth. Riprap is an apron of coarse rock installed on a cut or fill slope can prevent erosion and undercutting at culvert outlets and at other drainage outlets. Covering the exposed soil with rocks helps protect it from being wash away. Debris racks at culvert inlets can prevent clogging. Another alternative other than rocks is to apply a flexible concrete geogrid mat over the ground that can provide protection to the soil.



The area directly surrounding the culvert is covered in geotextile fabric, followed by a layer of clean, sediment free riprap. Photo: WI DNR

**Application:** Energy dissipaters and aprons can protect steep slopes and erosive soils by reducing water velocity, dispersing flows, and preventing channeling or undercutting at the culvert outlet. Dissipaters and aprons function on single or multiple culverts (arrays) during storm and normal flow events.

Culverts experiencing frequent debris clogging or plugging may benefit from debris (trash) racks. Debris racks at culvert inlets deflect large woody debris and bedload from the channel before it enters and clogs the culvert.

**Considerations:** If racks become clogged, flows will overtop the road and may cause catastrophic failure. Install debris racks only when regular maintenance is possible. When passage of debris and bedload is necessary, debris racks are a common culvert treatment, but may not be the best long-term solution.

**Potential Outcome/Benefits:** Energy dissipaters and aprons can reduce water velocity and potential erosion. Debris racks deflect debris and bedload preventing culvert clogging or plugging.

## STREAM CHANNEL MODIFICATION STRUCTURES

**Description:** These techniques protect road embankments from channel scour and erosion. They can mitigate for loss or alteration of riparian vegetation, and restore riparian terrestrial and aquatic habitats.

**Application:** Roads are often constructed adjacent to river or stream channels and may serve as a source of sediment (surface erosion and road fill failure). Roads constructed adjacent to channels can influence channel meander pattern and geometry. This can straighten the channel, reduce channel complexity, cause loss or alteration of native riparian vegetation, and degrade terrestrial and/or aquatic habitats. In-channel structures can be installed to alter or modify channel flows either above or below channel crossing structures to improve fish passage. This technique has application within each ecoregion in the country.





A constructed meander stream modification that slows water. Photo: WA Department of Fish and Wildlife

Indicators include the presence of road prism or embankment failures, undermined channel banks below the road, need for frequent high maintenance or reconstruction, change in channel classification type, change in native vegetation, change in terrestrial and/ or aquatic habitat quantity and quality, and change in fish or wildlife habitat access.

**Considerations:** Install these structures at the lowest flow period of the year to reduce the amount of heavy equipment disturbance causing sedimentation and turbidity. These techniques are designed for small stream channels (2–3 order channels) and are not appropriate in large stream or river channels. Usually this technique is most effective in a series of in-channel and/or channel bank structures.

**Potential Outcome/Benefits:** In-channel and channel bank structures can reduce the higher maintenance or reconstruction costs resulting from road prism failures due to channel scour and erosion.

## RECONNECTING CUTOFF WATER BODIES

**Description:** Culverts and bridges can reconnect side channels, ponds, wetlands and cut-off channel meanders within floodplains that have become isolated or cut off from the main channel due to the construction of a road prism.

**Application:** Roads constructed within the floodplain and adjacent to rivers or streams may isolate or cut off portions of the natural channel or wetland network. This can straighten the channel; increase water velocities, and cause loss or degradation of valuable aquatic and terrestrial riparian habitats. Structures can be installed within the road prism to create as many reconnections as needed to meet one or more of the following resource objectives: (1) restore access and use of historic fish and wildlife habitats; (2) restore hydrology and significant aquatic habitat (an increase in channel meander and channel length or the amount of wetland surface area); (3) increase the channel or wetland diversity.

Indicators for use include (1) seasonal or year-round movement or migration of wildlife or fish species is impeded by the road; (2) a noticeable loss of fish and/or wildlife habitat (change in food, cover, and shelter); (3) the presence of non-native vegetation and /or animals.

**Considerations:** Reconnecting water bodies to active river and stream channels within floodplains could increase the risk for damage from high flow events, such as flood flows to road and channel crossing structures. These structures require medium to high annual maintenance, especially in systems that move significant amounts of bedload and coarse woody debris. Restoring historic habitats and access to those habitats could increase the incidents of human interactions with fish and/or wildlife species (disturbance, poaching, etc.).

**Potential Outcome/Benefits:** Reconnecting floodplain water bodies can result in significant restoration of aquatic habitat quality and quantity, such as fish access to spawning or rearing habitat. Other benefits could be the long-term recovery of floodplain structure and function such as moderating effects of flood flows, increased channel or wetland diversity, and restored native riparian wetland vegetation.

## ENGINEERED LOG JAM COMPLEXES

**Description:** Log jam complexes are multiple log structures placed in rivers and streams to protect channel banks, roadways, and other adjacent features. This is a similar technique to the stream channel modification technique.

**Application:** Log jam complexes protect roadways adjacent to river channels by emulating natural river processes. Log jam complexes are usually placed in series or in combinations. These structures are suitable for larger channels, 3rd order or higher. Engineered log jams are one type of log jam complex and can have up to 500 wood pieces. Log jam structures can: 1) stabilize channel banks and protect roads using native materials; 2) deflect and catch large woody debris in transport; 3) promote establishment of vegetated riparian areas such as channel banks and in-channel riparian islands; 4) improve and create new fish habitats; 5) restore and maintain natural river system characteristics.

**Considerations:** Install log jam complexes at the lowest flow period of the year to reduce disturbance to the riparian area by heavy equipment. Use sediment reduction treatments as necessary. Use techniques to keep fish away from the construction area. Consider the proximity of these structures and the potential risk to other public and private property located downstream before and during project implementation.

**Potential Outcome/Benefits:** Benefits provided by engineered log jams include: 1) initiation of channel scour and deposition around the structures; 2) retention of woody debris in transport within the river system; 3) increase in channel complexity such as meander pattern and geometry; 4) restoration and improvement of aquatic and terrestrial habitats.



## BEAVER POND STRUCTURES

**Description:** Roads passing through riparian and wetland areas may act as dikes or dams impeding water flow. Beavers are attracted to this ponded water because they can impound water with little additional work by simply blocking or plugging culverts. Several water control structures, such as beaver pond levelers, have been developed to facilitate water movement through beaver dams and roads subject to beaver activity. These devices can maintain the valuable fish and wildlife habitat created by beavers while reducing damage to roads and other structures because they allow water movement but prevent complete removal of water from the ponded area.

**Application:** These structures maintain wetland habitat created by beavers and lower the water level of these ponds, reducing the risk of road erosion. Beavers search for leaks along the road berm or embankment and detect leaks by the sound and velocity of moving water. Beaver pond levelers lower pond water levels by extending the water intake well beyond the road berm or embankment and dispersing the water through a perforated pipe instead of one large culvert opening. This technique is appropriate when (1) beavers dam culverts and other road outlet structures; (2) the road prism is saturated; (3) beavers cause road erosion caused by beaver ponds built above the culvert inlet.

**Considerations:** Beaver pond leveler structures maintain ponded water levels above road/channel crossings during normal flow conditions. They are typically not designed to transport runoff from large storm events. Major roads should also contain nearby spillway areas to transport high flows (floods) across roads.

**Potential Outcome/Benefits:** Expected benefits include (1) maintaining fish and wildlife habitat created by beaver ponds; (2) reducing damage to adjacent roads, (3) maintaining floodwater storage; (4) maintaining the water purification functions of beaver ponds.

## WETLAND MAINTENANCE

**Description:** Roads located near riparian areas and wetlands may contain culverts that alter the natural hydrography of these water bodies. These culvert placements often set the water level either above or below natural levels. Most wetlands have seasonally fluctuating water tables allowing plants and animals to fulfill their annual life cycle requirements. Certain wetland maintenance techniques, such as stop-log structures, maintain water levels of wetlands located upstream from roads, simulating the natural hydrology throughout the year. Habitat for native fish, wildlife, and plant species can be maintained and restored by this technique.

**Application:** These structures are commonly used along most of the diked, dammed and drained river floodplains across the U.S. to restore and maintain wetland functions where hydrology has been altered and is no longer capable of functioning naturally. Structures such as stop-log structures have application on most forest and rangeland ecosystems, especially where roads traverse wetlands and marshes that naturally have seasonal variations in water levels. Depending upon the debris-loading situation at each site, different types of stop-log structures (as shown in these photos) can be used to reduce or prevent the plugging of culvert inlets. Indicators for use include: (1) existing wetland crossings; (2) the presence of tree mortality; (3) change in vegetative species composition

**Considerations:** Traditional stop-log structures should not be used alone, or where fish or aquatic invertebrate passage is a management objective. Stop-log structures can be modified to allow increased fish passage, but complementary fish passage structures are preferred. Consider traffic and roadbed loads when choosing among available corrugated metal pipe and reinforced concrete pipe structures. Maintaining the seasonal and annual desired water levels for forested wetlands and freshwater marshes will vary according to resource and road management objectives in each ecoregion.

**Potential Outcome/Benefits:** More diverse and natural plant community, and maintained or restored habitat for fish and wildlife species

**Example:** [https://www.fs.fed.us/rm/pubs/rmrs\\_gtr102\\_2.pdf](https://www.fs.fed.us/rm/pubs/rmrs_gtr102_2.pdf)



## FLOOD PREVENTION TECHNIQUES FOR WATER AND WASTEWATER UTILITIES

Flooding is one of the most common hazards in the United States, causing more damage than any other severe weather-related event. It can occur from swollen rivers, heavy rains, spring snowmelt, levee or dam failure, local drainage issues, and water distribution main breaks. Impacts to drinking water and wastewater utilities can include loss of power, damage to assets and dangerous conditions for personnel. As storms become more frequent and intense, flooding will be an ongoing challenge for drinking water and wastewater utilities.

Drinking water and wastewater utilities are particularly vulnerable to flooding. A wastewater treatment plant is at greatest risk for flooding when it's sited in a low-lying area near the body of water where it discharges its final effluent. Heavy inflows from storm events can also overwhelm a treatment plant, resulting in discharges of diluted effluent into nearby lakes or rivers. Instances of flood-induced overflow (bypass wastewater) occurring at wastewater facilities in northwest Wisconsin are well documented. The City of Ashland wastewater utility experienced 20 overflow events in a 5-year period. Much of the region, including the City of Ashland experienced 500-year flood events in 2012, 2016, and 2018. The increased magnitude and frequency of these events is cause for great concern with regard to wastewater utility flood resiliency.

There are four basic steps involved in increasing your utility's resilience to flooding.

- Step 1 – Understand the Threat of Flooding
- Step 2 – Identify Vulnerable Assets & Determine Consequences
- Step 3 – Identify & Evaluate Mitigation Measures
- Step 4 – Develop Plan to Implement Mitigation Measures

To help you through this process, work with a team of your partners and stakeholders. This team could include your utility staff (e.g., operators, supervisors, and field staff), other partners from local government (e.g., town engineer, public works staff, floodplain managers, emergency response personnel) and state government (e.g., primacy agency staff, hazard mitigation officers). It will be helpful to hold a kick-off meeting with this team to discuss goals and responsibilities to complete the assessment and implement mitigation measures. The four steps should be completed sequentially; however, they do not have to be completed all at once. Complete the steps as time and resources permit.

Flooding depends on various factors including rainfall, topography, river-flow, and drainage. The threat of flooding is based on the likelihood that such a flooding event will occur. The Federal Emergency Management Agency (FEMA) is a resource to help you. FEMA produces maps of a "100-year flood" (a flood event that has a one percent chance of occurring in a given year) and a more catastrophic "500-year flood" (a flood event that has a two tenths of a percent chance of occurring in a given year). NWRPC has also developed maps that highlight areas of concern. Maps produced by NWRPC are not to replace those created by FEMA.

### Step 1 – Understand the Threat of Flooding

To better understand the threat of flooding, your utility should first examine historical flooding data and review Federal Emergency Management Agency (FEMA) *Flood Maps*.

- Review utility records of past flooding events to come up with a description of damage to the utility. Also look at newspapers, historical data, local flood plain

- information, and talk to hazard mitigation experts to create a picture of previous floods.
- Identify which potential sources of flooding could impact your utility like flash floods, swollen rivers, spring thaw, levee/dam failure, non-natural causes (e.g., main breaks) or coastal flooding.
  - Identify which floodplains your utility system is located within and create a chart of critical equipment and where that compares to the flood plain. Floodplain maps can be viewed online at <https://msc.fema.gov/portal/home>.
  - Decide on what flooding threat your utility wants to prepare for (e.g., 100-year flood, 500-year flood)



Flood Insurance Rate Map, City of Hayward

Utility System	100-Year Floodplain (Flood Reaches Elevation (1110 ft.))	500-Year Floodplain (Flood Reaches Elevation (1113 ft.))
Intake (1108 ft.)	✓	✓
Treatment (1112 ft.)		✓
Distribution/Collection (1110 ft.)	✓	✓
Storage Tank (1120 ft.)		
Pump Stations (1112 ft.)		✓

## Step 2 – Identify Vulnerable Assets & Determine Consequences

Often located in low lying areas, water and wastewater utilities are particularly vulnerable to flooding. Water and debris can inundate the facility, thereby damaging equipment and structures and causing power outages. Such impacts can lead to various consequences including costly repairs, disruptions of services, hazardous situations for personnel, and public health advisories. In this step, identify the assets that are vulnerable to flooding and determine



the resulting consequences to those assets and to overall utility operations. Using this information and your judgment, determine the assets/operations that you will need to protect from flooding.

It is important to understand how your drinking water or wastewater utility may be impacted by flooding events so that you can identify appropriate mitigation actions to eliminate or reduce asset damage and prevent service disruptions.

To identify which key utility assets/operations are vulnerable to flooding, you should conduct an onsite inspection to locate assets and document elevations. Compare these elevations with the threat elevations in the FEMA Flood Map. The assets/operations that are vulnerable to flooding and that result in significant consequences for the utility are candidates for mitigation and protection. Below are instructions for evaluating vulnerabilities of assets and the resulting consequences at your utility.

- Measure elevations of critical utility assets to determine key operation that could be damaged from flooding.
- Evaluate the consequences based on replacement costs and the impacts to facility operations.
- Based on those the prior assessments, determine priority need for mitigation to improve flood resilience.
- Evaluated routes to and from the utility. Are they out of the danger zone and can the utility be accessed in a case of a flood?
- Conduct a wastewater utility risk assessment. Utilize the Vulnerability Self-Assessment Tool (VSAT) tool developed by USEPA. VSAT is a risk assessment application for water, wastewater, and combined utilities of all sizes. It allows utilities to assess their vulnerabilities to both man-made and natural hazards and evaluate potential improvements to enhance their security and resilience.  
<https://vsat.epa.gov/vsat/>

### Step 3 – Identify & Evaluate Mitigation Measures

First, identify possible mitigation measures that can protect the key vulnerable assets and operations prioritized in Step 2. Then, evaluate which mitigation measures make sense to pursue and implement.

To improve your utility's flood resilience, you should identify and evaluate which mitigation measures to pursue based on cost, effectiveness, and practicality. It is possible that some mitigation measures could be implemented at little to no cost to your utility. Below are instructions for evaluating mitigation measures at your utility.

- Determine your utilities minimum requirements to maintain critical services during a flood.
- Identify and evaluate what mitigation measures the utility can put in place to protect against damage.
- What is it vulnerable to? Access? Flooding to the facility and where is the water entering in? Sump pump to take water out, if it can take it out faster than it comes in.
- Short term- sand bagging. Plan how to get to and from the facility.
- Test generators weekly.
- Records retention back up at city hall or other building outside of floodplain

- Make a short-term plan and long term. Assign levels of risk and make list of minimum things that have to be done prior to a flood.

#### **Step 4 – Develop Plan to Implement Mitigation Measures**

Your utility will need to develop a plan to implement mitigation measures to reduce or eliminate asset damage and service disruptions during flooding. The plan should be revisited periodically and address actions, schedule, funding, responsibilities, etc. For example, flood mitigation measures that involve major capital and infrastructure investments should be integrated into the utility's overall scheduling in the asset management planning process (e.g., phasing in flood-resistant pumps). Now that you have selected mitigation measures, develop a plan to implement them.

- Conduct a cost benefit analysis to find identify which mitigation measures are most cost effective and critical to increasing resiliency to flooding. Build these mitigation plans into your budget. Apply to local/state/federal funding/bonds to help implement these measures.
- Create an implementation plan for the appropriate mitigation measures with specific timeframes.
- Look at age of infrastructure and figure out when things have to be replaced and implement gradual replacement program so it's not a onetime financial hit.

#### **Mitigation Measures for Drinking Water and Waste Water Assets**

It is important for drinking water and wastewater utilities to protect their buildings and other structures from floods. This includes any entryways, both obvious (e.g., doors, windows, floor drains) and not so obvious (e.g., wiring conduits, overflow drains, cracks) where water can enter structures. Significant damage can result from flood waters entering a building; water can damage or destroy the structure, process equipment, communications and controls, records and field and administrative equipment. Flood waters can also restrict access to the facility. These impacts could result in loss of service for your customers and significant repair costs for the utility. Utilities should establish emergency monitoring and warning systems (alarm systems where possible), emergency preparedness protocols and evacuation procedures for all buildings and facilities.

##### Prevent buildings from flooding.

- Caulk and/or seal wall and floor openings (e.g., windows, doors, garages)
- Install backflow prevention devices on sewers and drains.
- Install waterproof protection (e.g., removable/semi-permanent structures, sealed doors, shields) for building entry points (e.g., windows, doors, garages).
- Build floodwalls, levees or berms around the treatment plants.

##### Protect critical components if buildings do flood.

- Ensure that staff know the protocol on how and when to shut down and start up power and gas supplies, electrical controls, operating systems, and other equipment in system facilities.
- Create locations outside the flood zone where utility equipment (e.g., heavy equipment, vehicles, replacement parts, backup generators, pumps) can be stored permanently or temporarily, to prevent damage from flood waters.
- Prepare alternative routes to the treatment plant if it is blocked by floodwater or debris. Consult with other entities (e.g., Department of Transportation) to consider alternate road/transportation options (e.g., watercraft).



- Elevate or move equipment (e.g., computers, control centers, laboratories) to higher and safer ground to prevent them from being damaged.
- Always have a stock of spare parts.

Maintain operations when the electrical grid is down.

- Have a backup generator stored above the base flood elevation in case the electricity goes out.

Maintain continuity of operations during flooding.

- Regularly backup electronic and paper files that are either on-site or off-site. This should include all permits, compliance documentation, designs and as-built drawings, process diagrams, operations and maintenance records, standard operating procedures, operations data, and other vital information.
- Create a plan to operate the facility remotely if the buildings become inaccessible.
- Create interconnections or other partnership opportunities to share resources services with neighboring water utilities.

## MITIGATION OPTIONS FOR WASTEWATER TREATMENT PLANTS

Wastewater treatment plants are typically located at low elevations and near a receiving water body, which may pose a significant flood risk to a facility. Flood waters can wash out primary and secondary clarifiers, aeration tanks and chlorine contact chambers, as well as upset bioreactors. Other impacts from flood waters include damage to mechanical and electrical equipment/controls, interference with biosolids handling and disposal systems as well as washing of contaminants into the treatment train. Treatment plants that are still operational during a flood need to be prepared to accommodate higher flow rates and increased pollutant loads.

Prevent treatment plant from flooding.

- Install permanent physical barriers like levees or floodwalls to protect the entire facility from flooding.
- Integrate green infrastructure in the areas surrounding the plant to divert flood waters away.
- Install a flood water pumping system and/or channel system to divert flood waters.
- Separate combined sewers to reduce the amount of flow to the treatment plant in a flood.
- Increase the capacity of storage tanks to manage overflows for future treatment.

Protect critical components if treatment plant does flood.

- Bolt down air tanks to prevent them from floating away if flooded.
- Develop the capability to temporarily remove and safely store vulnerable components before a flood.
- Waterproof electrical components.
- Elevate or relocate individual assets, vertically extend the walls of a treatment structure (e.g., clarifier, basin, tank) above flood stage, and/or flood-proof structures to prevent the seepage of flood water.
- Buy submersible motorized and electrical equipment.
- Prepare alternative routes to the treatment plant if it is blocked by floodwater or debris.

Maintain treatment plant operations when the electrical grid is down and/or access routes are blocked.

- Increase capacity size of the chemical and fuel storage tanks.

- Install more energy efficient equipment to increase the longevity of the fuel supply for backup generators.
- Replace motorized equipment with a diesel driven or dual-option counterparts.
- Purchase backup generators or find an alternative energy supply.

Have a means of bypassing normal treatment plant operations when necessary.

- Install an external connection to the facility's compressed air system to allow a portable air compressor to be activated if the main air compressor becomes damaged.
- Establish a call list of multiple companies that can provide "pump around" services in an emergency.
- Consider starting a regionalization project to divert the flow of wastewater to an alternate system for emergency wastewater collection and conveyance.

## MITIGATION MEASURES FOR DRINKING WATER ASSETS

Flooded rivers and lakes can pose threats to source water intake structures by clogging them with excess silt/debris or by physically damaging them with debris. Flood waters that do enter the intake may carry increased contaminant loads and/or turbidity levels that may impact water treatment plant processes. Distribution system piping and appurtenances that are underground, along culverts and under bridges can be washed out by fast and high flowing flood waters. Finished water storage tanks also can be damaged by the force of flood waters. Groundwater sources also may be prone to damage. Flood waters can overtop wellheads, causing damage to the casings as well as contaminating the well water. Shallow wells near a flood zone can be contaminated even if the wellhead itself has not been overtopped. Distribution lines for groundwater sources can be equally vulnerable to flooding.

Prevent structures from flooding.

- Relocate or elevate pump houses and distribution system apparatuses that are vulnerable to flooding.

Protect critical components if intake, distribution and storage of finished water do flood.

- Protect and reinforce surface water intake pipes from debris, erosion and excessive silt. The installation of a jetty or breakwater can also keep debris/silt away from the structures. Another option is to install/upgrade the screen at the intake to prevent debris from building up.
- Waterproof, elevate or re-enforce distribution system appurtenances (i.e., fire hydrants, valve vaults) susceptible to flooding or damage from debris.
- Install submersible pumps or waterproof pump motors.
- Ensure that distribution lines across streams are sufficiently below the streambed.

Maintain delivery of safe drinking water during flooding.

- Sign up for U.S. Geological Survey (USGS) alerts for stream and river gauges: [Water Alert](#)
- Install monitoring equipment upstream of intake pipes to provide vital raw water conditions prior to a flooding event.
- Prepare alternative routes to intake structure and/or pump house if it is blocked by floodwater or debris.
- Create a plan to completely fill water storage tanks prior to a flooding event.
- Ensure that there are spare parts to repair critical equipment.
- Create interconnections or other partnership opportunities to share resources or to facilitate emergency public water supply services with neighboring water utilities.



## MITIGATION OPTIONS FOR GROUNDWATER UTILITIES

### Prevent well field/pump house from flooding.

- Procure temporary flood barriers (e.g., sandbags) for use in minor floods.
- Elevate the land directly surrounding the well field so water does not accumulate near the well. Ensure that the casing terminates at least 12 inches above ground level. Also, extend well casing above the flood zone.
- Relocate or elevate well field house pump houses to be above the flood zone.

### Protect critical components if groundwater intake and supply do flood.

- Seal the top of well casings, waterproof well caps, and extend vents above the flood zone elevation.
- Maintain the integrity of surface seals outside casings and check that there has been no soil settling or that no cavity has developed around the outside of well casings where surface water would be able to flow down to the aquifer.
- Install submersible pump or waterproof pump motors and other critical equipment.

### Maintain delivery of safe drinking water during flooding.

- Create a plan to completely fill water storage tanks prior to a flooding event.
- Prepare alternative routes to intake structure and/or pump house if it is blocked by floodwater or debris.

## MITIGATION OPTIONS FOR BOOSTER STATIONS AND OTHER PUMPS

Flood waters can severely damage pumps, thereby impacting the entire drinking water system from intake through distribution. Similarly, loss of facility power could render pumps inoperable without adequate backup power. Vulnerable water facility control systems include pump controls, variable frequency drives, electrical panels, motor control centers, and Supervisory Control and Data Acquisition (SCADA) systems.

### Prevent booster stations from flooding.

- Procure temporary flood barriers (e.g., sandbags) for use in minor floods.
- Install permanent barriers (e.g., flood walls, levees, sealed doors).

### Protect critical components if booster stations do flood.

- Develop the capabilities to temporarily remove and safely store crucial components in advance of a flooding event.
- Waterproof, relocate or elevate motor controls, variable frequency drives, computer and electrical panels.
- Shut down power to systems prior to a flood to mitigate damage to electrical components.
- Replace non-submersible pumps with submersible pumps.
- Replace standard electrical conduits with sealed, waterproof conduits.
- Installing sump pumps for below-ground facilities to provide additional time to take other mitigations measure.
- Replace below-grade booster stations with an above-grade station that is above the flood stage.

### Maintain pumping operations when the electrical grid is down.

- Store temporary or replacement pumps out of the flood zone.

- Install energy efficient utility systems to extend the fuel supply for backup generators in a flooding event.
- Replace pumps with diesel driven or dual-option counterparts.
- Weigh the option of having generators or an alternative energy supply.

Maintain pumping operations.

- Maintain a call list of multiple companies that can provide “pump around” services in an emergency.
- Stock extra portable pumps or specialized parts to repair damaged pumps. Consider having major components of specialized high capacity pumps on hand as well.

## **MITIGATION OPTIONS FOR DRINKING WATER TREATMENT PLANTS**

Flood waters may inundate a treatment facility and wash out open tanks and filter beds, damage mechanical equipment, render electrical power and controls useless, spoil finished water storage, deposit debris on-site, or wash contaminants into the treatment process. Flood waters may also alter source water chemistry and turbidity, posing treatment challenges to utilities that continue to operate during a flood. For example, residence times may need to be significantly longer following a flood to attain safe drinking water standards due to high turbidity and the potential influence of contaminants in the flood waters.

Prevent structures from flooding.

- Erect physical barriers like flood walls, levees or have the ability to deploy temporary systems that can achieve the necessary protection.
- Install green infrastructure within and/or outside of the treatment plant to attenuate, divert, or retain flood water.
- Install flood water pumping systems and/or channel/culvert systems to collect and divert flood water way from the treatment plant.

Protect critical components if the treatment plant does flood.

- Develop the capabilities to temporarily remove and safely store crucial components in advance of a flooding event.
- Waterproof electrical component (e.g., pump motors, monitoring equipment) and circuitry.
- Elevate, relocate or cap individual assets to prevent damage from flood waters; vertically extend the walls of a treatment structure (e.g., basin, tank, filter) above flood stage; and/or flood-proof/seal structures to prevent seepage of flood water into the treatment train.
- Install submersible motorized and electrical equipment.

Maintain delivery of safe drinking water during flooding.

- Closely monitor the quality of water entering the treatment plant and be able to alter the treatment process for high levels of contaminants or increased turbidity. Further, develop guidelines now and prepare for what type of adjustments would have to be made to make changes in treatment during a flood.
- Have on hand portable, handheld testing equipment in case the permanent mounted testing equipment fails due to a flooding event.
- Connect with firms or enter partnerships to share resources or to facilitate emergency public water supply services with neighboring water utilities.



Maintain operation of treatment plant if electrical grid is down.

- Install energy efficient utility systems to extend the fuel supply for backup generators in a flooding event.
- Replace pumps with diesel driven or dual-option counterparts.

Increase storage capacity in preparation for floods.

- Create a plan to completely fill water storage tanks prior to a flooding event.
- Determine if increasing the plants emergency water storage would be beneficial (as opposed to water age/quality concern).

**MITIGATION OPTIONS FOR CHEMICAL AND OTHER STORAGE**

After a flooding event, adequate supplies of chemicals and fuel are vital to maintain utility operations during the days and weeks that follow. Chemicals are needed for continued treatment of water and wastewater and fuel is needed to run equipment including emergency generators. Flooding may impact these resources in several ways. Deliveries of chemicals and fuels can be disrupted if access to the facility is restricted due to high flood waters or debris. Without necessary chemicals or fuels, utility service could be disrupted for a prolonged period of time. Storage tanks are also at risk of being damaged from a flooding event. For example, chemical or fuel tanks that are not properly secured can be carried away, damaged, or ruptured, potentially resulting in leaks and spills that may contaminate utility assets and the environment.

- Elevate or relocate tanks above base flood elevation levels or erect physical barriers or secure the tanks to the ground.
- Ensure there are larger capacity chemical storage tanks to service the plant through an emergency until the supply chain can be restored.
- Create emergency contract provisions with multiple fuel and chemical suppliers and inform them of estimated fuel/chemical needs.
- Verify fuel and chemical tanks are topped off prior to a known flooding event.
- For groundwater drawn systems, obtain or get access to a portable chlorinator.

**MITIGATION OPTIONS FOR INSTRUMENTATION AND ELECTRICAL CONTROLS**

Instrumentation, electrical controls, and electrical wiring are critical components of drinking water and wastewater treatment processes and should be protected from flood damage to prevent a potential service interruption. Motor Control Units (MCUs) may be co-located with the equipment they monitor/control or they may be located in a central control room. Typically, MCU clusters are co-located with the pumps and other equipment that they control. With some modification they can be made more resilient to flooding. Supervisory Control and Data Acquisition (SCADA) systems also may be at risk of failure during a flood. Loss of SCADA systems can impact operations and data collection in operations centers, treatment facilities, processes and remote locations in distribution and collection systems such as valve chambers and pump stations. Utilities should be able to monitor and control operations manually if instrumentation and controls are off-line due to flooding impacts.

Protect instrumentation and electrical control from flood damage.

- Elevate or relocate instruments, control centers, and motor control units.
- Ensure a cache of spare parts to restart operations as soon as possible.

- Have portable equipment available if the permanent equipment stops functioning due to flooding events.
- Waterproof or buy waterproof models of instruments and controls.
- Inform staff to shut down non-essential electrical equipment and controls prior to a flood.

Maintain continuity of operations (e.g. redundant controls at another location) if instrumentation and controls are damaged by a flood.

- Install redundant controls at another location or create remote access capabilities.
- Train staff to be able to operate the water plant manually.

## MITIGATION OPTIONS FOR POWER SUPPLY

Floods often result in power outages that have major implications for drinking water and wastewater utilities. Without a backup solution, outages can disrupt service leading to boil water advisories, sewer backups, or the discharge of raw sewage. To ensure continued service in the event of a power outage, a utility should consider a number of different strategies (e.g., backup generators, alternative/auxiliary source of power, energy efficient equipment) to run the critical components of its system keeping in mind that the minimum level of service required after a flood may differ from “normal” demands. Deciding on a strategy requires that you identify and evaluate your facility’s sources, reliability, redundancies, and critical power needs.

Long before a flood, take measures to reduce the duration of power outages.

- Establish a list of key utility facilities (e.g., intake works, pump stations) that require critical power restoration and include the physical locations of the facilities and their corresponding power company account numbers. Be sure to communicate this information with the power company during an outage to expedite electricity restoration.
- Increase the priority of power restoration to your utility’s facilities.
- Consider installing two independent power lines to your utility to avoid a complete shutdown if power is lost during a flood.
- Create a reliable connection to your power supply by installing a substation or through a dedicated feeder between the power station and the treatment plant.

Secure backup generators.

- Record the size and type of backup generator, along with the voltage, phase configuration, horsepower/ampereage, fuel, etc.
- Connect pump stations to a portable generator. Ensure that the two systems can be connected quickly when the time is needed.
- Maintain a call list of various vendors that rent portable generators and enter into an agreement to allow the sharing of backup generators during a flood event.
- Install your own portable or permanent generators that can be run on multiple fuels.

Secure a source of fuel for backup generators.

- Fill fuel storage tanks prior to a flood.
- Create an agreement with your fuel supplier and provide estimates of fuels needs in the case of a loss of power. Maintain communication with your local emergency management agencies for priority in receiving fuel supplies in an emergency.
- Have the capability for your utility’s vehicles to carry fuel tanks.
- Perform an energy audit of your facility to identify areas that could be replaced with a more energy efficient appliance.



- Purchase additional/larger fuel storage tanks.

Install an alternative energy system.

- Consider installing solar panels or wind turbines to supplement your backup power supply.
- Install cogeneration units and/or a waste heat recovery system at wastewater treatment plants to reduce or eliminate dependence on the grid.

Prepare/protect electrical connections/equipment.

- Shut down electrical equipment prior to a flood event to minimize damage.
- Create "start and connect" checklists for all critical equipment in the facility.
- Equip generators and motors with disconnect fittings that can be taken off before a flood and then restored.
- Ensure existing electrical panels have an easy and effective way of connecting to external portable generators.
- Waterproof electrical connections/motor controls/junction boxes.
- Elevate or relocate electrical vaults and service panels.

## MITIGATION OPTIONS FOR COLLECTION SYSTEM LIFT STATIONS

Lift stations are typically located at the lowest points in gravity-fed sewer systems and are therefore prone to flooding. Lift stations are also vulnerable to power outages. When lift stations lose power and do not have adequate emergency power, untreated sewage can back up into homes and businesses, flood streets, or run off into local waterways. This presents a serious threat to public health and the environment. Utilities should analyze various lift station failure scenarios (using flood stage in the flood zone for hydraulic calculations) and determine potential impacts to help inform mitigation decisions. Mitigation decisions will also depend on the type of lift station (e.g., wet or dry well), location (above or below grade), existing enclosure and ancillary equipment (e.g., minimal electrical/mechanical control equipment versus grit chambers, screens, electrical panels and other equipment).

Prevent lift stations from flooding.

- Procure temporary flood barriers (e.g., sandbags) for use in minor floods.
- Ensure that flood lines will remain over the anticipated flood stage to prevent floodwaters from entering the lift station.
- Install gates and backflow prevention devices on influent and emergency overflow lines to prevent flood waters from entering.
- Erect permanent physical barriers (e.g., flood walls or levees).
- Integrate green infrastructure in the areas surrounding the lift station to divert flood waters away.

Protect critical components if lift stations do flood.

- Install unions in the conduit system to reduce the time required to repair damaged sections.
- Install cogeneration units and/or a waste heat recovery system to reduce or eliminate dependence on the grid.
- Develop the capability to temporarily remove and safely store vulnerable components before a flood.
- Waterproof electrical components, controls, and circuitry.
- Elevate or relocate electrical components above the anticipated flood stage.
- Install submersible pumps, flow meters, and gate/valve operators.

- Elevate a below-grade lift station above the flood stage.

Maintain lift station operations when the electrical grid is down.

- Update electrical equipment to be more energy efficient.
- Replace pumps with a diesel driven or dual-option counterparts.

Have a means of bypassing normal lift station operations when necessary.

- Have on hand a call list of multiple vendors that can provide "pump around" services in a flood event.
- Ensure you have portable pumps to restore operation of the lift station if it loses power during an event.
- Consider starting a regionalization project to divert the flow of wastewater to an alternate system for emergency wastewater collection and conveyance.

## MITIGATION OPTIONS FOR HEADWORKS

The headworks includes the structures and equipment at the beginning of the wastewater treatment plant, such as gates and flow controls, metering equipment, pumps, mechanical screens, and grit removal systems. This equipment is often at a lower elevation compared to the rest of the facility, increasing its vulnerability to flooding. If the headworks is off-line due to flooding, the rest of the plant would be inoperable. A failure of the headworks without a relief or bypass may also create backwater effects on the collection system that could flood streets and basements. Utility operators should identify how a headworks failure would affect the collection system and wastewater treatment plant performance using flood water elevations in the flood zone for hydraulic calculations and then implement the appropriate mitigation measures.

Protect critical headworks components from flooding.

- Install nonelectrical backup controls where possible.
- Develop the capability to temporarily remove and safely store vulnerable components before a flood.
- Install mechanical screens that can handle higher than normal sand, grit, trash and debris loading during and after a flood event.
- Waterproof or elevate critical components to the plant (e.g., motor control units, instrumentation, electrical panels, etc.)
- Elevate, relocate or anchor pumps, screen motors, and other mechanical/electrical equipment.

Maintain headworks operation when the electrical grid is down.

- Consider installing a generator just for the headworks that is secure and has sufficient output.
- Replace pumps with a diesel driven or dual-option counterparts.